

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: <BRAHMAPUTRA CRACKER AND POLYMER LIMITD>

Name of Work: <CONSTRUCTION OF VEHICLE PARKING SHED AT
BCPL, TOWNSHIP>

Contract No: <BCPL/C&P/LE18W240SD/01051>

Name of the
Bidder/
Bidding Firm /
Company :**PRICE SCHEDULE**

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	DATE	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	GST IN % (NO NEED TO PLACE %, i.e. 2% will be only 2)	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT INCLUDING GST (Enter the GST % in GST column for each item)	TOTAL AMOUNT In Words
1	2	4	5	7	52	8	9	10
10	Roof truss Long Text: Providing fitting,hoisting and fixing of roof trusses including purlins fabricated using MS circular hollow section conforming to relevant I.S code, as per approved design and drawings including providing M.S cleats, base plates, bolts and nuts and one coat of red oxide Zinc Chromate primer and two coats of approved enamel paints complete including fitting necessary cleats etc. for fixing ceiling joists as per design and drawing as directed. TATA make Circular Hollow section-CHS of Garde YST-310 conforming to I.S Specification:1161-1998	225.000	QTL			0.00	0.00	INR Zero Only
20	Roofing sheet Long Text: Providing Pre Painted Galvanized Iron Sheet Roofing (PPGI) 0.50 mm thick at all levels including fitting and fixing with self drilling, self tapping screws complete. (Roof trusses, purlins etc. To be measured and paid separately). Dyna Roof/Wonder Roof/JSW Steel/Spectrum or equivalent as directed by the Departement	3000.000	M2			0.00	0.00	INR Zero Only

30	plain/reinforced cement concrete Long Text: Providing and laying plain/reinforced cement concrete works cement, coarse sand & 20mm down graded stone aggregate including dewatering if necessary, and curing complete but excluding cost of form work and reinforn cement for reinforced cement concrete work (form work and reinforcement will be measured and paid separatly) In substructure upto plinth level Without using admixture, plasticizer M15 grade concrete or Prop. 1:2:4	45.000	M3			0.00	0.00	INR Zero Only
40	Demolishing RCC work Long Text: Demolishing RCC work including stacking of steel bars and disposal of unserviceable material as directed for all levels.	25.000	M3			0.00	0.00	INR Zero Only
50	form work of ordinary timber planking Long Text: Providing form work of ordinary timber planking so as to give a rough finish including centering, shuttering, strutting and propping etc., height of propping and centering below supporting floor to ceiling not exceeding4.0M and removal of the same for in-situ reinforced concrete and plain concrete work in: Foundation, footings, bases of columns, pile cap, raft and mass concrete works etc.Sides of tie beams, grade beams etc. at or below ground level. Using 25mm thick plank	57.600	M2			0.00	0.00	INR Zero Only
60	primary coat over new steel Long Text: Applying primary coat over new steel and other metal surface over 100m in width or girth after preparing the surface by thoroughly cleaning oil,grease, dirt and other foreign matter and scoured with wire brushes, fine steels, wood scrapers and sand paper. With ready mixed "red-lead/ red oxide" primer.	535.04	M2			0.00	0.00	INR Zero Only
70	Painting two coats on new steel Long Text: Painting two coats (excluding priming coat) on new steel and other metal surface with enamel paint of approved brand and manufacture(Asian paint/ Berger paint/ ICI paint/J & N paint/ Nerolac) to give an even shade including cleaning the surface of all dirt, dust and other foreign matter. Surfaces over 100mm in width or girth. General purpose (Asian paint/ Berger paint/ ICI paint/ J & N paint/ Nerolac).	535.04	M2			0.00	0.00	INR Zero Only

80	Supplying, fitting and fixing reinf bars Long Text: Supplying, fitting and fixing in position reinforcement bars conforming to relevant I.S. Code for R.C.C. work/ R.B. walling including straightening, cleaning, cutting and bending to proper shapes and length as per details, supplying and binding with 20G annealed black wire and placing in position with proper blocks, supports, chairs, spacers etc. complete. (No extra measurement for lap, hook, chair, anchor etc. will be entertained in the measurement as they are included in the rate) (Upto 1st floor level) Other ISI approved TMT reinforcement bar (SAI/BISCON/THERMAX) (For Assam Type Bldg., drain works<(>,<)>retaining wall<(>,<)>boundary wall etc.	7.200	QTL			0.00	0.00	INR Zero Only
Total in Figures						0.00	0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only						