

BCPL/DIB/C&P/LE18W114MB/0665						
CONSTRUCTION OF FABRICATION YARD WITH RCC PAVEMENT AT GDU DULIAJAN UNIT						
SCHEDULE OF RATE - PRICED SOR						
SN	SAC no.	DESCRIPTION OF MATERIAL	QTY	UOM	UNIT RATE (RS)	TOTAL UNIT RATE INC TAXES & DUTIES (RS)
				Y	A	Z = (A) x (Y)
1		Earthwork in excavation for foundation trenches of walls, retaining walls, footings of column, steps, septic tank etc. including refilling (return filling) the quantity as necessary after completion of work, breaking clods in return filling, dressing, watering and ramming etc. and removal of surplus earth with all lead and lifts as directed and specified in the following classification of soils including bailing out water where necessary as directed and specified. Up to a depth of 2.00m below the existing ground level.	110	M3		
2		Plain cement concrete works with coarse aggregate of sizes 13mm to 32mm in foundation bed for footing steps, walls, brick works etc. as directed and specified including dewatering if necessary, and curing complete (shuttering where necessary shall be measured and paid separately).	1.6	M3		
3		Providing and laying plain/reinforced cement concrete works cement, coarse sand & 20mm down graded stone aggregate including dewatering if necessary, and curing complete but excluding cost of form work and reinforcement for reinforced cement concrete work (reinforcement will be measured and paid separately) (A) In substructure up to plinth level using M20 grade concrete or Prop. 1:1.5:3	50	M3		
4		Supplying, fitting and fixing in position reinforcement bars conforming to relevant I.S. Code for R.C.C. work/ R.B. walling including straightening, cleaning, cutting and bending to proper shapes and length as per details, supplying and binding with 20G annealed black wire and placing in position with proper blocks, supports, chairs, spacers etc. complete using ISI approved TMT reinforcement bar	28	QTL		
5		Steel work welded in built up sections, framed work including cutting, hoisting and fixing in positions and applying priming coat of red-lead paint including drilling holes, supplying, fitting and fixing with bolts and nuts or welding, if necessary as directed for erection of trusses and trussed purlins	145	QTL		

BCPL/DIB/C&P/LE18W114MB/0665						
CONSTRUCTION OF FABRICATION YARD WITH RCC PAVEMENT AT GDU DULIAJAN UNIT						
SCHEDULE OF RATE - PRICED SOR						
SN	SAC no.	DESCRIPTION OF MATERIAL	QTY	UOM	UNIT RATE (RS)	TOTAL UNIT RATE INC TAXES & DUTIES (RS)
6		Steel work welded in built up sections, framed work including cutting, hoisting and fixing in positions and applying priming coat of red-lead paint including drilling holes, supplying, fitting and fixing with bolts and nuts or welding, if necessary as directed In beams and joists with connecting base plates/ angled cleat etc.	6	QTL		
7		Providing corrugated galvenised Iron sheet roofing of approved brand, including fitting and fixing necessary galvenised J or L hooks, bolts and nuts 8 mm dia with bitumen washer 25 mm dia x 3 mm thick and 1.6 mm thick limpet washer complete excluding cost of roof truss, purlin etc. a) 0.50 mm thick	300	M2		
TOTAL AMOUNT IN FIGURE:						
TOTAL AMOUNT IN WORDS:						

The above rates is exlusive of GST. However, please mention the applicable GST @ _____% on all the above line items.

- i) You are requested to quote in the above standard SOR format only. Kindly do not attach any other SOR format and strictly adhere to the aforesaid format.
- ii) All other charges which are not appearing above and become applicable during execution of this PO, same shall be considered included in the quote rates.
- iii) Vendor shall maintain BCPL material code along with SAC Code in all corresponding documents for ease of identification & scrutiny.
- iv) The items quoted should be strictly as per the specifications mentioned.