



**PRICE SCHEDULE / SCHEDULE OF RATES (SOR) [PART - II - PRICED BID]
SECTION-VII**

E-TENDER NO:BCPL/C&P/LE17W142OR/00543

NAME OF WORK: CIVIL WORKS FOR EXTENSION OF NAPTHA UNLOADING HEADER AT BCPL RAILWAY SIDING AT LALMATI

Sl. No.	Activity line no.	Description of the item	Unit	Qty	SAC	Basic Unit Rate (in Rs.)		Amount (in Rs.)	
						In Figure	In Words	In Figure	In Words
(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)
1	10	Earthwork in excavation Long Text: Earthwork in excavation for foundation trenches of walls, retaining walls, footings of column, steps, septic tank etc. including refilling (return filling) the quantity as necessary after completion of work, breaking clods in return filling, dressing, watering and ramming etc. and removal of surplus earth with all lead and lifts as directed and specified in the following classification of soils including bailing out water where necessary as directed and specified.(A) Up to a depth of 2.00m below the existing ground level. All kinds of soil	M3	120					
2	20	Providing soling in foundation Long Text: Providing soling in foundation and under floor with stone/ best quality picked jhama brick, sand packed and laid to level and in panel after preparing the subgrade as directed including all labour and materials and if necessary dewatering, complete.(a).Brick on flat soling.	M2	7.715					
3	30	Plain cement concrete works Long Text: Plain cement concrete works with coarse aggregate of sizes 13mm to 32mm in foundation bed for footing steps, walls, brick works etc. as directed and specified including dewatering if necessary, and curing complete (shuttering where necessary shall be measured and paid separately). (a) In prop 1cement: 3 sand :6 coarse aggregate by volume	M3	8.420					



**PRICE SCHEDULE / SCHEDULE OF RATES (SOR) [PART - II - PRICED BID]
SECTION-VII**

E-TENDER NO:BCPL/C&P/LE17W142OR/00543

NAME OF WORK: CIVIL WORKS FOR EXTENSION OF NAPTHA UNLOADING HEADER AT BCPL RAILWAY SIDING AT LALMATI

Sl. No.	Activity line no.	Description of the item	Unit	Qty	SAC	Basic Unit Rate (in Rs.)		Amount (in Rs.)	
						In Figure	In Words	In Figure	In Words
(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)
4	40	Providing form work Long Text: Providing form work of ordinary timber planking so as to give a rough finish including centering, shuttering, strutting and propping etc., height of propping and centering below supporting floor to ceiling not exceeding 4.0M and removal of the same for in-situ reinforced concrete and plain concrete work in: Using 25 mm thick plank.	M2	400.950					
5	50	Providing and laying reinforced cement concrete Long Text: Providing and laying reinforced cement concrete works cement, coarse sand & 20mm down graded stone aggregate including dewatering if necessary, and curing complete but excluding cost of form work and reinforcement for reinforced cement concrete work (form work and reinforcement will be measured and paid separately) i) M20 grade concrete or Prop.1:1.5:3	M3	121.280					
6	60	15 mm thick cement plaster Long Text: 15 mm thick cement plaster in single coat on brick/concrete walls at all levels including arises, internal rounded angles finished even and smooth including curing complete as directed_i)In cement mortar 1:4	M2	49.500					
7	70	Half brick wall in cement mortar Long Text: Half brick wall in cement mortar including racking out joints and curing complete as directed in super structure above plinth level_i) In cement mortar 1:4	M2	22.280					



**PRICE SCHEDULE / SCHEDULE OF RATES (SOR) [PART - II - PRICED BID]
SECTION-VII**

E-TENDER NO:BCPL/C&P/LE17W142OR/00543

NAME OF WORK: CIVIL WORKS FOR EXTENSION OF NAPTHA UNLOADING HEADER AT BCPL RAILWAY SIDING AT LALMATI

Sl. No.	Activity line no.	Description of the item	Unit	Qty	SAC	Basic Unit Rate (in Rs.)		Amount (in Rs.)	
						In Figure	In Words	In Figure	In Words
(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)
8	80	Supplying, fitting & fixing in position reinforcement bars Long Text: Supplying, fitting and fixing in position reinforcement bars conforming to relevant I.S. Code for R.C.C. work/ R.B. walling including straightening, Cleaning, cutting and bending to proper shapes and length as per details, supplying and binding with 20G annealed black wires and placing in position with proper blocks, supports, chairs, spacers etc. complete. (No extra measurement for lap, hook, chair, anchor etc. will be entertained in the measurement as they are included in the rate) (Upto 1st floor level) (i)Super Ductile (SD) TMT reinforcement bars	QTL	31.100					
A		TOTAL SERVICE CHARGES exclusive of GST (Rs.)							
B		Applicable Rate of GST (%) & Type (CGST/SGST/IGST/UGST)							
C		Amount of GST (Rs.)							
D		Grand Total of Contract Value of all SOR items in Figure (Including GST) : (Sl. No. A+ Sl. No. C) (Rs.)							
E		Grand Total in words (Including GST) :							
		Signature of Authorized Representative:							



**PRICE SCHEDULE / SCHEDULE OF RATES (SOR) [PART - II - PRICED BID]
SECTION-VII**

E-TENDER NO:BCPL/C&P/LE17W142OR/00543

NAME OF WORK: CIVIL WORKS FOR EXTENSION OF NAPTHA UNLOADING HEADER AT BCPL RAILWAY SIDING AT LALMATI

Sl. No.	Activity line no.	Description of the item	Unit	Qty	SAC	Basic Unit Rate (in Rs.)		Amount (in Rs.)	
						In Figure	In Words	In Figure	In Words
(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)
		Name of authorized person submitting the tender on behalf of the Bidder(s):							
		Designation of authorized person:							
		Name of Firm / Contractor/Owner:							
		Address of Firm / Contractor/Owner:							
		Date:							
NOTE :									
1	BIDDERS ARE TO INDICATE THE UNIT RATE & AMOUNT FOR ITEMS AT SL. NO.1-8 (Activity line no. 10-80)								
2	EVALUATION SHALL BE CARRIED OUT CONSIDERING THE RATES QUOTED INCLUDING GST.								
3	Contractor is to pay its workmen the wages in line with SCC which should not be less than the minimum wages as notified by Central Govt or State Govt from time to time (whichever is higher) , evidence of which is to be submitted with monthly running bill.								
4	BIDDERS TO INDICATE THE SAC/ HSN Code (s)								