



**PRICE SCHEDULE / SCHEDULE OF RATES (SOR) [PART - II - PRICED BID]
SECTION-VIII**

E-TENDER NO: BCPL/C&P/LE17W187OR/00570

NAME OF WORK: HIRING OF SERVICES FOR CIVIL JOBS FOR LONG-TERM PROTECTION MEASURES OF 4.5" C2+ HYDROCARBON PIPELINE OF BCPL NEAR BURHIDIHING RIVER

Sl. No.	Activity line no.	Description of the item	Unit	Qty	SAC	Basic Unit Rate (in Rs.)		Amount (in Rs.)	
						In Figure	In Words	In Figure	In Words
(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)
1	10	Bored pile of 450 mm dia Long Text: Boring, providing and installing bored cast-in-situ reinforced cement concrete piles of grade M-35 of specified diameter and length below the pile cap, to carry a safe working load not less than specified, excluding the cost of steel reinforcement but including the cost of boring, with bentonite solution and temporary casing of appropriate length for setting out and removal of same and the length of the pile to be embedded in the pile cap etc. all complete, including removal of excavated earth with all lifts and leads (Length of pile for payment shall be measured upto bottom of pile cap)- 450 mm dia pile	RM	960					
2	20	6 mm MS liner for pile Long Text: Supply and providing M.S. liner for pile of 6mm thick in piles minimum 10.00 meters depth applying primer and painting outer surface etc. with approved drawing or direction of E/I including supply, strengthening, bending, welding, all supports ,labours, tools and tackles, plants and equipments etc. Complete as required for successful completion of the job as per direction of Engineer-in-charge.	TO	25					



**PRICE SCHEDULE / SCHEDULE OF RATES (SOR) [PART - II - PRICED BID]
SECTION-VIII**

E-TENDER NO: BCPL/C&P/LE17W187OR/00570

NAME OF WORK: HIRING OF SERVICES FOR CIVIL JOBS FOR LONG-TERM PROTECTION MEASURES OF 4.5" C2+ HYDROCARBON PIPELINE OF BCPL NEAR BURHIDIHING RIVER

Sl. No.	Activity line no.	Description of the item	Unit	Qty	SAC	Basic Unit Rate (in Rs.)		Amount (in Rs.)	
						In Figure	In Words	In Figure	In Words
(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)
3	30	Initial vertical test Long Text: Initial Vertical load testing of piles in accordance with IS 2911 (Part IV) including installation of loading platform and preparation of pile head or construction of test cap and dismantling of test cap after test etc. complete as per specification & the direction of Engineer - in-charge.	EA	1					
4	40	Routine test Long Text: Vertical load testing of piles in accordance with IS 2911 (Part IV) including installation of loading platform and preparation of pile head or construction of test cap and dismantling of test cap after test etc. complete as per specification & the direction of Engineer-in-charge-Routine test	EA	1					
5	50	Reinforcement work Long Text: Supplying, fitting and fixing in position reinforcement bars conforming to relevant IS code, for reinforced cement concrete works in piles including straightening, cleaning, cutting and bending to proper shapes and length as per specifications and drawings. The rings should be welded with vertical reinforcements as per specified IS codes of practice. (Inclusive of lap length, hook, chair, bend, anchor...etc)- TMT bar	TO	40					



**PRICE SCHEDULE / SCHEDULE OF RATES (SOR) [PART - II - PRICED BID]
SECTION-VIII**

E-TENDER NO: BCPL/C&P/LE17W187OR/00570

NAME OF WORK: HIRING OF SERVICES FOR CIVIL JOBS FOR LONG-TERM PROTECTION MEASURES OF 4.5" C2+ HYDROCARBON PIPELINE OF BCPL NEAR BURHIDIHING RIVER

Sl. No.	Activity line no.	Description of the item	Unit	Qty	SAC	Basic Unit Rate (in Rs.)		Amount (in Rs.)	
						In Figure	In Words	In Figure	In Words
(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)
6	60	MS bar Long Text: Supplying, fitting and fixing in position reinforcement bars conforming to relevant IS code, for reinforced cement concrete works in piles including straightening, cleaning, cutting and bending to proper shapes and length as per specifications and drawings. The rings should be welded with vertical reinforcements as per specified IS codes of practice. (Inclusive of lap length, hook, chair, bend, anchor...etc)- MS bar	TO	3					
7	70	Earth work Long Text: Earthwork in excavation for foundation trenches of walls, retaining walls, footings of column, steps, septic tank etc. including refilling (return filling) the quantity as necessary after completion of work, breaking clods in return filling, dressing, watering and ramming etc. and removal of surplus earth with all lead and lifts as directed and specified in the following classification of soils including bailing out water where necessary as directed and specified. Up to a depth of 2.00m below the existing ground level.	M3	600					



**PRICE SCHEDULE / SCHEDULE OF RATES (SOR) [PART - II - PRICED BID]
SECTION-VIII**

E-TENDER NO: BCPL/C&P/LE17W187OR/00570

NAME OF WORK: HIRING OF SERVICES FOR CIVIL JOBS FOR LONG-TERM PROTECTION MEASURES OF 4.5" C2+ HYDROCARBON PIPELINE OF BCPL NEAR BURHIDIHING RIVER

Sl. No.	Activity line no.	Description of the item	Unit	Qty	SAC	Basic Unit Rate (in Rs.)		Amount (in Rs.)	
						In Figure	In Words	In Figure	In Words
(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)
8	80	RCC M35 Long Text: Providing and laying plain/reinforced cement concrete works using cement, coarse sand & 20mm down graded stone aggregate with cost of necessary form work including dewatering if necessary, and curing for reinforced cement concrete work complete as directed (Reinforcement will be measured and paid separately)-M35	M3	3					
9	90	Steel clamp Long Text: Supplying fitting and fixing of Stainless steel clamp.	KG	1120					
10	100	Steel bolt Long Text: Supplying fitting and fixing of Stainless steel bolts	EA	80					
11	110	Str. steel work Long Text: Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	QTL	40					



**PRICE SCHEDULE / SCHEDULE OF RATES (SOR) [PART - II - PRICED BID]
SECTION-VIII**

E-TENDER NO: BCPL/C&P/LE17W187OR/00570

NAME OF WORK: HIRING OF SERVICES FOR CIVIL JOBS FOR LONG-TERM PROTECTION MEASURES OF 4.5" C2+ HYDROCARBON PIPELINE OF BCPL NEAR BURHIDIHING RIVER

Sl. No.	Activity line no.	Description of the item	Unit	Qty	SAC	Basic Unit Rate (in Rs.)		Amount (in Rs.)	
						In Figure	In Words	In Figure	In Words
(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)
12	120	Pump Long Text: Hire charges of Pump set for dewatering	DAY	30					
13	130	Temporary island Long Text: Providing and construction of temporary island to accommodate pile accessories including casting of pile cap, all complete in depth of water up to 400 cm	EA	4					
A		TOTAL SERVICE CHARGES exclusive of GST							
B		Applicable Rate of GST & Type (%)							
C		Amount of GST							
D		Grand Total of Contract Value of all SOR items in Figure (Including GST) : (Sl. No. A+ Sl. No. C)							
E		Grand Total in words (Including GST) :		(Rs.)					
		Signature of Authorized Representative:							



**PRICE SCHEDULE / SCHEDULE OF RATES (SOR) [PART - II - PRICED BID]
SECTION-VIII**

E-TENDER NO: BCPL/C&P/LE17W187OR/00570

NAME OF WORK: HIRING OF SERVICES FOR CIVIL JOBS FOR LONG-TERM PROTECTION MEASURES OF 4.5" C2+ HYDROCARBON PIPELINE OF BCPL NEAR BURHIDIHING RIVER

Sl. No.	Activity line no.	Description of the item	Unit	Qty	SAC	Basic Unit Rate (in Rs.)		Amount (in Rs.)	
						In Figure	In Words	In Figure	In Words
(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)
		Name of authorized person submitting the tender on behalf of the Bidder(s):							
		Designation of authorized person:							
		Name of Firm / Contractor/Owner:							
		Address of Firm / Contractor/Owner:							
		Date:							
NOTE :									
1	BIDDERS ARE TO INDICATE THE UNIT RATE & AMOUNT FOR ITEMS AT SL. NO.1 - 13 (Activity line no. 10-130)								
2	EVALUATION SHALL BE CARRIED OUT CONSIDERING THE RATES QUOTED INCLUDING GST.								
3	Contractor is to pay its workmen the wages in line with SCC which should not be less than the minimum wages as notified by Central Govt or State Govt from time to time (whichever is higher) , evidence of which is to be submitted with monthly running bill.								
4	BIDDERS TO INDICATE THE SAC								