

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: BRAHMAPUTRACRACKER AND POLYMER LIMITED

Name of Work: HIRING OF SERVICE CONTRACT FOR MONITORING AND MAINTENANCE OF PIPELINES AND SV STATION OF BCPL FOR A PERIOD OF A PERIOD OF 02 YEARS, FOR BCPL, LEPETKATA

Contract No: BCPL/C&P/LE20W071SD/01453

Name of the Bidder/ Bidding Firm / Company :	
--	--

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

After opening of priced bids, a comparative statement shall be generated by the system. However, this may not be the final CS depending on the situation if any further input is to be incorporated by the authority.

Sl. No.	Service Description	Quantity	Units	UNIT RATE In Figures To be entered by the Bidder in Rs. P (EXCLUSIVE OF GST)	SAC	GST IN % (NO NEED TO PLACE %, i.e. 2% will be only 2)	TOTAL AMOUNT in Rs. P (EXCLUSIVE OF GST)	TOTAL AMOUNT INCLUDING GST (Enter the GST % in GST column for each item)	TOTAL AMOUNT In Words
1	2	4	5	7	51	52	8	9	10
1	Corrosion Monitoring & CP System Monitoring and Preventive Maintenance of CPPSM/TRU -Monthly • Measurement, observation, recording and reporting of operating parameters of TR unit, alarms, feeding & draining potentials, energy meter & hour meter readings etc. • Checking of control cards, panel meters, switches, earthing connections, power supply, cable lugs, terminal plates etc. • Cleaning of TR unit, CP room and surroundings using vacuum cleaner. • An annual performance test and yearly maintenance of the TR units (Nos. of Total TRU : 17) shall be performed through the authorized service engineer as approved by EIC during the 3rd quarter of each year. No separate payment shall be made against this item. • The performance test and maintenance shall include, Performance of the unit on Auto and Manual modes, No load and Full load test, Meter Calibration, Converter module calibration, PSP Control Module Calibration, Indicator checks, Circuit resistance across Anode and Pipe, Checking of Permanent reference cell etc. and submission of final report about the health of the Unit with modifications and repairing required to be carried out.								
2	Lepetkata	312	EA				0.00	0.00	INR Zero Only
3	Duliajan	48	EA				0.00	0.00	INR Zero Only
4	Tiloi (SV-3) for 4.5" LLPL	24	EA				0.00	0.00	INR Zero Only
5	Railway Siding for 20" Naphtha Pipeline	24	EA				0.00	0.00	INR Zero Only
6	PSP Monitoring and Maintenance at TLP (Test Lead Points)- Quarterly • Measurement, observation, recording and reporting of ON and OFF Pipe to Soil Potential (PSP) carrier pipe, casing, protected & unprotected sides of insulation joint/flange, foreign pipelines, anode potential, anode current wherever anodes are installed, current readings in CJB using standard Cu/CuSO4 reference cell and data logger at all test stations. • Checking and cleaning of spark gap arrestors across IJ/IF, surge diverters etc. installed. • Checking of cable lugs, ferrules, terminal plate, nut & bolts and maintaining them in good condition and replacement of same if found faulty. • Cleaning of test stations with brush and duster cloth and lubrication of test station door hinges and locks with grease or oil. • Clearing of 20 m wide ROU strip by cutting & uprooting of trees, bushes and shrubs etc.in 2 (two) metre length on each side of TLP. • Based on the monitoring, the contractor shall give clear cut detailed recommendations establishing reason to mitigate the defects or to maintain PSP within limit. • The contractor shall check positive potential swing of 100mV or more which shall indicate presence of interference situation.								
7	18" Dia Lepetkata - Dulijan Pipeline (Twin), 48 KM long	432	EA				0.00	0.00	INR Zero Only
8	36" and 18" Dia OIL, Duliajan - BCPL, Dulijan Pipeline (Twin), 1.4 KM long	16	EA				0.00	0.00	INR Zero Only

9	4.5" Dia Lepetkata - Lakwa Pipeine, 48 KM Long	496	EA				0.00	0.00	INR Zero Only
10	24" Dia ONGC, Lakwa - BCPL,Lakwa Pipeine(Twin), 2.3 KM Long	112	EA				0.00	0.00	INR Zero Only
11	24" Dia Raw Water Pipeline (Lepetkata - Burhiding River Intake point, 6.2 KM Long)	112	EA				0.00	0.00	INR Zero Only
12	28" Dia Effluent Treated Pipeline (Lepetkata - Diffuser Point in Brahmaputra River, 17.5 KM Long)	160	EA				0.00	0.00	INR Zero Only
13	20" Dia Naphtha Pipeline (Lepetkata - Railway Siding, 5.2 KM Long)	72	EA				0.00	0.00	INR Zero Only
14	BCPL Plant Premises , Lepetkata for fire water pipeline and cooling water pipeline	1376	EA				0.00	0.00	INR Zero Only
15	AJB Monitoring & Maintenance - Half Yearly / # Yearly • Measurement, observation, recording and reporting of current discharge of each anode and adjusting resistor settings accordingly to make current discharge of all anodes equal. • Measurement of earth resistance of each anode and total bed using Wenner 3 pin method using Digital Earth Resistance Measuring Device. • Checking of shunts, resistors, cables lugs, ferrols, terminal plate, nut & bolts, AJB door hinges, locks etc and maintaining in good condition. • Changing of all rusted/faulty shunts, resistors, cables lugs, ferrols, terminal plate, nut & bolts, AJB door hinges, locks etc								
16	Lepetkata	12	EA				0.00	0.00	INR Zero Only
17	Duliajan	4	EA				0.00	0.00	INR Zero Only
18	Tiloi (SV-3) for 4.5" LLPL	4	EA				0.00	0.00	INR Zero Only
19	Railway Siding for 20" Naphtha Pipeline	4	EA				0.00	0.00	INR Zero Only
20	# Cooling Water Pipeline and Fire water line Lepetkata	102	EA				0.00	0.00	INR Zero Only
21	Monitoring and Maintenance of ER Probe - HALF YEARLY Data retrieval tool to be maintained/arranged by the party, Down Load the Data of the ER Probe and submit the report with analysis.								
22	18" Dia Rich Gas Pipeline at Lepetkata	4	EA				0.00	0.00	INR Zero Only
23	18" Dia Lean Gas Pipeline at Duliajan	4	EA				0.00	0.00	INR Zero Only
24	4.5" Dia C2 + Liquid HydrocarbonPipeine at Lepetkata	4	EA				0.00	0.00	INR Zero Only
25	28" Dia Effluent Treated Pipeline (Lepetkata - Diffuser Point in Brahmaputra River, 17.5 KM Long)	4	EA				0.00	0.00	INR Zero Only
26	20" Dia Naphtha Pipeline (Lepetkata - Railway Siding, 6 KM Long)	4	EA				0.00	0.00	INR Zero Only
27	Monitoring and Maintenance of CTSU - HALF YEARLY								
28	18" Dia Lepetkata - Dulijan Pipeline (Twin), 48 KM long	4	EA				0.00	0.00	INR Zero Only
29	4.5" Dia Lepetkata - Lakwa Pipeine, 48 KM Long	4	EA				0.00	0.00	INR Zero Only
30	24" Dia Raw Water Pipeline (Lepetkata - Burhiding River Intake point, 6.2 KM Long)	4	EA				0.00	0.00	INR Zero Only
31	28" Dia Effluent Treated Pipeline (Lepetkata - Diffuser Point in Brahmaputra River, 17.5 KM Long)	4	EA				0.00	0.00	INR Zero Only

32	20" Dia Naphtha Pipeline (Lepetkata - Railway Siding, 6 KM Long)	4	EA				0.00	0.00	INR Zero Only
33	Supply & Installation of TLP Supply, installation, testing and commissioning of new test station, includes providing foundation, applying painting one coat (75 micron) of high build epoxy primer and two coats (50 microns each) of high build epoxy enamel paint, other accessories, cable gland lugs, conduits as required to make the installation complete as per specification, drawing and instruction of Engineer - In - Charge to complete the work in all respect for all pipelines of BCPL in Dibrugarh and Sivasagar Districts along the pipeline ROU.								
34	Complete TLP with New Foundation: This will included shifting cable from old TS (Test Station) to New TS to Complete the work in all respect	50	EA				0.00	0.00	INR Zero Only
35	TLP Post & Box on Existing Foundation: On existing foundation, this will included removing of old TS box & Post, and fixing new TS box with terminal plate & Post re-termination of Cables to Complete the work in all respect	15	EA				0.00	0.00	INR Zero Only
36	TLP Box: Only Test Station Box with terminal plate. This will include removing of old TS box, and fixing new TS box, re-termination of cables to complete the work in all respect.	5	EA				0.00	0.00	INR Zero Only
37	Painting of TLP/AJB/CJB/CPPSM/TRU etc.								
38	This includes Surface preparation using metal wire brush, sand paper, removing dust,grease, scales, cleaning with lint free cloth, applying painting one coat (75 micron) of high build epoxy primer and two coats (50 microns each) of high build epoxy enamel paint incluig supply of all weather Paint of Asian, Burger, Shalimar, Jonson & Nicolson or EIC Approved brand, metal brush, sand paper, all tools and tackels as per direction of EIC to complete the work in all respect.	200	EA				0.00	0.00	INR Zero Only
39	Supply & Laying of Diff Size of Cables Supply, cutting to right sizes, laying, testing and commissioning of different sizes of cables (PE Sheathed, PVC Insulated GI armoured, copper cables , annealed, high conductivity, stranded, tinned,600/1100 V grade), including making connection in both end, including supply of cable gland, lugs etc. (Except cable to pipe connection) excavation, sand padding of 150 mm below and above cable, laying of bricks above sand, laying of cable warning PE sheet at 0.6 meter depth , backfilling , supply and installation of cable markers at every 50 meter etc., as per drawing specification and instruction of EIC to complete the job in all respect.								
40	1CX25MM2 Cu PE PVC Armoured	200	M				0.00	0.00	INR Zero Only
41	1CX10MM2 Cu PE PVC Armoured	200	M				0.00	0.00	INR Zero Only
42	1CX6MM2 Cu PE PVC Armoured	200	M				0.00	0.00	INR Zero Only
43	1 C X 4MM2 Cu PVC Armoured	200	M				0.00	0.00	INR Zero Only
44	1C X 50MM2 Cu PVC Armoured	100	M				0.00	0.00	INR Zero Only
45	Supply, Installation of Solid Cu/CuSO4 State Permanent Ref Cell Supply, installation, testing and commissioning of Solid State Cu-CuSO4 Permanent Reference Cells with min. 10meter lead cable, as per drawing, specification, and direction of Engineer- In-Charge. Work includes excavation of trench, backfilling and connection of cable etc. as per drawing specification.	30	EA				0.00	0.00	INR Zero Only

46	Making Pipe to Cable Connection Making pipe to cable connection on running pipe as per approved procedures (including encapsulation of pipe to cable connection), drawing, specification and direction of Engineer-In –Charge, including supply of consumable, process material, excavation for exposing pipe, backfilling, etc. for satisfactory completion of work. The work shall also be include holiday checking with Brush type Holiday Detector, CAD welding/ Pin Brazing operation at 20 KV as per drawing specification and instruction of EIC to complete the job in all respect.								
47	1C Upto 10 mm2 cable	50	EA				0.00	0.00	INR Zero Only
48	1C from 25-50 mm2 cable	10	EA				0.00	0.00	INR Zero Only
49	Supply & Installation of Zn Anode / Zinc Grounding cell Supply, Installation, Testing, Commissioning of pre-package Zn Grounding cell of 22KG , complete in all respects including labor, tools tackles and consumables etc. along with required length of 25 mm2 single core stranded tined copper cable PE Sheathed / PVC Insulated cable as tale cable, as per drawing specification and direction of EIC to complete the job in all respect.	3	EA				0.00	0.00	INR Zero Only
50	Supply & Installation of Mg Anode Supply, Installation, Testing, Commissioning of pre-package Mg Anode as per weight desired, complete in all respects including labor , tools tackles and consumables etc. along with required length of tale cable (Approx. 10 meter) of 10 mm2 single core stranded tined copper 600 / 1100 V grade Un-Armoured cable PE Sheathed / PVC Insulated cable as tale cable, as per drawing specification and direction of EIC to complete the job in all respect.								
51	02.50 Kg	10	EA				0.00	0.00	INR Zero Only
52	05.00 Kg	15	EA				0.00	0.00	INR Zero Only
53	07.50 Kg	20	EA				0.00	0.00	INR Zero Only
54	10.00 Kg	5	EA				0.00	0.00	INR Zero Only
55	Data Logging along PL for 24 Hrs Data logging along the pipeline as per requirement for 24 Hrs. including arrangement of data logger, Half Cell, technician labor tools & tackles and consumables, as per direction of EIC to complete the job in all respect.	5	EA				0.00	0.00	INR Zero Only
56	Excavation & Backfilling along the Pipeline Excavation & backfilling along the pipeline for Inspection of pipeline Coating or any other purpose in all types soils, hard murum shoring, strutting & dewatering (if necessary) as per direction of E.I.C to complete the job in all respect.	100	M3				0.00	0.00	INR Zero Only
57	Providing Manpower for CP Activity Providing Manpower for different type of CP activities / Pipeline related activities etc.								
58	Skilled Man Power	30	D				0.00	0.00	INR Zero Only
59	Semi Skilled Man Power	30	D				0.00	0.00	INR Zero Only
60	Un-Skilled Man Power	50	D				0.00	0.00	INR Zero Only
61	Monitoring and Maintenance of Battery Banks in SV Stations -Monthly Monitoring and Maintenance of Battery Banks in SV Stations includes the Cleaning of Battery Terminals, topping up battery cell by DM Water, recording of the Cell Voltage & Specific Gravity. All material consumable tools including Hydrometer, DM Water etc in the scope of Contractor. Quality of DM water is to be supported by lab test report.								
62	18" Dia Lepetkata - Dulijan Pipeline (Twin), 48 KM long	48	EA				0.00	0.00	INR Zero Only

63	4.5" Dia Lepetkata - Lakwa Pipeine, 48 KM Long	96	EA				0.00	0.00	INR Zero Only
64	Electrical Maintenance Jobs at 6 SV Stations - Monthly basis Maintenance job of overall Electrical system for pipeline including SV Stations - testing, rectification and replacement of defect exhaust fans, light fitting & fixtures (both indoor & outdoor), JBs which includes electrical wiring where ever required both for power & lighting points. Upkeep and maintenance of UPS, Battery charger etc - Cable jointing of differencnt sizes if any,- Up keep & maintenance of Power Lines (HT/LT lines), PDB & LDB, JBs , Split AC, Tube light, Led Bulbs, etc. The details are in the scope of work or as per EIC direction to complete the job in all respect.	24	EA				0.00	0.00	INR Zero Only
65	ROU WASHOUT RESTORATION WORKS:								
66	Earth filling from brought out earth (excluding rock) in trenches, open pits, over pipeline trenches etc. as per scope of work.	100	M3				0.00	0.00	INR Zero Only
67	Providing and laying in position empty HDPE cement bags filled with cement sand in the ration 1:10 (1 cement:10 coarse sand) as per scope of work.	400	EA				0.00	0.00	INR Zero Only
68	Providing and laying in position earth filled HDPE cement bags as per scope of work	500	EA				0.00	0.00	INR Zero Only
69	Random rubble masonry with hard stone in foundation / Superstructure in cement mortar 1:6 (1 cement: 6 coarse sand) as per scope of work.	50	M3				0.00	0.00	INR Zero Only
70	MISCELLANEOUS ROU /SV MAINTAINENACE WORK: Clearing of 20 m wide ROU strip by cutting & uprooting of trees, bushes and shrubs etc. in running length as per scope of work.	2000	M				0.00	0.00	INR Zero Only
71	FORMATION OF BUNDS FOR WASHOUT REPAIR AS PER SITE CONDITIONS & SCOPE OF WORK.								
72	Earth work in foundation trenches not exceeding 1.5 m in width or 10 sqm on plan all kind of soil as per scope of work.	50	M3				0.00	0.00	INR Zero Only
73	Providing and placing in position Cement Concrete: 1: 4: 8.as directed by EIC. Detail as per scope of work.	25	M3				0.00	0.00	INR Zero Only
74	Pumping out of water caused by rains, broken water mains/drains etc. as per scope of work.	50	H				0.00	0.00	INR Zero Only
75	PIPELINE REPAIRING/MODIFICATION WORK at various locations/terminals as per scope of work for BCPL Pipelines.								
76	Repair of Pipeline leakages/dent within 06-08 hrs of Terminal shutdown as per scope of work.	50	ID				0.00	0.00	INR Zero Only

77	Repair of Pipeline leakages/dent without terminal shutdown during normal operation as per scope of works.	30	ID				0.00	0.00	INR Zero Only
78	Supply of nitrogen gas cylinders(55kg,150bar,7 cubic mtr.) as per scope of work.	20	EA				0.00	0.00	INR Zero Only
79	LOCATING OF BCPL PIPELINE AS PER SCOPE OF WORK. LOCATING OF BCPL PIPELINE with pipeline locator and by person with manual digging at various locations along pipelines with maximum length not exceeding 50mtr. in each case, as per scope of work.	25	EA				0.00	0.00	INR Zero Only
80	COATING REPAIR OF UNDERGROUND PIPELINE AS PER SCOPE OF WORK.								
81	Coating repair using Cold Applied tapes. Detail as per scope of work.	50	M2				0.00	0.00	INR Zero Only
82	Coating repair using Denso tape as per scope of work.	50	M2				0.00	0.00	INR Zero Only
83	Monitoring of Earth Pits - Half Yearly • Measurement, observation, recording and reporting of earth resistance of earth pit and grid using Wenner 3 pin method using Digital Earth Resistance Measuring Device. • Numbering the Earth Pit and writing the next due date on the cover of Earth Pit with Paint. • Removing debris if any in the earth pit and watering. • Physical & functional checking of all Earth pits, associated cables/connections. • Cleaning of all connections and greasing them with replacement of brass nut, bolts if found damaged or missing. Jointing of earth cable if found open circuited, disconnected / damaged. • Proper cleaning & house-keeping inside & surrounding of the earth pit.								
84	18" Dia Lepetkata - Dulijan Pipeline (Twin), 47 KM long	100	EA				0.00	0.00	INR Zero Only
85	4.5" Dia Lepetkata - Lakwa Pipeline, 47 KM Long	180	EA				0.00	0.00	INR Zero Only
86	24" Dia Raw Water Pipeline (Lepetkata - Burhiding River Intake point, 6.2 KM Long)	8	EA				0.00	0.00	INR Zero Only
87	28" Dia Effluent Treated Pipeline (Lepetkata - Diffuser Point in Brahmaputra River, 17.5 KM Long)	8	EA				0.00	0.00	INR Zero Only
88	20" Dia Naphtha Pipeline (Lepetkata - Railway Siding, 6 KM Long)	16	EA				0.00	0.00	INR Zero Only
89	Maintenance of Earth Pits Pouring of common salt (appx 25 kg, water (appx 200 liters) & soil reactivation compound (appx. 10 kg) or as per requirement to bring down the earth resistance within limit including raising the heights of civil foundation , repair of cement plastering and all other activities cover monitoring of Earth pit.All consumables, materials required for the above said jobs will be in contractor's scope.	20	EA				0.00	0.00	INR Zero Only

90	Supply, Installation, Testing of GI Pipe Earthing Station GI Pipe Earthing Station: Supply, assembling, installing, testing and commissioning with all the items for constructing GI earthing pipe size 75 mmX 5 mm thick (minimum 4.5 mtr.deep) GI funnel with stainless steel hinged door on steel frame(300X300mm) to cover up the watering pit, minimum 50 Kg salt, minimum 100kgs of fine charcoal powder, earthing conductor size 25mm X 3mm GI flat from pipe to the ground level, required hardware and miscellaneous item. The work involves digging pit on the soil, burying the earth electrodes in the mixture of common salt and charcoal, connecting earthing conductor to earthing electrode, backfilling the soil and constructing the watering pit with brick peripheri, preparing the earth-pit chamber or any cosumables required to complete the job will be in contractors scope, at the site as specified and details as per the direction of EIC.	6	EA				0.00	0.00	INR Zero Only
91	Supply & Laying of GI pipe 100mm NB Supply and laying og GI pipes "B" class of following sizes in required length fixed on steel, concrete or similar structure, above ground, or laid in trenches, ready to be buried in concrete, including cutting, threading, bending and similar works, supply of clamps, small iron structures, spacers and installation of seats, plugs, bushings etc. small civil works, including all manpower, materials and tools as per approved drawings, specifications of the tender and directions of EIC. 100mm NB	150	M				0.00	0.00	INR Zero Only
92	Supply, Installation , Connection of 25X3 mm GI Earth Strip Supply, installation and connection of following GI earth strip along the ready cable trenches os cable trays or fixing on walls or structures including welding at joints, providing anti-corrosive paint or bitumen and jute covering for welded portion, clamping and all necessary hardware for connecting etc., including all labour and tools, as per approved drawings, specifications of this tender and directions of Engineer-in-Charge. 25X3 mm	100	M				0.00	0.00	INR Zero Only
93	Supply and installation of explosion proof spark gap/ Surge arrestor Supply and installation of explosion proof spark gap/ Surge arrestor of DEHN ExSG4/ equivalent make across insulating joint for BCPL including required cable 25 Sq. mm CU. Bugs, nuts, bolts, labour, tools & tackles and consumables	8	EA				0.00	0.00	INR Zero Only
94	TR unit spare parts / Mandatory spare of Raychem Make / equivalent								
95	Panel Meter (AC/DC) (230V-415V / 0V-50V, PSP)	25	EA				0.00	0.00	INR Zero Only
96	Control Card RRL-103A	5	EA				0.00	0.00	INR Zero Only
97	Control Card RRL-104C1	5	EA				0.00	0.00	INR Zero Only

98	Control Card RRL-105D1	5	EA				0.00	0.00	INR Zero Only
99	Control Card RRL-106	5	EA				0.00	0.00	INR Zero Only
100	Mother Board RRL-MB01	1	EA				0.00	0.00	INR Zero Only
101	Lighting Arrestor	3	EA				0.00	0.00	INR Zero Only
102	Supply of Rubber Mat as per direction Scope of Work.	10	Mtr				0.00	0.00	INR Zero Only
103	Supply, Installation, Testing, Commissioning of pre-package Zn grounding cell Supply, Installation, Testing, Commissioning of pre-packaged Zn grounding cell of 22KG, complete in all respect including labour, tools tackles and consumables etc. along with required length of 25mm2 single core stranded tined copper cable PE Sheathed/ PVC insulated cable as tale cable, as per drawing specification and direction of EIC to complete the job in all respect.	3	EA				0.00	0.00	INR Zero Only
104	Cable joint/ reapiing of underground cable Cable jointing/ repairing of underground cable as per approved procedure including excavation and back filling cable jointing by cable jointing kit (Raychem/equivalent) Termination and identification of cable. Supply of cable jointing kit and other consumables, labour, tools and tackles, copper sleeves, heat sink, ferrule etc. for 4mm sq., 6 sq. mm, 10mm sq., 25 sq. mm & 50 sq.mm. XLPE armoured copper cable as per scope of work, specification and direction of EIC	30	EA				0.00	0.00	INR Zero Only
105	Repainting & relettering of existing various types of markers as per scope of work								
106	Warning Marker	100	EA				0.00	0.00	INR Zero Only
107	Direction Marker	50	EA				0.00	0.00	INR Zero Only
108	Kilometer Marker	100	EA				0.00	0.00	INR Zero Only
109	Aerial Marker	50	EA				0.00	0.00	INR Zero Only
110	Boundary Pillar	100	EA				0.00	0.00	INR Zero Only

111	Supply & Installation of various types of markers at designated location/Chainage as per scope of work.								
112	Warning Marker	50	EA				0.00	0.00	INR Zero Only
113	Direction Marker	50	EA				0.00	0.00	INR Zero Only
114	Kilometer Marker	50	EA				0.00	0.00	INR Zero Only
115	Aerial Marker	20	EA				0.00	0.00	INR Zero Only
116	Boundary Pillar	100	EA				0.00	0.00	INR Zero Only
117	- DG Trial Run, Routine check and correction if required in 6 Nos. SV Stations - Actual run of DG set (30KVA) on monthly basis on existing maximum load of each 6 nos. of SV stations located at six different locations for 1 hr. which also includes checking of overall health of DG set for smooth running of DG set as and when required.	144	Nos				0.00	0.00	INR Zero Only
118	- Supply of diesel (as required) - Supply of diesel as and when required.	720	L				0.00	0.00	INR Zero Only
119	- C-check maintenance as per OEM recommendation details as below: - Checking of air cleaner / replacement (if required) - Cleaning of fuel tank / draining sediments / filter replacement (if required) - Checking of coolant level / top up / replacement (if required) - Cleaning of Radiator - Checking of fan hub - Checking of alternator / starter - Checking of fuel pump / calibrate (if required) - Checking of all parameters indicators and replacement of faulty display if required. 1 hour actual run of DG set on full load.	6	Nos				0.00	0.00	INR Zero Only
120	- Supply of consumables required for C-check for one 30KVA DG set details as below: - Coolant as per OEM - Air filter as per OEM - Lube oil Filter as per OEM - Lube oil as per OEM - Gear oil as per OEM - Fuel filter as per OEM - connecting tube if required etc.	6	Nos				0.00	0.00	INR Zero Only
Total in Figures							0.00	0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only							