



1. ALL DIMENSIONS ARE IN MM.
2. WIDTH OF RACKS ON ONE SIDE OR BOTH SIDES SHALL BE DECIDED AS PER JOB REQUIREMENT.
3. THE EXACT HEIGHT OF OPENING IN TRENCH WALL FOR G.I. PIPE FOR TAKING CABLE SHALL BE SUITABLY DECIDED AT SITE.
4. THE REMOVABLE CONCRETE COVERS SHALL BE SEALED WITH MASTIC ASPHALT FILLER / BITUMEN TO PREVENT INGRESS OF WATER / HYDROCARBONS IN CABLE TRENCH.
5. TOP OF THE TRENCH SHALL BE 100 MM ABOVE FINISHED GRADE LEVEL (F.G.L.) IN CASE OF UNPAVED AREAS AND SHALL BE FLUSHED WITH FINISHED FLOOR LEVEL (F.F.L.) IN CASE OF PAVED AREAS.
6. MINIMUM GAP OF 250MM SHALL BE PROVIDED BETWEEN FA / COMMUNICATION / TELEPHONE CABLES AND ALL OTHER POWER / CONTROL CABLES.

Copyright EIL - All rights reserved