



**PRICE SCHEDULE / SCHEDULE OF RATES (SOR) [PART - II - PRICED BID]
SECTION-VIII**

E-TENDER NO: BCPL/C&P/LA17W155OR/00521

NAME OF WORK: SUPPLY & INSTALLATION OF FALSE FLOORING SYSTEM AT BCPL PLANT, LAKWA

Sl. No.	Activity line no.	Description of the item	Unit	Qty	SAC	Basic Unit Rate (in Rs.)		Amount (in Rs.)	
						In Figure	In Words	In Figure	In Words
(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)
1	10	False flooring panels Long Text: Providing and installing/fixing in position up to 600mm high truly levelled and aligned cavity/false/access flooring system of UNITILE/UNIFLOOR MAKE having load bearing capacity of distributed load of minimum 1080kg/sq.m and point load of 360Kg., the system consisting of Removable and re-usable floor panels of size 600mmx600mm made of all steel welded construction(cleaned, degreased and phosphated with 11 tank process, finished with 40-60 micron epoxy coating(and heated to achieve adhesion to the panel surface and corrosion resistance) with bottom surface consisting of multiple hemispherical cones and top plain sheet(fuse welded at 144 locations) to form an enclosed panel.	sqm	210					



**PRICE SCHEDULE / SCHEDULE OF RATES (SOR) [PART - II - PRICED BID]
SECTION-VIII**

E-TENDER NO: BCPL/C&P/LA17W155OR/00521

NAME OF WORK: SUPPLY & INSTALLATION OF FALSE FLOORING SYSTEM AT BCPL PLANT, LAKWA

Sl. No.	Activity line no.	Description of the item	Unit	Qty	SAC	Basic Unit Rate (in Rs.)		Amount (in Rs.)	
						In Figure	In Words	In Figure	In Words
(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)
		The inner empty core of the panel injected with light weight fire retardent, non-combustible cementitious compound(at high pressure to fill all crevices of the panel), each panel is then finished with floor grade antistatic high pressure laminate/PVC on a semi-automated lamination line to ensure maximum bonding to the steel surface. The edges of the finished panels provided with conducive PVC edge trim 5mm wide on all sides(mechanically locked and sealed in place) to avoid detachment: False flooring panels with 2mm thick fire retardant floor grade high pressure laminate conforming to BS:476 part-7 on a semi-automated lamination line in approved design/shade/texture.							
2	20	Sub-structure/pedestal assembly Long Text: Providing and installing/fixing in position up to 600mm high truly levelled and aligned cavity/false/access flooring system of UNITILE/UNIFLOOR MAKE having load bearing capacity of distributed load of minimum 1080kg/sq.m and point load of 360Kg., the system consisting of Sub-structure/pedestal assembly(designed for speedy assembly/removal for relocation/maintenance) of zinc electroplated steel comprising of :-	sqm	210					



**PRICE SCHEDULE / SCHEDULE OF RATES (SOR) [PART - II - PRICED BID]
SECTION-VIII**

E-TENDER NO: BCPL/C&P/LA17W155OR/00521

NAME OF WORK: SUPPLY & INSTALLATION OF FALSE FLOORING SYSTEM AT BCPL PLANT, LAKWA

Sl. No.	Activity line no.	Description of the item	Unit	Qty	SAC	Basic Unit Rate (in Rs.)		Amount (in Rs.)	
						In Figure	In Words	In Figure	In Words
(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)
		a. 75mmx75mmx3.5mm pedestal head attachment mechanically riveted to a 100mm long, minimum 19mm dia roll-formed stud with 2 check nuts for level adjustment(for upto 25mm) and arresting vertical movement, anti-vibrational conductive cap with inbuilt isolating spacers for panel and stringer location, b. Pedestal stud consisting of minimum 20mm dia(OD) pipe of minimum 1.5mm thickness mechanically locked to maintain true plumb welded to pedestal base plate, c. Pedestal base plate 100mmx100mmxminimum 2mm thick with stiffening folds fixed/anchored to main concrete floor by means of adhesive or fastener as recommended by manufacturer. Stringers of minimum sectional size 21mmx29mmx0.8mm made of hot dip galvanised steel cold rolled construction with ribs embossed on 3 sides (designed for strength, lateral stability, rolling loads and to support panels on all four sides for alignment), having counter sunk holes at both ends for fixing to pedestal head assembly with M6 machine screws.							

E-TENDER NO: BCPL/C&P/LA17W155OR/00521

Sl. No.	Activity line no.	Description of the item	Unit	Qty	SAC	Basic Unit Rate (in Rs.)		Amount (in Rs.)	
						In Figure	In Words	In Figure	In Words
(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)
		The item includes: i) Complete dismantling of existing false flooring components including stacking at specified locations. ii) Providing & fixing all accessories like screws, bolts, adhesive etc. as per manufacturer's specifications ii) Making necessary adjustment in grid dimensions, stringer lengths, floor panel dimensions etc. at ends or centre (to cater to specific room sizes) or at panel locations as required. iii) Cutting of floor panels as required iv) Providing additional supports/pedestal assembly at edges, cutouts etc. as required v) Providing necessary wiring/arrangement etc. for antistatic PVC type floor finish as required etc. all complete.							
A		TOTAL SERVICE CHARGES exclusive of GST							
B		Applicable Rate of GST & Type (%)							
C		Amount of GST							
D		Grand Total of Contract Value of all SOR items in Figure (Including GST) : (Sl. No. A+ Sl. No. C)							

E-TENDER NO: BCPL/C&P/LA17W155OR/00521

Sl. No.	Activity line no.	Description of the item	Unit	Qty	SAC	Basic Unit Rate (in Rs.)		Amount (in Rs.)	
						In Figure	In Words	In Figure	In Words
(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)
E		Grand Total in words (Including GST) :		(Rs.)					
		Signature of Authorized Representative:							
		Name of authorized person submitting the tender on behalf of the Bidder(s):							
		Designation of authorized person:							
		Name of Firm / Contractor/Owner:							
		Address of Firm / Contractor/Owner:							
		Date:							

1	BIDDERS ARE TO INDICATE THE UNIT RATE & AMOUNT FOR ITEMS AT SL. NO.1 - 2 (Activity line no. 10-20)
2	EVALUATION SHALL BE CARRIED OUT CONSIDERING THE RATES QUOTED INCLUDING GST.
3	Contractor is to pay its workmen the wages in line with SCC which should not be less than the minimum wages as notified by Central Govt or State Govt from time to time (whichever is higher) , evidence of which is to be submitted with monthly running bill.
4	BIDDERS TO INDICATE THE SAC