



SPEC. FOR HEALTH, SAFETY AND
ENVIRONMENT MANAGEMENT, SAFETY
MEASURES FOR ELECTRICAL
INSTALLATIONS DURING
CONSTRUCTION

[ANNEXURE-X TO SPECIAL CONDITIONS OF CONTRACT]

निर्माण स्थल पर स्वास्थ्य, सुरक्षा एवं पर्यावरण प्रबंधन मानक विनिर्देशन

STANDARD SPECIFICATION FOR HEALTH, SAFETY & ENVIRONMENT (HSE) MANAGEMENT AT CONSTRUCTION SITES

4	13/02/2008	REVISED & UPDATED				
			AS	RK	SCB	VC
3	17/07/2007	REVISED & UPDATED	AS	MPJ	VNP	VC
2	11/08/2005	REVISED & UPDATED	MPJ	MPJ	VNP	VJN
1	29/05/2003	REVISED & UPDATED	AS	MPJ	HOD(C)	SKG
0	19/07/2002	ISSUED AS STANDARD SPECIFICATION	AB	MPJ	HOD(C)	GRR
Rev. No	Date	Purpose	Prepared by	Checked by	Standards Committee Convenor	Standards Bureau Chairman
					Approved by	

Abbreviations:

AERB	:	Atomic Energy Regulatory Board
ANSI	:	American National Standards Institute
BARC	:	Bhabha Atomic Research Centre
BS	:	British Standard
EIL	:	Engineers India Limited
ELCB	:	Earth Leakage Circuit Breaker
EPC	:	Engineering, Procurement and Construction
EPCC	:	Engineering, Procurement, Construction and Commissioning
ESI	:	Employee State Insurance
GCC	:	General Conditions of Contract
GM	:	General Manager
GTAW	:	Gas Tungsten Arc Welding
HOD	:	Head of Department
HSE	:	Health, Safety & Environment
HV	:	High Voltage
IS	:	Indian Standard
IE	:	Indian Electricity
LPG	:	Liquefied Petroleum Gas
LSTK	:	Lump Sum Turn Key
MV	:	Medium Voltage
PPE	:	Personal Protective Equipment
RCM	:	Resident Construction Manager or Site-in-Charge, as applicable
ROW	:	Right of Way
SCC	:	Special Conditions of Contract
SLI	:	Safe Load Indicator
TBM	:	Tool Box Meeting

Construction Standards Committee

Convenor : Sh. S.C. Barman, HOD (Construction)

Members : Sh. A.K. Mittal, DGM (Projects)
Sh. M.P. Jain, AGM (Projects)
Sh. R. Kannan, AGM (Construction)
Sh. Rakesh Nanda, AGM (Piping)

CONTENTS

CLAUSE	TITLE	PAGE NO.
1.0	Scope	5
2.0	References	5
3.0	Requirement of Health, Safety and Environment (HSE) Management System to be complied by Bidders	
3.1	Management Responsibility	5
3.1.1	HSE Policy & Objective	5
3.1.2	Management System	5
3.1.3	Indemnification	5
3.1.4	Deployment & Qualification of Safety Personnel	5
3.1.5	Implementation & Monitoring	6
3.1.6	Awareness	6
3.1.7	Fire prevention & First-Aid	7
3.1.8	Documentation	7
3.1.9	Audit	7
3.1.10	Meetings	7
3.1.11	Intoxicating drinks & drugs and smoking	7
3.1.12	Penalty	8
3.1.13	Accident/Incident investigation	10
3.2	House Keeping	10
3.3	HSE Measures	11
3.3.1	Construction Hazards	11
3.3.2	Accessibility	11
3.3.3	Personal Protective Equipments (PPEs)	11
3.3.4	Working at height	11
3.3.5	Scaffoldings	12
3.3.6	Electrical installations	13
3.3.7	Welding/Gas cutting	15
3.3.8	Ergonomics and tools & tackles	15
3.3.9	Occupational Health	15
3.3.10	Hazardous substances	16
3.3.11	Slips, trips & falls	16
3.3.12	Radiation exposure	16
3.3.13	Explosives/Blasting operations	17
3.3.14	Demolition/Dismantling	17
3.3.15	Road Safety	17
3.3.16	Welfare measures	17

Contd to page 4 ...

CONTENTS (contd from page 3)

3.3.17	Environment Protection	17
3.3.18	Rules & Regulations	18
3.3.19	Weather Protection	18
3.3.20	Communication	18
3.3.21	Confined Space Entry	18
3.3.22	Heavy Lifts	19
3.3.23	Key performance indicators	19
3.3.24	Unsuitable Land Conditions	19
3.3.25	Under Water Inspection	19
3.4	Tool Box Meeting	19
3.5	Training & Induction Programme	20
3.6	Inspection	20
3.7	Additional safety requirements for working Inside a running plant	20
3.8	Self Assessment and Enhancement	22
3.9	HSE Promotion	22
4.0	Details of HSE Management System by Contractor	
4.1	On Award of Contract	22
4.2	During Job Execution	22
4.3	During short listing of the sub-contractors	23
5.0	Records	23

Appendices

1	Standards/Codes on HSE	Appendix-A	24
2	Details of First AID Box	Appendix-B	26
3	Types of Fire Extinguishers & their Appln.	Appendix-C	27
4	Indicative List of statutory Acts & Rules	Appendix-D	28
5	Construction Hazards and their mitigation	Appendix-E	29

Attachments (Reporting Formats)

I.	HSE Checklist cum Compliance Report	HSE-1 Rev.0	41
II.	Accident/Incident Report	HSE-2 Rev.0	47
III.	Suppl. Accident/Incident Investigation Report	HSE-3 Rev.0	48
IV.	Near Miss Incident Report	HSE-4 Rev.0	49
V.	Monthly HSE Report	HSE-5 Rev.0	50
VI.	Permit for Working at height	HSE-6 Rev.0	51
VII.	Permit for Working in Confined Space	HSE-7 Rev.0	53
VIII.	Permit for Radiation work	HSE-8 Rev.0	54
IX.	Permit for Demolishing/ Dismantling	HSE-9 Rev.0	55

1.0 SCOPE

This specification establishes the Health, Safety and Environment (HSE) management requirement to be complied by Contractors including their sub-contractors during construction.

This specification is not intended to replace the necessary professional judgement needed to design & implement an effective HSE system for construction activities and the contractor is expected to exceed requirements given in this specification.

Requirements stipulated in this specification shall supplement the requirements of HSE Management given in relevant Act(s)/legislations, General Conditions of Contract (GCC), Special Conditions of Contract (SCC) and Job (Technical) Specifications. Where different documents stipulate different requirements, the most stringent shall apply.

2.0 REFERENCES

The document should be read in conjunction with following:

- General Conditions of Contract (GCC)
- Special Conditions of Contract (SCC)
- Building and other construction workers (regulation of employment and condition of service) Act, 1996
- Job (Technical) specifications
- Relevant International/ National Codes (refer Appendix-A for standards/codes on HSE)
- Statutory requirements

3.0 REQUIREMENTS OF HEALTH, SAFETY & ENVIRONMENT (HSE) MANAGEMENT SYSTEM TO BE COMPLIED BY BIDDERS

3.1 MANAGEMENT RESPONSIBILITY

3.1.1 HSE Policy & Objectives

The Contractor should have a documented HSE policy & objectives to demonstrate commitment of their organization to ensure health, safety and environment aspects in their line of operations.

3.1.2 Management System

The HSE management system of the Contractor shall cover the HSE requirements including but not limited to what is specified under clause 1.0 and 2.0 above.

3.1.3 Indemnification

Contractor shall indemnify & hold harmless, Owner/EIL & their representatives, free from any and all liabilities arising out of non-fulfillment of HSE requirements.

3.1.4 Deployment & qualifications of safety personnel

Contractor shall designate/ deploy all the categories of HSE personnel at site as indicated below:

- a) Safety Steward

One for every 500 workers or part thereof. He/She shall possess minimum one year of experience in construction work environment.

b) **Safety Supervisor**

One for every 1000 workers or part thereof. He/She shall possess minimum two years of work experience in construction work environment.

c) **Safety Officer**

One for every 1000 workers or part thereof. He/She shall possess a recognized Degree in any branch of engineering or technology or architecture and had a post qualification construction experience of minimum two years or possess a recognized Diploma in any branch of engineering or technology and had a post qualification construction experience of minimum five years.

In addition, he/she shall also possess a recognized degree or diploma in industrial safety and preferably have adequate knowledge of the language spoken by majority of the workers at the construction site.

In case the statutory requirements i.e. Centre or State Acts and/ or Rules as applicable like the Building and Other Construction Workers -Regulation of Employment and Conditions of Service- Act or Rules wherever notified, the Factories Act or Rules wherever notified, etc. are more stringent than above, the same shall be followed.

The Contractor shall ensure physical presence of safety personnel at each work location where Hot work permit is required. No work shall be started at site until above safety personnel are physically present at site. The contractor shall submit a safety organogram clearly indicating the lines of responsibility and reporting system and elaborate the responsibilities of safety personnel in the HSE Manual/Programme. The contractor shall furnish Bio-Data/ Resume/ Curriculum Vitae of the safety personnel as above, at least 1 month before the mobilization, for EIL/Owner's approval.

3.1.5 Implementation & Monitoring

Contractor shall be fully responsible for planning, reporting, implementing and monitoring all HSE requirements and compliance of all laws & statutory requirements. The Contractor shall also ensure that the HSE requirements are clearly understood & faithfully implemented at all levels at site.

3.1.6 Awareness

The contractor shall brief the visitors about the HSE precautions which are required to be taken before proceeding to site and make necessary arrangements to issue appropriate PPEs like hard hats & safety shoes to his visitors.

The Contractor shall promote and develop consciousness about Health, Safety and Environment among all personnel working for the Contractor. Regular awareness programmes and fabrication shop/work site meetings atleast on monthly basis shall be arranged on HSE activities to cover hazards involved in various operations during construction. During the awareness programme, steps shall be taken by the contractor to motivate & encourage the workmen & supervisory staff by issuing/ awarding them with the tokens/ gifts/ mementos/ monetary incentives.

A verbal warning shall be given to the worker during the first HSE violation. A written warning shall be issued on the second violation and thereafter for the third violation; the services of the worker shall be terminated. For all these violations, penalties shall be imposed separately on the contractor. A record of warnings for each worker shall be maintained by the contractor like by punching their cards.

3.1.7 Fire prevention & First-Aid

The contractor shall arrange suitable first aid measures such as First Aid Box (Refer Appendix-B for details), trained personnel to administer First Aid, stand-by ambulance or vehicle and install fire protection measures such as adequate number of steel buckets with sand & water and adequate number of appropriate fire extinguishers (Refer Appendix-C for details) to the satisfaction of EIL/Owner. The contractor's safety personnel shall be trained enough to carry out above activities effectively so as to provide immediate relief in case of an emergency.

In case the number of workers exceeds 500, the Contractor shall position an ambulance/ vehicle on full time basis very close to the worksite.

3.1.8 Documentation

The Contractor shall evolve a comprehensive, planned and documented system for implementation and monitoring of the HSE requirements. This shall be submitted to EIL/Owner for approval. The monitoring for implementation shall be done by regular inspections and compliance to the observations thereof. The Contractor shall get similar HSE requirements implemented at his sub-contractor(s) work site/office. However, compliance of HSE requirements shall be the responsibility of the Contractor. Any review/approval by EIL/Owner shall not absolve contractor of his responsibility/liability in relation to all HSE requirements.

3.1.9 Audit

Contractor shall carry out internal HSE audits. He shall also cooperate during HSE audits by Owner/ EIL. Non-Conformances on HSE (including his sub-contractors) brought out during review/audit by his internal audit team as well as EIL/Owner's representative shall be resolved forthwith by Contractor. Compliance report shall be submitted to EIL/Owner promptly.

To this effect, the contractor shall submit an Audit Plan to EIL/Owner indicating the type of audits (internal by self including his sub-contractors, external by EIL/Owner & Third Party) and their frequencies. The contractor shall conduct an internal HSE audit atleast on quarterly basis and submit a report to EIL/Owner.

3.1.10 Meetings

The Contractor shall ensure participation of his top most executive at site (viz. Resident Engineer/ Site-in-Charge) in Safety Committee/HSE Committee meetings arranged by EIL/Owner usually on monthly basis or as and when called for. The compliance of any observations during the meeting shall be arranged urgently. The contractor shall assist EIL/Owner to achieve the targets set by them on HSE during the project implementation.

In addition, the contractor shall also arrange internal HSE meetings chaired by his top most executive at site on weekly basis and maintain records.

3.1.11 Intoxicating drinks & drugs and Smoking

The contractor shall ensure that his staff members & workers (permanent as well casual) shall not be in a state of intoxication during working hours and shall abide by any law relating to consumption & possession of intoxicating drinks or drugs in force. Awareness about local laws on this issue shall form part of the Induction Training.

The contractor shall ensure that all personnel working for him comply with No-smoking requirements of the owner as notified from time to time. Cigarettes, lighters, auto ignition tools or appliances shall not be allowed inside the plant complex. Smoking shall be permitted only inside smoking booths expressly designated & authorized by the Owner/EIL.

3.1.12 Penalty

The Contractor shall adhere consistently to all provisions of HSE requirements. In case of non-compliance or repeated failure in implementation of any of the HSE provisions; EIL/Owner may impose stoppage of work without any cost & time implication to the Owner and/or impose a suitable penalty.

The amount of penalty to be levied shall be upto a cumulative limit of

- 1.0% (one percent) of the contract value for Item Rate or Composite contracts with an overall ceiling of Rs. 10,00,000/- (Rupees ten lakhs).
- 0.2% (Zero decimal two percent) of the contract value for LSTK, EPC, EPCC or Package contracts with an overall ceiling of Rs.1,00,00,000/- (Rupees one crore).

This penalty shall be in addition to all other penalties specified elsewhere in the contract. The decision of imposing stop-work-instruction and imposition of penalty shall rest with EIL/Owner. The same shall be binding on the contractor. Imposition of penalty does not make the contractor eligible to continue the work in unsafe manner.

The amount of penalty applicable on different types of HSE violations is specified below:

S. No.	Violation of HSE norms	Penalty Amount
1.	For not using personal protective equipment (Helmet, Shoes, Goggles, Gloves, Full body harness, Face shield, Boiler suit, etc.)	Rs.250/- per day/Item/ Person.
2.	Working without Work Permit/Clearance	Rs.5,000/- per occasion
3.	Unsafe electrical practices (not installing ELCB, using poor joints of cables, using naked wire without top plug into socket, laying wire/cables on the roads, electrical jobs by incompetent person, etc.)	Rs.3,000/- per item per day.
4.	Working at height without full body harness, using non-standard/ rejected scaffolding and not arranging fall protection arrangement as required like Safety Nets.	Rs. 3,000/ per case per day.
5.	Unsafe handling of compressed gas cylinders (No trolley, jubilee clips double gauge regulator, improper storage/handling).	Rs.100/- per item per day.
6.	Use of domestic LPG for cutting purpose.	Rs.1,000 per occasion.
7.	No fencing/barricading of excavated areas.	Rs.1,000 per occasion.

8.	Not providing shoring/strutting/proper slope and not keeping the excavated earth at least 1.5M away from excavated area.	Rs.5,000/- per occasion.
9.	Non display of caution boards, list of hospitals, emergency services available at work locations.	Rs.500/- per occasion.
10.	Traffic rules violations like over speeding of vehicles, rash driving, wrong parking, not using seat belts, vehicles not fitted with reverse warning alarms.	Rs.1,000/- per occasion.
11.	Absence of Contractor's top most executive at site in the safety meetings whenever called by EIL/Owner	Rs. 5,000/- per meeting.
12.	Failure to maintain safety records by Contractor Safety personnel.	Rs.1,000/- per month.
13.	Failure to conduct daily safety site inspection, HSE meeting and HSE audit at predefined frequencies	Rs.1,000/- per occasion.
14.	Failure to submit the monthly HSE report by 5 th of subsequent month to Engineer-in-Charge.	Rs.5,000/- per occasion and Rs.100/- per day for further delay.
15.	Poor House Keeping	Rs.1,000/- per occasion
16.	Failure to report & follow up accident (including Near Miss) reporting system.	Rs.10,000/- per occasion
17.	Degradation of environment (not confining toxic spills, spilling oil/lubricants onto ground)	Rs.1,000/- per occasion
18.	Not medically examining the workers before allowing them to work at height, not providing ear muffs while allowing them to work in noise polluted areas, made them to work in air polluted areas without respiratory protective devices, etc.	Rs.1,000/- per occasion
19.	Violation of any other safety condition as per job HSE plan, work permit and HSE conditions of contract (using crowbar on cable trenches, improper welding booth, not keeping fire extinguisher ready at hot work site, unsafe rigging practices, non-availability of First-Aid box, etc.)	Rs.1,000/- per occasion
20.	Any violation not covered above	To be decided by EIL/Owner.

3.1.13 Accident/ Incident investigation

All accidents/incidents shall be reported immediately on Format No. HSE-2. Thereafter, a supplementary Accident/Incident investigation report on Format No. HSE-3 shall be submitted. Near Miss incident(s) shall also be reported on Format No. HSE-4. The accidents/incidents shall be investigated by a team of Contractor's senior personnel for establishing root cause and recommending corrective & preventive actions. Findings shall be documented and suitable actions taken to avoid recurrences shall be communicated to EIL/Owner. Owner/EIL shall have the liberty to independently investigate such occurrences and the Contractor shall extend all necessary help and cooperation in this regard. EIL/Owner shall have the right to share the content of this report with the outside world.

3.2 HOUSE KEEPING

Contractor shall ensure that a high degree of house keeping is maintained and shall ensure interalia; the followings:

- a. All surplus earth and debris are removed/disposed off from the working areas to designated location(s).
- b. Unused/surplus cables, steel items and steel scrap lying scattered at different places within the working areas are removed to identified location(s).
- c. All wooden scrap, empty wooden cable drums and other combustible packing materials, shall be removed from work place to identified location(s).
- d. Roads shall be kept clear and materials like pipes, steel, sand, boulders, concrete, chips and bricks etc shall not be allowed on the roads to obstruct free movement of men & machineries.
- e. Fabricated steel structural, pipes & piping materials shall be stacked properly for erection.
- f. Water logging on roads shall not be allowed.
- g. No parking of trucks/trolleys, cranes and trailers etc shall be allowed on roads, which may obstruct the traffic movement.
- h. Utmost care shall be taken to ensure over all cleanliness and proper upkeep of the working areas.
- i. Trucks carrying sand, earth and pulverized materials etc. shall be covered while moving within the plant area/ or these materials shall be transported with top surface wet.
- j. The contractor shall ensure that the atmosphere in plant area and on roads is free from particulate matter like dust, sand, etc. by keeping the top surface wet for ease in breathing.
- k. At least two exits for any unit area shall be assured at all times.

3.3 HSE MEASURES

3.3.1 Construction Hazards

Contractor shall ensure identification of all Occupational Health, Safety & Environmental hazards in the type of work he is going to undertake and enlist mitigation measures. Contractor shall carry out Job Safety Analysis (JSA) specifically for high risk jobs like working at height & in confined space, deep excavations, radiography jobs, electrical installations, blasting operations, demolishing/ dismantling activities, welding/ gas cutting jobs and submit the findings to EIL/Owner. The necessary HSE measures devised shall be in place prior to start of an activity by the contractor.

A list of typical construction hazards alongwith their effects & preventive measures is given in Appendix-E.

3.3.2 Accessibility

The Contractor shall provide safe means of access to any working place including provisions of suitable and sufficient scaffolding at various stages during all operations of the work for the safety of his workmen and EIL/Owner.

The access to plant complex shall be strictly regulated. Any person or vehicle entering the complex shall undergo identification check, as per the procedures in force.

3.3.3 Personal Protective Equipments (PPEs)

The Contractor shall ensure that all their staff, workers and visitors including their sub-contractor(s) have been issued (records to be kept) & wear appropriate PPEs like nape strap type safety helmets preferably with head & sweat band with ¾" cotton chin strap (made of industrial HDPE), safety shoes with steel toe cap and antiskid sole, full body harness (CE marked and conforming to EN361), protective goggles, gloves, ear muffs, respiratory protective devices, etc. All these gadgets shall conform to applicable IS Specifications/CE or other applicable international standards.

Owner may issue a comprehensive color scheme for helmets to be used by various agencies. The Contractor shall follow the scheme issued by the owner. All Safety/ Fire personnel shall preferably wear red colour helmet so that workmen can approach them for guidance during emergencies.

For shot blasting, the usage of protective face shield and helmets, gauntlet and protective clothing is mandatory.

For offshore jobs/contracts, contractor shall provide PPEs (new) to EIL & Owner's personnel, at his (contractor's) cost. All personnel shall wear life jacket at all time.

An indicative list of HSE standards/codes is given under Appendix-A.

3.3.4 Working at height

The contractor shall issue height permit for working at height after verifying and certifying the checkpoints as specified in the attached permit (Format No. HSE-6). He shall also undertake to ensure compliance to the conditions of the permit during the currency of the permit including adherence to personal protective equipments.

The permit shall be issued initially for one week or expected duration of an activity and extended further for the balance duration. This permit shall be applicable in areas where specific clearance from Owner's operation Deptt./Safety Deptt. is not required. EIL field Engineers/Safety Officers/Area Coordinators may verify and counter sign this permit (as an evidence of verification) during the execution of the job.

In case work is undertaken without taking sufficient precautions as given in the permit, EIL Engineers may cancel the permit and stop the work till satisfactory compliance is arranged. Contractors are expected to maintain a register for issuance of permit and extensions thereof including preserving the used permits for verification during audits etc.

Contractor shall arrange (at his cost) and ensure use of Fall Arrester Systems by his workers. Fall arresters are to be used while climbing/descending tall structures. These arresters should lock automatically against the anchorage line, restricting free fall of the user. The device is to be provided with a double security opening system to ensure safe attachment or release of the user at any point of rope. In order to avoid shock, the system should be capable of keeping the person in vertical position in case of a fall.

Contractor shall ensure that Full body harnesses conforming EN361 and having authorized CE marking is used by all personnel while working at height. The lanyards and life lines should have enough tensile strength to take the load of the worker in case of a fall. One end of the lanyard shall be firmly tied with the harnesses and the other end with life line. The harness should be capable of keeping the workman vertical in case of a fall, enabling him to rescue himself.

Contractor shall provide Roof Top Walk Ladders for carrying out activities on sloping roofs in order to reduce the chances of slippages and falls.

Contractor shall ensure that a proper Safety Net System is used wherever the hazard of fall from height is present. The safety net, preferably a knotted one with mesh ropes conforming to IS 5175/ ISO 1140 shall have a border rope & tie cord of minimum 12mm dia. The Safety Net shall be located not more than 6.0 meters below the working surface extending on either side upto sufficient margin to arrest fall of persons working at different heights.

Contractor shall ensure positive isolation while working at different levels like in the pipe rack areas. The working platforms with toe boards & hand rails shall have sufficient space to hold the workmen and the tools & the tackles including the equipments required for executing the job.

3.3.5 Scaffoldings & Barricading

Suitable scaffoldings shall be provided to workmen for all works that cannot be safely done from the ground or from solid construction except such short period work that can be safely done using ladders. When a ladder is used, an extra workman shall be engaged for holding the ladder.

The contractor shall ensure that the scaffolds used during construction activities shall be strong enough to take the designed load. Owner/EIL reserves the right to ask the contractor to submit certification and or design calculations from his Engineering regarding load carrying capacity of the scaffoldings.

All scaffolds shall be inspected by a Scaffolding Inspector of the contractor. He shall paste a GREEN tag on each scaffold found safe and a RED tag on each scaffold found unsafe. Scaffoldings with GREEN tag only shall be permitted to be used and RED ones shall immediately be removed from the site.

The contractor shall ensure positive barricading of the excavated, radiography, heavy lift, high pressure hydrostatic & pneumatic testing and other such areas. Sufficient warning signs shall be displayed along the barricading areas.

3.3.6 Electrical installations

All electrical installations/ connections shall be carried out as per the provisions of latest revision of following codes/standards, in addition to the requirements of Statutory Authorities and IE/applicable international rules & regulations:

- OISD STD 173 : Fire prevention & protection system for electrical installations
- SP 30 (BIS) : National Electric Code

All electrical installations shall be approved by the concerned statutory authorities.

3.3.6.1 The contractor shall meet the following requirements:

- i) Ensure that electrical systems and equipment including tools & tackles used during construction phase are properly selected, installed, used and maintained as per provisions of the latest revision of the Indian Electrical/ applicable international regulations.
- ii) Shall deploy qualified & licensed electricians for proper & safe installation and for regular inspection of construction power distribution system/points including their earthing. A copy of the license shall be submitted to EIL / Owner for records. Availability of at least one competent licensed electrician shall be ensured at site round the clock to attend to the normal/emergency jobs.
- iii) All switchboards / welding machines shall be kept in well-ventilated & covered shed. The shed shall be elevated to avoid water logging. No flammable materials shall be used for constructing the shed. Also flammable materials shall not be stored in and around electrical equipment / switchboard. Adequate clearances and operational space shall be provided around the equipment.
- iv) Fire extinguishers and insulating mats shall be provided in all power distribution centers.
- v) Temporary electrical equipment shall not be employed in hazardous area without obtaining safety permit.
- vi) Proper house keeping shall be done around the electrical installations.
- vii) All temporary installations shall be tested before energising, to ensure proper earthing, bonding, suitability of protection system, adequacy of feeders/cables etc.
- viii) All welders shall use hand gloves irrespective of holder voltage.
- ix) Multilingual (Hindi, English and local language) caution boards, shock treatment charts and instruction plate containing location of isolation point for incoming supply, name & telephone No. of contact person in emergency shall be provided in substations and near all distribution boards / local panels.
- x) Operation of earth leakage device shall be checked regularly by temporarily connecting series test lamp (2 bulbs of equal rating connected in series) between phase and earth.
- xi) Regular inspection of all installations (at least once in a month)

3.3.6.2 The following features shall also be ensured for all electrical installations during construction phase by the contractor:

- i) Each installation shall have a main switch with a protective device, installed in an enclosure adjacent to the metering point. The operating height of the main switch shall not exceed 1.5 M. The main switch shall be connected to the point of supply by means of armoured cable.
- ii) The outgoing feeders shall be double or triple pole switches with fuses / MCBs. Loads in a three phase circuit shall be balanced as far as possible and load on neutral should not exceed 20% of load in the phase.
- iii) The installation shall be adequately protected against overload, short circuit and earth leakage by the use of suitable protective devices. Fuses wherever used shall be HRC type. Use of rewirable fuses shall be strictly prohibited. The earth leakage device shall have an operating current not exceeding 30 mA.
- iv) All connections to the hand tools / welding receptacles shall be taken through proper switches, sockets and plugs.
- v) All single phase sockets shall be minimum 3 pin type only. All unused sockets shall be provided with socket caps.
- vi) Only 3 core (P+N+E) overall sheathed flexible cables with minimum conductor size of 1.5 mm² copper shall be used for all single phase hand tools.
- vii) Only metallic distribution boxes with double earthing shall be used at site. No wooden boxes shall be used.
- viii) All power cables shall be terminated with compression type cable glands. Tinned copper lugs shall be used for multistrand wires / cables.
- ix) Cables shall be free from any insulation damage.
- x) Minimum depth of cable trench shall be 750 mm for MV & control cables and 900 mm for HV cables. These cables shall be laid over a sand layer and covered with sand, brick & soil for ensuring mechanical protection. Cables shall not be laid in waterlogged area as far as practicable. Cable route markers shall be provided at every 25 M of buried trench route. When laid above ground, cables shall be properly cleated or supported on rigid poles of atleast 2 M high. Minimum head clearance of 6 meters shall be provided at road crossings.
- xi) Under ground road crossings for cables shall be avoided to the extent feasible. In any case no under ground power cable shall be allowed to cross the roads without pipe sleeve.
- xii) All cable joints shall be done with proper jointing kit. No taped/ temporary joints shall be used.
- xiii) An independent earthing facility should preferably be established within the temporary installation premises. All appliances and equipment shall be adequately earthed. In case of armoured cables, the armour shall be bonded to the earthing system.
- xiv) All cables and wire rope used for earth connections shall be terminated through tinned copper lugs.

- xv) In case of local earthing, earth electrodes shall be buried near the supply point and earth continuity wire shall be connected to local earth plate for further distribution to various appliances. All insulated wires for earth connection shall have insulation of green colour.
- xvi) Separate core shall be provided for neutral. Earth / Structures shall not be used as a neutral in any case.
- xvii) ON/OFF position of all switches shall be clearly designated / painted for easy isolation in emergency.

3.3.7 Welding/ Gas cutting

Contractor shall ensure that flash back arrestors conforming to BS:6158 or equivalent are installed on all gas cylinders as well as at the torch end of the gas hose, while in use. All cylinders shall be mounted on trolleys and provided with a closing key. The burner and the hose placed downstream of pressure reducer shall be equipped with Flash Back Arrester/Non Return Valve device. The hoses for acetylene and oxygen cylinders must be of different colours. Their connections to cylinders and burners shall be made with a safety collar. At end of work, the cylinders in use shall be closed and hoses depressurized. All welding machines shall have effective earthing. In order to help maintain good housekeeping, and to reduce fire hazard, live electrode bits shall be contained safely and shall not be thrown directly on the ground.

3.3.8 Ergonomics and tools & tackles

The Contractor shall assign to his workmen, tasks commensurate with their qualification, experience and state of health. All lifting tools, tackles, equipment, accessories including cranes shall be tested periodically by statutory/competent authority for their condition and load carrying capacity. Valid test & fitness certificates from the applicable authority shall be submitted to Owner/EIL for their review/acceptance before the lifting tools, tackles, equipment, accessories and cranes are used. The contractor shall not be allowed to use defective equipment or tools not adhering to safety norms.

Contractor shall ensure installation of Safe Load Indicator (SLI) on all cranes (while in use) to minimize overloading risk. SLI shall have capability to continuously monitor and display the load on the hook, and automatically compare it with the rated crane capacity at the operating condition of the crane. The system shall also provide visual and audible warnings at set capacity levels to alert the operator in case of violations.

The contractor shall be responsible for safe operations of different equipments mobilized and used by him at the workplace like transport vehicles, engines, cranes, mobile ladders, scaffoldings, work tools, etc.

3.3.9 Occupational Health

The contractor shall identify all operations that can adversely affect the health of its workers and issue & implement mitigation measures.

For surface cleaning operations, sand blasting shall not be permitted even if not explicitly stated elsewhere in the contract.

To eliminate radiation hazard, Tungsten electrodes used for Gas Tungsten Arc Welding shall not contain Thorium.

Appropriate respiratory protective devices shall be used to protect workmen from inhalation of air borne contaminants like silica, asbestos, gases, fumes, etc.

Workmen shall be made aware of correct methods for lifting, carrying, pushing & pulling of heavy loads. Wherever possible, manual handling shall be replaced by mechanical lifting equipments.

For jobs like drilling/demolishing/dismantling where noise pollution exceeds the specified limit of 85 decibels, ear muffs shall be provided to the workers.

To avoid upper limb disorders and backaches, Display Screen Equipments' workplace stations shall be carefully designed & used with proper sitting postures. Power driven hand-held tools shall be maintained in good working condition to minimize their vibrating effects and personnel using these tools shall be taught how to operate them safely & how to maintain good circulation in hands.

The contractor shall arrange health check up for all the workers at the time of induction. Health check may have to be repeated if the nature of duty assigned to him is changed necessitating health check or doubt arises about his wellness. EIL/Owner reserve the right to ask the contractor to submit test reports. Regular health check-ups are mandatory for the workers assigned with Welding, Radiography, Blasting, Heavy Lift and Height (>2m) jobs. All the health check-ups shall be conducted by registered Medical practitioner and records are to be maintained.

The contractor shall ensure vaccination of all the workers including their families.

3.3.10 Hazardous substances

Hazardous, inflammable and/or toxic materials such as solvent coating, thinners, anti-termite solutions, water proofing materials shall be stored in appropriate containers preferably with lids having spillage catchment trays and shall be stored in a good ventilated area. These containers shall be labeled with the name of the materials highlighting the hazards associated with its use and necessary precautions to be taken.

Where contact or exposure of hazardous materials exceeds the specified limit or otherwise have harmful affects, appropriate personal protective equipments such as gloves, goggles, aprons, chemical resistant clothing, respirator, etc. shall be used.

The work place shall be checked prior to start of activities to identify the location, type and condition of any asbestos materials which could be disturbed during the work. In case asbestos material is detected, usage of appropriate PPEs by all personnel shall be ensured and the matter shall be reported immediately to EIL/ Owner.

3.3.11 Slips, trips & falls

The contractor shall establish a regular cleaning and basic housekeeping programme that covers all aspects of the workplace to help minimize the risk of slips, trips & falls. The contractor shall take positive measures like keeping the work area tidy, storing waste in suitable containers & harmful items separately, keeping passages, stairways, entrances & exits especially emergency ones clear, cleaning up spillages immediately and replacing damaged carpet/ floor tiles, mats & rugs at once to avoid slips, trips & falls.

3.3.12 Radiation exposure

- a) All personnel exposed to physical agents such as non-ionizing radiation, ultraviolet rays or similar other physical agents shall be provided with adequate shielding or protection commensurate with the type of exposure involved.

- b) For ionizing radiation, requirements of Bhabha Atomic Research Centre (BARC)/ Atomic Energy Regulatory Board (AERB) shall be followed.

3.3.13 Explosives/Blasting operations

Blasting operations shall be carried out as per latest Explosive Rules (Indian/ International) with prior permission. The contractor shall obtain license from Controller of explosives for collection, transportation, storage of explosives as well as for carrying out blasting operations.

3.3.14 Demolition/ Dismantling

The contractor shall adhere to safe demolishing/ dismantling practices at all stages of work to guard against unsafe working practices. The contractor shall disconnect service lines (power, gas supply, water, etc.)/ make alternate arrangements prior to start of work and restore them, if required as directed by EIL/ Owner at no extra cost. Before carrying out any demolition/ dismantling work, the contractor shall take prior approval of EIL/Owner in Format No.HSE-9. For revamp jobs in operating plants where location of underground utilities is not known with certainty, the contractor shall depute an experienced person for supervision and shall make adequate arrangements for Fire fighting & First-Aid during the execution of these activities.

3.3.15 Road Safety

The contractor shall ensure adequately planned road transport safety management system. The vehicles shall be fitted with reverse warning alarms & flashing lights and usage of seat belts shall be ensured. The contractor shall also ensure a separate pedestrian route for safety of the workers and comply with all traffic rules & regulations. The maximum allowable speed shall be adhered to. In case of an alert or emergency, the vehicles must clear all the routes, roads, access.

Dumpers, Tippers, etc. shall not be allowed to carry workers within the plant area and also to & from the labour colony. Hydras shall only be allowed for handling the materials at fabrication/ storage yards and in no case shall be allowed to transport the materials.

For pipeline jobs, the contractor shall submit a comprehensive plan covering transportation of pipes, movement of side booms, movement of vehicles on the ROW, etc.

3.3.16 Welfare measures

Contractor shall, at the minimum, ensure the following facilities at work sites.

- A crèche at site where 10 or more female workers are having children below the age of 6 years.
- Reasonable canteen facilities at site and in labour camps at appropriate location depending upon site conditions.
- Adequately lighted & ventilated Rest rooms at site (separate for male workers and female workers)
- Toilets, drinking water, adequate lighting at site and labour camps, commensurate with applicable Laws/ Legislation

3.3.17 Environment Protection

Contractor shall ensure proper storage and utilization methodology of materials that are detrimental to the environment. Where required, Contractor shall ensure that only the environment friendly materials are selected and emphasize on recycling of waste materials

such as metals, plastics, glass, paper, oil & solvents. The waste that can not be minimized, reused or recovered shall be stored and disposed of safely. In no way, toxic spills shall be allowed to percolate into the ground. The contractor shall not use the empty areas for dumping the wastes.

The contractor shall strive to conserve energy and water wherever feasible.

The contractor shall ensure dust free environment at workplace by sprinkling water on the ground at frequent intervals. The air quality parameters for dust, poisonous gases, toxic releases, harmful radiations, etc. shall be checked by the contractor on daily basis and whenever need arises.

The contractor shall not be allowed to discharge chemicals, oil, silt, sewage, sullage and other waste materials directly into the controlled waters like surface drains, streams, rivers, ponds. A discharge plan suggesting the methods of treating the waste before discharging shall be submitted to EIL/Owner for approval.

For pipeline jobs, top soil shall be stacked separately while making ROW through fields. This fertile soil shall be placed back on top after backfilling.

For offshore construction barges, arrangements shall be made for safe disposal of human, food & other wastes and applicable laws in this regard shall be followed.

3.3.18 Rules & Regulations

All persons deployed at site shall be knowledgeable of and comply with the environmental laws, rules & regulations relating to the hazardous materials, substances and wastes. Contractor shall not dump, release or otherwise discharge or dispose off any such materials without the express authorization of EIL/Owner. An indicative list of Statutory Acts & Rules relating to HSE is given under Appendix-D.

3.3.19 Weather Protection

Contractor shall take appropriate measures to protect workers from severe storms, solar radiations, poisonous gases, dust, etc. by ensuring proper usage of PPEs like Sun glasses, Sun screen lotions, respirators, dust masks, etc. and rearranging/ planning the construction activities to suit the weather conditions.

3.3.20 Communication

All persons deployed at the work site shall have access to effective means of communication so that any untoward incident can be reported immediately and assistance sought by them.

All health & safety information shall be communicated in a simple & clear language easily understood by the local workforce.

3.3.21 Confined Space Entry

The contractor shall obtain a work permit (Format No. HSE -7) before entering a confined space. All necessary precautions mentioned therein shall be adhered to. An attendant shall be positioned outside a confined space for extending help during an emergency. All appropriate PPEs and air quality parameters shall be checked before entering a confined space. It shall be ensured that the piping of the equipment which has to be opened, is pressure- free by checking that blinds are in place, vents are open and volume is drained.

3.3.22 Heavy Lifts

The contractor shall submit detailed rigging studies plan for EIL/ Owner approval prior to lifting equipment which cannot be erected with a crane of approx. 100 MT capacity due to constraints of its dimensions, location of foundation height, approach & weight.

Prior to actual lifting activities, contractor shall check the validity of the crane inspection certificate issued by statutory/ competent authority. This requirement shall also apply to all rigging equipments utilized for the job.

The contractor shall, at all times, be responsible for all rigging activities.

Adequate safety measures such as positive barricading, usage of appropriate PPEs, permit to work, etc. shall be taken during all heavy or critical lifts.

3.3.23 Key Performance Indicators

The contractor shall measure an activity in both leading & trailing indicators for statistical and performance measurement. The activities pertaining to key performance indicators are covered in Monthly HSE Report (Format No. HSE-5). The contractor shall try to achieve a statistically fair record and strive for its continual improvement.

3.3.24 Unsuitable Land Conditions

Contractor shall take appropriate measures and necessary work permits/clearances if work is to be done in or around marshy areas, river crossings, mountains, monuments, etc.

3.3.25 Under Water Inspection

Contractor shall ensure that boats and other means used for transportation, surveying & investigation works shall be certified seaworthy by a recognized classification society. It shall be equipped with all life saving devices like life jackets, adequate fire protection arrangements

and shall possess communication facilities like cellular phones, wireless, walkie-talkie. All divers used for seabed surveys, underwater inspections shall have required authorized license, suitable life saving kit. Number of hours of work by divers shall be limited as per regulations. EIL/ Owner shall have the right to inspect the boat and scrutinize documents in this regard.

3.4 TOOL BOX MEETING (TBM)

Contractor shall conduct daily TBM with workers prior to start of work and shall maintain proper record of the meeting. A suggested format is given below. The TBM is to be conducted by the immediate supervisor of the workers.

TOOLBOX MEETING RECORDING SHEET		
Date & Time		
Subject		
Presenter		
Hazards involved		
Precautions to be taken		
Worker's Name	Signature	Section
Remarks, in any		

The topics during TBM shall include

- Hazards related to work assigned on that day and precautions to be taken.
- Any forthcoming HSE hazards/events/instruction/orders, etc.

The above record can be kept in local language, which workers can read. These records shall be made available to EIL/ Owner whenever demanded.

3.5 TRAINING & INDUCTION PROGRAMME

Contractor shall conduct an induction programme on HSE for his workers and maintain records. The Gate Pass shall be issued only to those workers who successfully qualify the induction programme.

Contractor shall ensure that all his personnel possess appropriate training to carry out the assigned job safely. The training should be imparted in a language understood by them and should specifically be trained about

- Potential hazards to which they may be exposed at their workplace
- Measures available for prevention and elimination of these hazards

The topics during training shall cover, at the minimum ;

- Education about hazards and precautions required
- Emergency and evacuation plan
- HSE requirements
- Fire fighting and First-Aid
- Use of PPEs
- Local laws on intoxicating drinks, drugs, smoking in force

Records of the training shall be kept and submitted to EIL/ Owner whenever demanded.

For offshore and jetty jobs, contractor shall ensure that all personnel deployed have undergone a structured sea survival training including use of lifeboats, basket landing, use of radio communication etc. from an agency acceptable to Owner/EIL.

3.6 INSPECTION

The contractor shall carryout daily HSE inspection and record observations at a central location. These inspection records shall be freely accessible to Owner/ EIL representatives. The contractor shall also assist Owner/EIL representatives during the HSE inspections conducted by them.

3.7 ADDITIONAL SAFETY REQUIREMENTS FOR WORKING INSIDE A RUNNING PLANT

As a minimum, the contractor shall ensure adherence to following safety requirements while working in or in the close vicinity of an operating plant:

- a) Contractor shall obtain permits for Hot work, Cold work, Excavation and Confined Space from Owner in the prescribed format.
- b) The contractor shall monitor, record and compile list of his workers entering the operational plant/unit each day and ensure & record their return after completing the job.

- c) Contractor's workers and staff members shall use designated entrances and proceed by designated routes to work areas only assigned to them. The workers shall not be allowed to enter units' area, tanks area, pump rooms, etc. without work authorization permit.
- d) Work activities shall be planned in such a way so as to minimize the disruption of other activities being carried out in an operational plant/unit and activities of other contractors.
- e) The contractor shall submit a list of all chemicals/toxic substances that are intended to be used at site and shall take prior approval of the Owner.
- f) Specific training on working in a hydrocarbon plant shall be imparted to the work force and mock drills shall be carried out for Rescue operations/First-Aid measures.
- g) Proper barricading/cordoning of the operational units/plants shall be done before starting the construction activities. No unauthorized person shall be allowed to trespass. The height and overall design of the barricading structure shall be finalized in consultation with the Owner and shall be got approved from the Owner.
- h) Care shall be taken to prevent hitting underground facilities such as electrical cables, hydrocarbon piping during execution of work.
- i) Barricading with water curtain shall be arranged in specific/critical areas where hydrocarbon vapors are likely to be present such as near horton spheres or tanks. Positioning of fire tenders (from owner) shall also be ensured during execution of critical activities.
- j) Emergency evacuation plan shall be worked out and all workmen shall be apprised about evacuation routes. Mock drill operations may also be conducted.
- k) Flammable gas test shall be conducted prior to any hot work using appropriate measuring instruments. Sewers, drains, vents or any other gas escaping points shall be covered with flame retardant tarpaulin.
- l) Respiratory devices shall be kept handy while working in confined zones where there is a danger of inhalation of poisonous gases. Constant monitoring of presence of Gas/Hydrocarbon shall be done.
- m) Clearance shall be obtained from all parties before starting hot tapping, patchwork on live lines and work on corroded tank roof.
- n) Positive isolation of line/equipment by blinding for welding/cutting/grinding shall be done. Closing of valve will not be considered sufficient for isolation.
- o) Welding spatters shall be contained properly and in no case shall be allowed to fall on the ground containing oil. Similar care shall be taken during cutting operations.
- p) The vehicles, cranes, engines, etc. shall be fitted with spark arresters on the exhaust pipe and got it approved from Safety Department of the Owner.
- q) Plant air should not be used to clean any part of the body or clothing or use to blow off dirt on the floor.
- r) Gas detectors should be installed in gas leakage prone areas as per requirement of Owner's plant operation personnel.

- s) An experienced full time safety personnel shall be exclusively deployed to monitor safety aspects in running plants.

3.8 SELF ASSESSMENT AND ENHANCEMENT

The contractor shall develop a method of check & balance through self assessment & enhancement techniques and shall explore the opportunities for continual improvement in the HSE system.

3.9 HSE PROMOTION

The contractor shall encourage his workforce to promote HSE efforts at workplace by way of organizing workshops/seminars/training programmes, celebrating HSE awareness weeks & National Safety Day, conducting quizzes & essay competitions, distributing pamphlets, posters & material on HSE, providing incentives for maintaining good HSE practices and granting bonus for completing the job without any lost time accident.

4.0 DETAILS OF HSE MANAGEMENT SYSTEM BY CONTRACTOR

4.1 ON AWARD OF CONTRACT

The Contractor shall submit a comprehensive Health, Safety and Environment Manual or programme for approval by EIL/Owner prior to start of work. The Contractor shall participate in the pre-start meeting with EIL/Owner to finalize HSE Plans including the following:

- Job procedure to be followed by the Contractor for construction activities including handling of equipments, scaffolding, electric installations, etc. describing the risks involved, actions to be taken and methodology for monitoring each activity.
- EIL/Owner review/audit requirement.
- Organization structure along with responsibility and authority, records/ reports etc. on HSE activities.
- Emergency evacuation plan/ procedures for site and labour camps
- Job Safety Analysis for high risk jobs
- Procedures for reporting & investigation of accidents and near misses.
- HSE Training programmes
- Reference to Rules, Regulations and statutory requirements.
- HSE reporting

4.2 DURING JOB EXECUTION

Contractor shall implement approved Health, Safety and Environment management programme including but not limited to as brought out under para 3.0. Contractor shall also ensure:

- to arrange workmen compensation insurance, registration under ESI Act, third party liability insurance etc, as applicable.
- to arrange all HSE permits before start of activities (as applicable), like permits for hot work, working at heights (Refer Format No. HSE-6), confined space (Refer Format No. HSE-7), Radiation Work Permit (Refer Format No. HSE-8), Demolishing/ Dismantling Work Permit (Refer Format No. HSE-9), storage of chemical/ explosive materials & its use and implement all precautions mentioned therein. In this regard, requirements of Oil industry Safety Directorate Standard No. Std -105 "Work Permit Systems" shall be complied with while working in existing Oil or Gas processing plants.

- to submit, timely, the completed checklist on HSE activities in Format No.HSE-1, Monthly HSE report in Format No.HSE-5 (use of web based package is compulsory wherever the facility is available else a hard copy is to be submitted), accident/incident reports, investigation reports etc. as per EIL/Owner requirements. Compliance of instructions on HSE shall be done by Contractor and informed urgently to EIL/Owner.
- that his top most executive at site attends all the Safety Committee/HSE meetings arranged by EIL/Owner. Only in case of his absence from site that a second senior most person shall be nominated by him, in advance, and communicated to EIL/Owner.
- display at site office and at prominent locations HSE Policy, caution boards, list of hospitals, emergency services available, safety signs like Men at work, Speed Limits, Hazardous Area.
- provide posters, banners for safe working to promote safety consciousness.
- assess, analyze & mitigate the construction hazards
- carryout audits/inspection at his works as well as sub contractor works as per approved HSE plan/procedure/programme & submit the reports for EIL/Owner review.
- assistance & cooperate during HSE audits by EIL/Owner, and submit compliance report.
- generate & submit of HSE records/report as per this specification.
- apprise EIL/Owner on HSE activities at site.
- carryout all dismantling activities safely, with prior approval of EIL/Owner representative.

4.3 DURING SHORT LISTING OF THE SUB-CONTRACTORS

The contractor shall review the HSE management system of the sub-contractors in line with the requirements given in this specification. The contractor shall be held responsible for the shortcomings observed in the HSE management system of the sub-contractor(s) during execution of the job.

5.0 RECORDS

At the minimum, the contractor shall maintain/ submit HSE records in the following reporting formats:

1.	Monthly HSE Checklist cum compliance report	HSE-1
2.	Accident/ Incident Report	HSE-2
3.	Supplementary Accident/ Incident Investigation report	HSE-3
4.	Near Miss Incident Report	HSE-4
5.	Monthly HSE Report	HSE-5
6.	Permit for working at height	HSE-6
7.	Permit for working in confined space	HSE-7
8.	Permit for radiation work	HSE-8
9.	Permit for demolishing/ dismantling	HSE-9

**APPENDIX-A
(Sheet 1 of 2)**

A. I.S. CODES ON HSE

SP: 53	Safety code for the use, Care and protection of hand operated tools.
IS: 818	Code of practice for safety & health requirements in electric and gas welding and cutting operations
IS: 1179	Eye & Face precautions during welding, equipment etc.
IS: 1860	Safety requirements for use, care and protection of abrasive grinding wheels.
IS: 1989 (Part -II)	Leather safety boots and shoes
IS: 2925	Industrial Safety Helmets
IS: 3016	Code of practice for fire safety precautions in welding & cutting operation.
IS: 3043	Code of practice for earthing
IS: 3764	Code of safety for excavation work
IS: 3786	Methods for computation of frequency and severity rates for industrial injuries and classification of industrial accidents
IS: 3996	Safety Code of scaffolds and ladders
IS: 4082	Recommendations on stacking and storage of construction materials and components at site
IS: 4770	Rubber gloves for electrical purposes
IS: 5121	Safety code for piling and other deep foundations
IS: 5216 (Part-I)	Recommendations on Safety procedures and practices in electrical works
IS: 5557	Industrial and Safety rubber lined boots
IS: 5983	Eye protectors
IS: 6519	Selection, care and repair of Safety footwear
IS: 6994 (Part-I)	Industrial Safety Gloves (Leather & Cotton Gloves)
IS: 7293	Safety Code for working with construction Machinery
IS: 8519	Guide for selection of industrial safety equipment for body protection
IS: 9167	Ear protectors
IS: 11006	Flash back arrestor (Flame arrestor)
IS: 11016	General and safety requirements for machine tools and their operation
IS: 11057	Specification for Industrial safety nets
IS: 11226	Leather safety footwear having direct moulded rubber sole
IS: 11972	Code of practice for safety precaution to be taken when entering a sewerage system
IS: 13367	Code of practice-safe use of cranes
IS: 13416	Recommendations for preventive measures against hazards at working place

APPENDIX-A
(Sheet 2 of 2)

B. INTERNATIONAL STANDARDS ON HSE

Safety Glasses	:	ANSI Z 87.1, ANSI ZZ 87.1, AS 1337, BS 2092, BS 1542, BS 679, DIN 4646/ 58211
Safety Shoes	:	ANSI Z 41.1, AS 2210, EN 345
Hand Gloves	:	BS 1651
Ear Muffs	:	BS 6344, ANSI S 31.9
Hard Hat	:	ANSI Z 89.1/89.2, AS 1808 , BS 5240, DIN 4840
Goggles	:	ANSI Z 87.1
Face Shield	:	ANSI Z 89.1
Breathing Apparatus	:	BS 4667, NIOSH
Welding & Cutting	:	ANSI Z 49.1
Safe handling of compressed Gases in cylinders	:	P-1 (Compressed Gas Association 1235 Jefferson Davis Highway, Arlington VA 22202 - USA)

APPENDIX-B

DETAILS OF FIRST AID BOX

SL. NO.	DESCRIPTION	QUANTITY
1.	Small size Roller Bandages, 1 Inch Wide (Finger Dressing small)	6 Pcs.
2.	Medium size Roller Bandages, 2 Inches Wide (Hand & Foot Dressing)	6 Pcs.
3.	Large size Roller Bandages, 4 Inches Wide (Body Dressing Large)	6 Pcs.
4.	Large size Burn Dressing (Burn Dressing Large)	4 Pkts.
5.	Cotton Wool (20 gms packing)	4 Pkts.
6.	Antiseptic Solution Dettol (100 ml.) or Savalon	1 Bottle
7.	Mercurichrome Solution (100 ml.) 2% in water	1 Bottle
8.	Ammonia Solution (20 ml.)	1 Bottle
9.	A Pair of Scissors	1 Piece
10.	Adhesive Plaster (1.25 cm X 5 m)	1 Spool
11.	Eye pads in Separate Sealed Pkt.	4 pcs.
12.	Tourniquet	1 No.
13.	Safety Pins	1 Dozen
14.	Tinc. Iodine/ Betadin (100 ml.)	1 Bottle
15.	Polythene Wash cup for washing eyes	1 No.
16.	Potassium Permanganate (20 gms.)	1 Pkt.
17.	Tinc. Benzoine (100 ml.)	1 Bottle
18.	Triangular Bandages	2 Nos.
19.	Band Aid Dressing	5 Pcs.
20.	Iodex/Moov (25 gms.)	1 Bottle
21.	Tongue Depressor	1 No.
22.	Boric Acid Powder (20 gms.)	2 Pkt.
23.	Sodium Bicarbonate (20 gms.)	1 Pkt.
24.	Dressing Powder (Nebasulf) (10 gms.)	1 Bottle
25.	Medicinal Glass	1 No.
26.	Duster	1 No.
27.	Booklet (English & Local Language)	1 No. each
28.	Soap	1 No.
29.	Toothache Solution	1 No.
30.	Vicks (22 gms.)	1 Bottle
31.	Forceps	1 No.
32.	Note Book	1 No.
33.	Splints	4 Nos.
34.	Lock	1 Piece
35.	Life Saving/Emergency/Over-the counter Drugs	As decided at site

Box size : 14" x 12" x 4"

Note : The medicines prescribed above are only indicative. Equivalent medicines can also be used.
A prescription, in this regard, shall be required from a qualified Physician.

APPENDIX-C

TYPE OF FIRES VIS-À-VIS FIRE EXTINGUISHERS

Fire ↓ Fire → Extinguisher	Water	Foam	CO ₂	Dry Powder	Multi purpose (ABC)
Originated from paper, clothes, wood	✓	✓	can control minor surface fires	can control minor surface fires	✓
Inflammable liquids like alcohol, diesel, petrol, edible oils, bitumen	×	✓	✓	✓	✓
Originated from gases like LPG, CNG, H ₂	×	×	✓	✓	✓
Electrical fires	×	×	✓	✓	✓

LEGEND : ✓ : CAN BE USED

 × : NOT TO BE USED

Note : Fire extinguishing equipment must be checked atleast once a year and after every use by an authorized person. The equipment must have an inspection label on which the next inspection date is given. Type of extinguisher shall clearly be marked on it.

APPENDIX-D

Indicative List of Statutory Acts & Rules Relating to HSE

- The Indian Explosives Act and Rules
- The Motor Vehicle Act and Central Motor Vehicle Rules
- The Factories Act and concerned Factory Rules
- The Petroleum Act and Petroleum Rules
- The Workmen Compensation Act
- The Gas Cylinder Rules and the Static & Mobile Pressure Vessels Rules
- The Indian Electricity Act and Rules
- The Indian Boiler Act and Regulations
- The Water (Prevention & Control & Pollution) Act
- The Water (Prevention & Control of Pollution) Cess Act
- The Mines & Minerals (Regulation & Development) Act
- The Air (Prevention & Control of Pollution) Act
- The Atomic Energy Act
- The Radiation Protection Rules
- The Indian Fisheries Act
- The Indian Forest Act
- The Wild Life (Protection) Act
- The Environment (Protection) Act and Rules
- The Hazardous Wastes (Management & Handling) Rules
- The Manufacturing, Storage & import of Hazardous Chemicals Rules
- The Public Liability Act
- The Building and Other Construction Workers (Regulation of Employment and Condition of service) Act
- Other statutory acts Like EPF, ESIS, Minimum Wage Act.

APPENDIX-E
(Sheet 1 of 12)

CONSTRUCTION HAZARDS, THEIR EFFECTS & PREVENTIVE MEASURES

ACTIVITY	TYPE OF HAZARD	EFFECT OF HAZARD	PREVENTIVE MEASURES
(A) EXCAVATION • Pit Excavation upto 3.0m	➤ Falling into pit	➤ Personal injury	➤ Provide guard rails/ barricade with warning signal ➤ Provide atleast two entries/ exits. ➤ Provide escape ladders.
	➤ Earth Collapse	➤ Suffocation/ Breathlessness ➤ Buried	➤ Provide suitable size of shoring and strutting, if required. ➤ Keep soil heaps away from the edge equivalent to 1.5m or depth of pit whichever is more. ➤ Don't allow vehicles to operate too close to excavated areas. Maintain atleast 2m distance from edge of cut. ➤ Maintain sufficient angle of repose. Provide slope not less than 1:1 and suitable bench of 0.5m width at every 1.5m depth of excavation in all soils except hard rock. ➤ Battering/benching the sides.
	➤ Contact with buried electric cables ➤ Gas/ Oil Pipelines	➤ Electrocutation ➤ Explosion	➤ Obtain permission from competent authorities, prior to excavation, if required. ➤ Locate the position of buried utilities by referring to plant drawings. ➤ Start digging manually to locate the exact position of buried utilities and thereafter use mechanical means.
• Pit Excavation beyond 3.0m	➤ Same as above plus ➤ Flooding due to excessive rain/ underground water	➤ Can cause drowning situation	➤ Prevent ingress of water ➤ Provide ring buoys ➤ Identify and provide suitable size dewatering pump or well point system
	➤ Digging in the vicinity of existing Building/ Structure	➤ Building/Structure may collapse ➤ Loss of health & wealth	➤ Obtain prior approval of excavation method from local authorities. ➤ Use under-pining method ➤ Construct retaining wall side by side.
	➤ Movement of vehicles/ equipments close to the edge of cut.	➤ May cause cave-in or slides. ➤ Persons may get buried.	➤ Barricade the excavated area with proper lighting arrangements ➤ Maintain at least 2m distance from edge of cut and use stop blocks to prevent over-run ➤ Strengthen shoring and strutting

APPENDIX-E : (Sheet 2 of 12)

CONSTRUCTION HAZARDS, THEIR EFFECTS & PREVENTIVE MEASURES (...Contd.)

ACTIVITY	TYPE OF HAZARD	EFFECT OF HAZARD	PREVENTIVE MEASURES
Narrow deep excavations for pipelines, etc.	➤ Same as above plus ➤ Frequent cave-in or slides	➤ May cause severe injuries or prove fatal	➤ Battering/benching of sides ➤ Provide escape ladders
	➤ Flooding due to Hydro-static testing	➤ May arise drowning situation	➤ Same as above plus ➤ Bail out accumulated water ➤ Maintain adequate ventilation.
Rock excavation by blasting	➤ Improper handling of explosives	➤ May prove fatal	➤ Ensure proper storage, handling & carrying of explosives by trained personnel. ➤ Comply with the applicable explosive acts & rules.
	➤ Uncontrolled explosion	➤ May cause severe injuries or prove fatal	➤ Allow only authorized persons to perform blasting operations. ➤ Smoking and open flames are to be strictly prohibited
	➤ Scattering of stone pieces in atmosphere	➤ Can hurt people	➤ Use PPE like goggles, face mask, helmets etc.
Rock excavation by blasting (Contd)	➤ Entrapping of persons/ animals.	➤ May cause severe injuries or prove fatal	➤ Barricade the area with red flags and blow siren before blasting.
	➤ Misfire	➤ May explode suddenly	➤ Do not return to site for atleast 20 minutes or unless announced safe by designated person.
Piling Work	➤ Failure of pile-driving equipment	➤ Can hurt people	➤ Inspect Piling rigs and pulley blocks before the beginning of each shift.
	➤ Noise pollution	➤ Can cause deafness and psychological imbalance.	➤ Use personal protective equipments like ear plugs, muffs, etc.
	➤ Extruding rods/casing	➤ Can hurt people	➤ Barricade the area and install sign boards ➤ Provide first-aid
	➤ Working in the vicinity of 'Live-Electricity'	➤ Can cause electrocution/ Asphyxiation	➤ Keep sufficient distance from Live-Electricity as per IS code. ➤ Shut off the supply, if possible ➤ Provide artificial/rescue breathing to the injured
(B) CONCRETING	➤ Air pollution by cement	➤ May affect Respiratory System	➤ Wear respirators or cover mouth and nose with wet cloth.
	➤ Handling of ingredients	➤ Hands may get injured	➤ Use gloves & other PPE.
	➤ Protruding reinforcement rods.	➤ Feet may get injured	➤ Use Safety shoes ➤ Provide platform above reinforcement for movement of workers.

APPENDIX-E : (Sheet 3 of 12)

CONSTRUCTION HAZARDS, THEIR EFFECTS & PREVENTIVE MEASURES (...Contd.)

ACTIVITY	TYPE OF HAZARD	EFFECT OF HAZARD	PREVENTIVE MEASURES
	➤ Earthing of electrical mixers, vibrators, etc. not done.	➤ Can cause electrocution/asphyxiation	➤ Ensure earthing of equipments and proper functioning of electrical circuit before commencement of work.
	➤ Falling of materials from height	➤ Persons may get injured	➤ Use hard hats ➤ Remove surplus material immediately from work place. ➤ Ensure lighting arrangements during night hours
	➤ Continuous pouring by same gang	➤ Cause tiredness of workers and may lead to accident.	➤ Insist on shift pattern ➤ Provide adequate rest to workers between subsequent pours.
	➤ Revolving of concrete mixer/ vibrators	➤ Parts of body or clothes may get entrapped.	➤ Allow only mixers with hooper ➤ Provide safety cages around moving motors ➤ Ensure proper mechanical locking of vibrator
● Super-structure	➤ Same as above plus ➤ Deflection in props or shuttering material	➤ Shuttering/props may collapse and prove fatal	➤ Avoid excessive stacking on shuttering material ➤ Check the design and strength of shuttering material before commencement of work ➤ Rectify immediately the deflection noted during concreting.
	➤ Passage to work place	➤ Improperly tied and designed props/planks may collapse	➤ Ensure the stability and strength of passage before commencement of work. ➤ Do not overload and stand under the passage.
(C) REINFOR-CEMENT	➤ Curtailment and binding of rods	➤ Persons may get injured	➤ Use PPE like gloves, shoes, helmets, etc. ➤ Avoid usage of shift tools
	➤ Carrying of rods for short distances/at heights	➤ Workers may get injured their hands and shoulders.	➤ Provide suitable pads on shoulders and use safety gloves. ➤ Tie up rods in easily liftable bundles ➤ Ensure proper staging.
	➤ Checking of clear distance/ cover with hands	➤ Rods may cut or injure the fingers	➤ Use measuring devices like tape, measuring rods, etc.
	➤ Hitting projected rods and standing on cantilever rods.	➤ Persons may get injured and fell down	➤ Use safety shoes and avoid standing unnecessarily on cantilever rods ➤ Avoid wearing of loose clothes

APPENDIX-E : (Sheet 4 of 12)

CONSTRUCTION HAZARDS, THEIR EFFECTS & PREVENTIVE MEASURES (...Contd.)

ACTIVITY	TYPE OF HAZARD	EFFECT OF HAZARD	PREVENTIVE MEASURES
	➤ Falling of material from height	➤ May prove fatal	➤ Use helmets ➤ Provide safety nets
	➤ Transportation of rods by trucks/trailers	➤ Protruded rods may hit the persons	➤ Use red flags/lights at the ends ➤ Do not protrude the rods in front of or by the side of driver's cabin. ➤ Do not extend the rods 1/3 rd of deck length or 1.5m whichever is less
(D) WELDING AND GAS CUTTING	➤ Welding radiates invisible ultraviolet and infra-red rays	➤ Radiation can damage eyes and skin.	➤ Use specified shielding devices and other PPE of correct specifications. ➤ Avoid thoriated tungsten electrodes for GTAW
	➤ Improper placement of oxygen and acetylene cylinders	➤ Explosion may occur	➤ Move out any leaking cylinder ➤ Keep cylinders in vertical position ➤ Use trolley for transportation of cylinders and chain them ➤ Use flashback arrestors
	➤ Leakage/cuts in hoses	➤ May cause fire	➤ Purge regulators immediately and then turn off ➤ Never use grease or oil on oxygen line connections and copper fittings on acetylene lines ➤ Inspect regularly gas carrying hoses ➤ Always use red hose for acetylene & other fuel gases and black for oxygen
	➤ Opening-up of cylinder	➤ Cylinder may burst	➤ Always stand back from the regulator while opening the cylinder ➤ Turn valve slowly to avoid bursting ➤ Cover the lug terminals to prevent short circuiting
	➤ Welding of tanks, container or pipes storing flammable liquids	➤ Explosion may occur	➤ Empty & purge them before welding ➤ Never attach the ground cable to tanks, container or pipe storing flammable liquids ➤ Never use LPG for gas cutting

APPENDIX-E : (Sheet 5 of 12)

CONSTRUCTION HAZARDS, THEIR EFFECTS & PREVENTIVE MEASURES ...(Contd.)

ACTIVITY	TYPE OF HAZARD	EFFECT OF HAZARD	PREVENTIVE MEASURES
(E) RADIOGRAPHY	➤ Ionizing radiation	➤ Radiations may react with the skin and can cause cancer, skin irritation, dermatitis, etc.	➤ Ensure Safety regulations as per BARC/AERB before commencement of job. ➤ Cordon off the area and install Radiation warning symbols ➤ Restrict the entry of unauthorized persons ➤ Wear appropriate PPE and film badges issued by BARC/AERB
	➤ Transportation and Storage of Radiography source	➤ Same as above	➤ Never touch or handle radiography source with hands ➤ Store radiography source inside a pit in an exclusive isolated storage room with lock and key arrangement. The pit should be approved by BARC/AERB. ➤ Radiography source should never be carried either in passenger bus or in a passenger compartment of trains. ➤ BARC/AERB have to be informed before source movement. ➤ Permission from Director General of Civil Aviation is required for booking radio isotopes with airlines.
	➤ Loss of Radio isotope	➤ Same as above	➤ Try to locate with the help of Survey Meter. ➤ Inform BARC/AERB (*)
(F) ELECTRICAL INSTALLATION AND USAGE	➤ Short circuiting	➤ Can cause Electrocutation or Fire	➤ Use rubberized hand gloves and other PPE ➤ Don't lay wires under carpets, mats or door ways. ➤ Allow only licensed electricians to perform on electrical facilities ➤ Use one socket for one appliance ➤ Ensure usage of only fully insulated wires or cables ➤ Don't place bare wire ends in a socket ➤ Ensure earthing of machineries and equipments ➤ Do not use damaged cords and avoid temporary connections ➤ Use spark-proof/flame proof type field distribution boxes.

(*) Atomic Energy Regulatory Board (AERB),
Bhabha Atomic Research Centre (BARC)
Anushaktinagar, Mumbai – 400 094

APPENDIX-E : (Sheet 6 of 12)

CONSTRUCTION HAZARDS, THEIR EFFECTS & PREVENTIVE MEASURES (...Contd.)

ACTIVITY	TYPE OF HAZARD	EFFECT OF HAZARD	PREVENTIVE MEASURES
			➤ Do not allow open/bare connections ➤ Provide all connections through ELCB ➤ Protect electrical cables/equipment's from water and naked flames ➤ Check all connections before energizing
	➤ Overloading of Electrical System	➤ Bursting of system can occur which leads to fire	➤ Display voltage and current ratings prominently with 'Danger' signs. ➤ Ensure approved cable size, voltage grade and type ➤ Switch off the electrical utilities when not in use ➤ Do not allow unauthorized connections. ➤ Ensure proper grid wise distribution of Power
	➤ Improper laying of overhead and underground transmission lines/cables	➤ Can cause electrocution and prove fatal	➤ Do not lay unarmoured cable directly on ground, wall, roof of trees ➤ Maintain atleast 3m distance from HT cables ➤ All temporary cables should be laid atleast 750 mm below ground on 100 mm fine sand overlying by brick soling ➤ Provide proper sleeves at crossings/ intersections ➤ Provide cable route markers indicating the type and depth of cables at intervals not exceeding 30m and at the diversions/termination
(G) FIRE PREVENTION AND PROTECTION	➤ Small fires can become big ones and may spread to the surrounding areas	➤ Cause burn injuries and may prove fatal	➤ In case a fire breaks out, press fire alarm system and shout "Fire, Fire" ➤ Keep buckets full of sand & water/ fire extinguishing equipment near hazardous locations ➤ Confine smoking to 'Smoking Zones' only. ➤ Train people for using specific type of fire fighting equipments under different classes of fire ➤ Keep fire doors/shutters, passages and exit doors unobstructed ➤ Maintain good house keeping and first-aid boxes (for details refer Appendix-B) ➤ Don't obstruct access to Fire extinguishers. ➤ Do not use elevators for evacuation during fire. ➤ Maintain lightning arrestors for elevated structures ➤ Stop all electrical motors with internal combustion

APPENDIX-E : (Sheet 7 of 12)

CONSTRUCTION HAZARDS, THEIR EFFECTS & PREVENTIVE MEASURES (...Contd.)

ACTIVITY	TYPE OF HAZARD	EFFECT OF HAZARD	PREVENTIVE MEASURES
			➤ Move the vehicles from dangerous locations ➤ Remove the load hanging from the crane booms ➤ Remain out of the danger areas.
	➤ Improper selection of Fire extinguisher	➤ It may not extinguish the fire	➤ Ensure usage of correct fire extinguisher meant for the specified fire (for details refer Appendix-C). ➤ Do not attempt to extinguish Oil and electric fires with water. Use foam cylinders/CO₂/sand or earth.
	➤ Improper storage of highly inflammable substances	➤ Same as above	➤ Maintain safe distance of flammable substances from source of ignition ➤ Restrict the distribution of flammable materials to only min. necessary amount ➤ Construct specifically designed fuel storage facilities ➤ Keep chemicals in cool and dry place away from heat. Ensure adequate ventilation ➤ Before welding operation, remove or shield the flammable material properly ➤ Store flammable materials in stable racks, correctly labeled preferably with catchment trays. ➤ Wipe off the spills immediately
	➤ Short circuiting of electrical system	➤ Same as above ➤ Can cause Electrocutation	➤ Don't lay wires under carpets, mats or door ways ➤ Use one socket for one appliance. ➤ Use only fully insulated wires or cables ➤ Do not allow open/bare connections ➤ Provide all connections through ELCB ➤ Ensure earthing of machinaries and equipments
(H) VEHICULAR MOVEMENT	➤ Crossing the Speed Limits (Rash driving)	➤ Personal injury	➤ Obey speed limits and traffic rules strictly ➤ Always expect the unexpected and be a defensive driver ➤ Use seat belts/helmets ➤ Blow horn at intersections and during overtaking operations. ➤ Maintain the vehicle in good condition ➤ Do not overtake on curves, bridges and slopes
	➤ Adverse weather condition	➤ Same as Above	➤ Read the road ahead and ride to the left ➤ Keep the wind screen and lights clean ➤ Do not turn at speed. ➤ Recognize the hazard, understand the defense and act correctly in time.

APPENDIX-E : (Sheet 8 of 12)

CONSTRUCTION HAZARDS, THEIR EFFECTS & PREVENTIVE MEASURES (...Contd.)

ACTIVITY	TYPE OF HAZARD	EFFECT OF HAZARD	PREVENTIVE MEASURES
	➤ Consuming alcohol before and during the driving operation	➤ Same as above	➤ Alcohol and driving do not mix well. Either choose alcohol or driving. ➤ If you have a choice between hitting a fixed object or an on-coming vehicle, hit the fixed object ➤ Quit the steering at once and become a passenger. Otherwise take sufficient rest and then drive. ➤ Do not force the driver to drive fast and round the clock. ➤ Do not day dream while driving
	➤ Falling objects/ Mechanical failure	➤ May prove fatal	➤ Ensure effective braking system, adequate visibility for the drives, reverse warning alarm.. ➤ Proper maintenance of the vehicle as per manufacturer instructions
(I) PROOF TESTING (HYDROSTATIC /PNEUMATIC TESTING)	➤ Bursting of piping ➤ Collapse of tanks ➤ Tanks flying off	➤ May cause injury and prove fatal	➤ Prepare test procedure & obtain EIL/owner's approval ➤ Provide separate gauge for pressurizing pump and piping/equipment ➤ Check the calibration status of all pressure gauges, dead weight testers and temperature recorders ➤ Take dial readings at suitable defined intervals and ensure most of them fall between 40-60% of the gauge scale range ➤ Provide safety relief valve (set at pressure slightly higher than test pressure) while testing with air/ nitrogen ➤ Ensure necessary precautions, stepwise increase in pressure, tightening of bolts/nuts, grouting, etc. before and during testing ➤ Keep the vents open before opening any valve while draining out of water used for hydrotesting of tanks. ➤ Pneumatic testing involves the hazard of released energy stored in compressed gas. Specific care must therefore be taken to minimize the chance of brittle failure during a pneumatic leak test. Test temperature is important in this regard and must be considered when the designer chooses the material of construction.

APPENDIX-E : (Sheet 9 of 12)

CONSTRUCTION HAZARDS, THEIR EFFECTS & PREVENTIVE MEASURES (...Contd.)

ACTIVITY	TYPE OF HAZARD	EFFECT OF HAZARD	PREVENTIVE MEASURES
			A pressure relief device shall be provided, having a set pressure not higher than the test pressure plus the lesser of 345 KPa (50 psi) or 10% of the test pressure. The gas used as test fluid, if not air, shall be nonflammable and nontoxic.
(J) WORKING AT HEIGHTS	➤ Person can fall down	➤ May sustain severe injuries or prove fatal	➤ Provide guard rails/barricade at the work place ➤ Use PPE like full body harness, life line, helmets, safety shoes, etc. ➤ Obtain a permit before starting the work at height above 3 meters ➤ Fall arrest and safety nets, etc. must be installed ➤ Provide adequate working space (min. 0.6 m) ➤ Tie/weld working platform with fixed support ➤ Use roof top walk ladder while working on a slopping roofs ➤ Avoid movement on beams
		➤ May hit the scrap/material stacked at the ground or in between	➤ Keep the work place neat and clean ➤ Remove the scrap immediately
	➤ Material can fall down	➤ May hit the workers working at lower levels and prove fatal	➤ Same as above plus ➤ Do not throw or drop materials or equipment from height. I.e. do not <i>bomb</i> materials ➤ All tools to be carried in a tool-kit Bag or on working uniform ➤ Remove scrap from the planks ➤ Ensure wearing of helmet by the workers working at lower levels
(K) CONFINED SPACES	➤ Suffocation/drowning	➤ Unconsciousness, death	➤ Use respiratory devices, if reqd. ➤ Avoid over crowding inside a confined space ➤ Provide Exhaust fans for ventilation ➤ Do not wear loose clothes, neck ties, etc ➤ Fulfill conditions of the permit

APPENDIX-E : (Sheet 10 of 12)

CONSTRUCTION HAZARDS, THEIR EFFECTS & PREVENTIVE MEASURES (...Contd.)

ACTIVITY	TYPE OF HAZARD	EFFECT OF HAZARD	PREVENTIVE MEASURES
			➤ Check for presence of hydrocarbons, O₂ level ➤ Obtain work permit before entering a confined space ➤ Ensure that the connected piping of the equipment which is to be opened is pressure free, fluid has been drained, vents are open and piping is positively isolated by a blind flange
	➤ Presence of foul smell and toxic substances	➤ Inhalation can pose threat to life	➤ Same as above plus ➤ Check for hydrocarbon and Aromatic compounds before entering a confined space ➤ Depute one person outside the confined space for continuous monitoring and for extending help in case of an emergency
	➤ Ignition/ flame can cause fire	➤ Person may sustain burn injuries or explosion may occur	➤ Keep fire extinguishers at a hand distance ➤ Remove surplus material and scrap immediately ➤ Do not smoke inside a confined space ➤ Do not allow gas cylinders inside a confined space ➤ Use low voltage (24V) lamps for lighting ➤ Use tools with air motors or electric tools with max. voltage of 24V ➤ Remove all equipments at the end of the day
(L) HANDLING AND LIFTING EQUIPMENTS	➤ Failure of load lifting and moving equipments	➤ Can cause accident and prove fatal	➤ Avoid standing under the lifted load and within the operating radius of cranes ➤ Check periodically oil, brakes, gears, horns and tyre pressure of all moving machinery ➤ Check quality, size and condition of all chain pulley blocks, slings, U-clamps, D-shackles, wire ropes, etc. ➤ Allow crane to move only on hard, firm and leveled ground. ➤ Allow lifting slings as short as possible and check gunny packings at the friction points ➤ Do not allow crane to tilt its boom while moving ➤ Install Safe Load Indicator ➤ Ensure certification by applicable authority

APPENDIX-E : (Sheet 11 of 12)

CONSTRUCTION HAZARDS, THEIR EFFECTS & PREVENTIVE MEASURES (...Contd.)

ACTIVITY	TYPE OF HAZARD	EFFECT OF HAZARD	PREVENTIVE MEASURES
	➤ Overloading of lifting equipments	➤ Same as above	➤ Safe lifting capacity of derricks and winches written on them shall be got verified ➤ The max. safe working load shall be marked on all lifting equipments ➤ Check the weight of columns and other heavy items painted on them and accordingly decide about the crane capacity, boom and angle of erection ➤ Allow only trained operators and riggers during crane operation.
	➤ Overhead electrical wires	➤ Can cause electrocution and fire	➤ Do not allow boom or other parts of crane to come within 3m reach of overhead HT cables ➤ Hook and load being lifted shall preferably remain in full visibility of crane operators.
(M) SCAFFOLDING, FORMWORK AND LADDERS	➤ Person can fall down	➤ Person May sustain severe injuries and prove fatal	➤ Provide guard rails for working at height ➤ Face ladder while climbing and use both hands. ➤ Ladders shall extend about 1m above landing for easy access and tying up purpose ➤ Do not place ladders against movable objects and maintain base at 1/4 unit of the working length of the ladder. ➤ Suspended scaffolds shall not be less than 500 mm wide and tied properly with ropes ➤ No loose planks shall be allowed ➤ Use PPE, like helmets, safety shoes, Etc
	➤ Failure of scaffolding material	➤ Same as above	➤ Inspect visually all scaffolding materials for stability and anchoring with permanent structures. ➤ Design scaffolding for max. load carrying capacity. ➤ Scaffolding planks shall not be less than 50X250 mm full thickness lumber or equivalent. These shall be cleated or secured and must extend over the end supports by atleast 150mm and not more than 300mm ➤ Don't overload the scaffolds ➤ Do not splice short ladders to make a longer one. Vertical ladders shall not exceed 6m.
	➤ Material can fall down	➤ Persons working at lower level gets injured	➤ Remove excess material and scrap immediately ➤ Carry the tools in a tool-kit bag only ➤ Provide safety nets

APPENDIX-E : (Sheet 12 of 12)

CONSTRUCTION HAZARDS, THEIR EFFECTS & PREVENTIVE MEASURES (...Contd.)

ACTIVITY	TYPE OF HAZARD	EFFECT OF HAZARD	PREVENTIVE MEASURES
(N) STRUCTURAL WORKS	➤ Personal negligence and danger of fall	➤ Can cause injury or casualty	➤ Do not take rest inside rooms built for welding machines or electrical distribution system. ➤ Avoid walking on beams at height ➤ Wear helmet with chin strap and full body harness while working at height. ➤ Use hand gloves and goggles during grinding operations ➤ Cover or mark the sharp and projected edges ➤ Do not stand within the operating radius of cranes
	➤ Lifting/ slipping of material	➤ Same as above	➤ Do not stand under the lifted load ➤ Stack properly all the materials. Avoid slippage during handling ➤ Control longer pieces lifted up by cranes from both ends ➤ Remove loose materials from height ➤ Ensure tightening of all nuts & bolts
(O) PIPELINE WORKS	➤ Erection/ lowering failure	➤ Can cause injury	➤ Do not stand under the lifted load ➤ Do not allow any person to come within the radii of the side boom handling pipes ➤ Check the load carrying capacity of the lifting tools & tackles ➤ Use safe Load Indicators ➤ Use appropriate PPEs
	➤ Other	➤ Same as above	➤ Wear gum boots in marshy areas ➤ Allow only one person to perform signaling operations while lowering of pipes ➤ Provide night caps on pipes ➤ Provide end covers on pipes for stoppage of pigs while testing/ cleaning operations

FORMAT NO. : HSE-1 REV 0
HSE CHECKILIST CUM COMPLIANCE REPORT

(Sheet 1 of 6)

PROJECT : _____ REPORT NO. : _____
DATE : _____ CONTRACTOR : _____
INSPECTION BY : _____ OWNER : _____
FREQUENCY : FORTNIGHTLY JOB NO. : _____

Note : Write 'NA' wherever the item is not applicable

SL. NO.	ITEM	YES	NO	REMARKS	ACTION
1.	HOUSEKEEPING				
a)	Waste containers provided and used				
b)	Sanitary facilities adequate and Clean				
c)	Passageways and Walkways Clear				
d)	General neatness of working areas				
e)	Other				
2.	PERSONNEL PROTECTIVE EQUIPMENT				
a)	Goggles; Shields				
b)	Face protection				
c)	Hearing protection				
d)	Foot protection				
e)	Hand protection				
f)	Respiratory Masks etc.				
g)	Full body harness conforming to CC, EN 361				
h)	Hard hat (HDPE)				
i)	Other				
3.	EXCAVATIONS/OPENINGS				
a)	Openings properly covered or barricaded				
b)	Excavations shored				
c)	Excavations barricaded				
d)	Overnight lighting provided				
	Other				

FORMAT NO.:HSE-1 REV 0
(Sheet 2 of 6)

	ITEM	YES	NO	REMARKS	ACTION
4.	WELDING & GAS CUTTING				
a)	Gas cylinders chained upright				
b)	Cables and hoses not obstructing				
c)	Screens or shields used				
d)	Flammable materials protected				
e)	Live electrode bits contained properly				
f)	Fire extinguisher (s) accessible				
g)	Other				
5.	SCAFFOLDING & BARRICADING				
a)	Fully decked platforms				
b)	Guard and intermediate rails in place				
c)	Toe boards in place				
d)	Adequate shoring				
e)	Adequate access				
f)	Positive barricading for critical activities				
g)	Installation of warning signs				
h)	Other				
6.	LADDERS				
a)	Extension side rails 1 m above				
b)	Top of landing				
c)	Properly secured				
d)	Angle + 70° from horizontal				
e)	Other				

FORMAT NO.:HSE-1 REV 0
(Sheet 3 of 6)

	ITEM	YES	NO	REMARKS	ACTION
7.	HOISTS, CRANES AND DERRICKS				
a)	Condition of cables and sheaves OK				
b)	Condition of slings, chains, hooks and eyes O.K.				
c)	Inspection and maintenance logs maintained				
d)	Outriggers used				
e)	Signs/barricades provided				
f)	Signals observed and understood				
g)	Qualified operators				
h)	Other				
8.	MACHINERY, TOOLS AND EQUIPMENT				
a)	Proper instruction				
b)	Safety devices				
c)	Proper cords				
d)	Inspection and maintenance				
e)	Other				
9.	VEHICLE AND TRAFFIC				
a)	Rules and regulations observed				
b)	Inspection and maintenance				
c)	Licensed drivers				
d)	Other				

FORMAT NO.:HSE-1 REV 0
(Sheet 4 of 6)

	ITEM	YES	NO	REMARKS	ACTION
10.	TEMPORARY FACILITIES				
a)	Emergency instructions posted				
b)	Fire extinguishers provided				
c)	Fire-aid equipment available				
d)	Secured against storm damage				
e)	General neatness				
f)	In accordance with electrical requirements				
g)	Other				
11.	FIRE PREVENTION				
a)	Personnel instructed				
b)	Fire extinguishers checked				
c)	No smoking in Prohibited areas.				
d)	Hydrants Clear				
e)	Other				
12.	ELECTRICAL				
a)	Use of 3-core armored cables				
b)	Usage of 'All insulated' or 'double-insulated' electrical tools				
c)	All electrical connection are routed through ELCB				
d)	Natural Earthing at the source of power (Main DB)				
e)	Continuity and tightness of earth conductor				
f)	Covering of junction boxes, panels and other energized wiring places				
g)	Ground fault circuit interrupters provided				
h)	Prevention of tripping hazards				
f)	Other				

FORMAT NO.:HSE-1 REV 0
(Sheet 5 of 6)

	ITEM	YES	NO	REMARKS	ACTION
14.	HANDLING AND STORAGE OF MATERIALS				
a)	Properly stored or stacked				
b)	Passageways clear				
c)	Other				
15.	FLAMMABLE GASES AND LIQUIDS				
a)	Containers clearly identified				
b)	Proper storage				
c)	Fire extinguishers nearby				
d)	Other				
16.	WORKING AT HEIGHT				
a)	Erection plan and work permit obtained				
b)	Safety nets				
c)	Full body harness and lanyards; chute lines				
d)	Health Check record available for workers going up?				
e)	Other				
17.	CONFINED SPACE				
a)	Work Permit obtained				
b)	Test for toxic gas and sufficient availability of oxygen conducted				
c)	Atleast one person outside the confined space for monitoring deputed				
d)	Availability of sufficient means of entry, exit and ventilation				
e)	Fire extinguisher and first-aid facility ensured				
f)	Lighting provision made by using 24V Lamp				
g)	Proper usage of PPEs ensured				
18.	RADIOGRAPHY				
a)	Proper storage and handling of source as per BARC/ AERB guidelines				
b)	Work permit obtained				

FORMAT NO.:HSE-1 REV 0
(Sheet 6 of 6)

	ITEM	YES	NO	REMARKS	ACTION
c)	Cordoning of the area done				
d)	Use of appropriate PPE's ensured				
e)	Proper training to workers/supervisors imparted				
f)	Minimum occupancy of workplace ensured				
19.	HEALTH CHECKS				
a)	Workers medically examined and found be fit for working i) at heights ii) in confined space				
b)	Availability of First Aid facilities.				
c)	Proper sanitation at site, office and labour camps				
d)	Arrangement of medical facilities.				
e)	Measures for dealing with illness.				
f)	Availability of Potable drinking water for workmen & staff.				
g)	Provision of crèches for children.				
h)	Stand by vehicle available for evacuation of injured				
20.	ENVIRONMENT				
a)	Chemical and Other Effluents properly disposed				
b)	Cleaning liquid of pipes disposed off properly				
c)	Seawater used for hydro-testing disposed off as per agreed procedure				
d)	Lubricant Waste/Engine oils properly disposed				
e)	Waste from Canteen, offices, sanitation etc disposed properly				
f)	Disposal of surplus earth, stripping materials, Oily rags and combustible materials done properly				
g)	Green belt protection				

Signature of Resident
Engr. With Seal

FORMAT NO. : HSE-2 REV 0
ACCIDENT/INCIDENT REPORT

(To be submitted by contractor after every Accident/ Incident within 24 hours)

Report No.: _____

Name of Site: _____

Date: _____

Name of work: _____

Contractor: _____

Type of Accident/ Incident: ☐ Fatal ☐ Other Lost Time ☐ Non Loss Time ☐ First-Aid case

Name of the injured :

Age :

Father's name :

Sub-contractor M/s :

Date & time of Accident/ Incident :

Location :

Brief description of Accident/ Incident

Cause of Accident/ Incident

Nature of injury/damage

Medical Aid provided/actions taken

Intimation to local authorities (if applicable)

**Signature of contractor
with seal**

To : Owner
: RCM/Site-in-charge EIL (3 copies)

└─> Divisional Head (Constn) through RCM
└─> Project Manager EIL, through RCM

FORMAT NO. : HSE-3 REV 0
SUPPLEMENTARY ACCIDENT/
INCIDENT INVESTIGATION REPORT

Supplementary to Report No: _____ (Copy enclosed)

Project : _____ Site : _____

Name of work : _____ Dated : _____

Contractor : _____ Work Order/LOI No. _____

Name of the Injured : _____ Age : _____

Sub-Contractor M/s : _____

Date & Time of Accident/ Incident : _____ Location : _____

Brief Description & Cause of Accident/ Incident

Nature of Injury/Damage

Comments of Medical Practitioner, who attended the victim/injured

Suggested improvement in the working condition, if any

Loss of man days and impact on site works

Any other comment by Safety Officer

Signature of Contractor
with Seal

To : Owner
: RCM/Site-in-charge EIL (3 copies)

→ Divisional Head (Constn) through RCM
→ Project Manager EIL, through RCM

FORMAT NO. : HSE-4 REV 0
NEAR MISS INCIDENT – SUGGESTED PROFORMA

Report No.: _____

Name of Site: _____

Date: _____

Name of work: _____

Contractor: _____

Incident reported by :

Date & Time of Incident :

Location :

Brief description of incident

Probable cause of incident

Suggested corrective action

Steps taken to avoid recurrence

Yes ☐

No ☐

Signature of Contractor
with seal

To : Owner
: RCM/Site-in-charge EIL (3 copies)

→ Divisional Head (Constn) through RCM
→ Project Manager EIL, through RCM

FORMAT NO. : HSE-5 REV 0
MONTHLY HEALTH, SAFETY & ENVIRONMENT (HSE) REPORT
(To be submitted by each Contractor)

Actual work start Date : _____ For the Month of : _____

Project : _____ Report No : _____

Name of the Contractor : _____ Status as on : _____

Name of Work : _____ Job No : _____

(Wherever web based package is available, the contractor shall feed the record in that)

ITEM		UPTO PREVIOUS MONTH		THIS MONTH	CUMU-LATIVE
1) Average number of Staff & Workmen (average daily headcount, not man days)					
2) Manhours worked					
3) Number of Induction programmes conducted					
4) Number of HSE meetings organized at site					
5) Number of HSE awareness programmes conducted at site					
6) Number of Tool Box Meetings conducted					
7) Number of Lost Time Accidents (LTA)	Fatal				
	Other LTA				
8) Number of Loss Time Injuries (LTI)	Fatalities				
	Other LTI				
9) Number of Non-Loss Time Accidents					
10) Number of First Aid Cases					
11) Number of Near Miss Incidents					
12) No. of unsafe acts/ practices detected					
13) No. of disciplinary actions taken against staff/ workmen					
14) Man-days lost due to accidents					
15) LTA Free Manhours i.e. Number of LTA free manhours from the Last LTA					
16) Frequency Rate (No. of LTA per 2 lacs manhours worked)					
17) Severity Rate (No. of man days lost per 2 lacs manhours worked)					
18) Loss Time Injury Frequency (No. of LTI per 2 lacs manhours worked)					
19) No. of activities for which Job Safety Analysis (JSA) completed					
20) No. of incentives/ awards given					
21) No. of occasions on which penalty imposed by EIL/ Owner					
22) No. of Audits conducted					
23) No. of pending NCs in above Audits					
24) Compensation cases raised with Insurance					
25) Compensation cases resolved and paid to workmen					
26) Whether workmen compensation policy taken			Yes		No
27) Whether workmen compensation policy is valid			Yes		No
28) Whether workmen registered under ESI Act, as applicable			Yes		No
Remarks, if any					

Date :

Safety Officer/Resident Engineer
(Signature and Name)

To : - OWNER
- RCM EIL (2 copies)

FORMAT NO. : HSE-6 REV 0
PERMIT FOR WORKING AT HEIGHT (ABOVE 2 METER)

(Sheet 1 of 2)

Project site _____
Name of the work _____
Name of Contractor _____
Total No. of workers _____

Sr.No. _____
Date _____
Nature of work _____
Exact location of work _____
Duration of work: from _____ to _____

The following items have been checked and compliance shall be ensured during the currency of the permit:

SL. No.	ITEM	DONE	NOT REQD.
1.	Equipment/Work Area inspected	☐	☐
2.	Considered hazard from other routine/non-routine operations and concerned person alerted	☐	☐
3.	ELCB provided	☐	☐
4.	Proper lighting provided	☐	☐
5.	Area cordoned off.	☐	☐
6.	Precautions against public traffic taken	☐	☐
7.	Sound Scaffolding provided	☐	☐
8.	Adequate protected Platform provided	☐	☐
9.	Access and Exit to the area (Ladder properly fixed)	☐	☐
10.	Floor Openings covered	☐	☐
11.	Safety Net provided	☐	☐
12.	Health check of personnel	☐	☐

- A. Following personal protective equipment/measures are provided (✓ mark) and used as relevant:
Hard hat /Gloves/Goggles/Shoes/Face Shield/Life line/Full body safety harness/ Roof top
walk ladder/Any other(pl. specify)
- B. This permit shall be available at the work site at all times.
- C. Permit shall be issued for maximum one week only (Monday to Sunday)
- D. This permit shall be applicable in non-operational areas.
- E. After completion of the work, used permits shall be preserved for record purposes
- F. Additional precautions, if any _____

Permission is granted to work (See overleaf) = Yes/No

Name of Contractor's supervisor
(Initiator)

Name of Contractor's Safety Officer
(Issuing Authority)

FORMAT NO. : HSE-7 REV 0
CONFINED SPACE ENTRY PERMIT

Project site _____
Name of the work _____
Name of Contractor _____
Exact location of work _____

Sr.No. _____
Date _____
Nature of work _____

Safety Requirements POSITIVE ISOLATION OF THE VESSEL IS MANDATORY

(A) Has the equipment been ?

Y	NR		Y	NR		Y	NR	
☐	☐	isolated from power/steam/air	☐	☐	water flushed &/or steamed	☐	☐	radiation sources removed
☐	☐	isolated from liquid or gases	☐	☐	Manways open & ventilated	☐	☐	proper lighting provided
☐	☐	depressurized &/or drained	☐	☐	cont. inert gas flow arranged	☐	☐	
☐	☐	blanked/ blinded/ disconnected	☐	☐	adequately cooled	☐	☐	

(B) Expected Residual Hazards

☐	☐	lack of O ₂	☐	☐	combustible gas/ liquid	☐	☐	H ₂ S / toxic gases
☐	☐	corrosive chemicals	☐	☐	pyrophoric iron / scales	☐	☐	electricity / static
☐	☐	heat/ steam / frost	☐	☐	high humidity	☐	☐	ionizing radiation
☐	☐		☐	☐		☐	☐	

(C) Protection Measures

☐	☐	gloves	☐	☐	ear plug / muff	☐	☐	goggles / face shield
☐	☐	protective clothing	☐	☐	dust / gas / air line mask	☐	☐	personal gas alarm
☐	☐	grounded air educter/blower /AC	☐	☐	attendant with SCBA/air mask	☐	☐	rescue equipment/team
☐	☐	Fire fighting arrangements	☐	☐	safety harness & lifeline	☐	☐	communication equipment
☐	☐		☐	☐		☐	☐	

Authorization / Renewal (It is safe to enter the confined space)

Date	No. of persons allowed	Name of persons allowed	Signature		Time		Signature
			Contractor's Supervisor	Contractor's Safety Officer	From	To	Workman

Permit Closure :

(A) Entry ☐ was closed ☐ stopped ☐ will continue on ...

(B) ☐ Site left in a safe condition
☐ Housekeeping done

(C) Multilock ☐ removed ☐ key transferred
☐ Ensured all men have come out ☐ Manways barricaded

Remarks, if any:

**FORMAT NO. : HSE-8 REV 0
RADIATION WORK PERMIT**

Project : Sr.No. :
Name of the work : Date :
Name of contractor : Job No. :

Location of work :

Source strength :

Cordoned distance (m) :

Name of Radiographing agency :

Approved by Owner/EIL ☐

No. of workers engaged :

The following items have been checked & compliance shall be ensured during currency of the permit:

S. No.	Item description	Done
1.	Safety regulations as per BARC/AERB ensured while source in use/in transit & during storage	☐
2.	Area cordoned off	☐
3.	Lighting arrangements for working during nights ensured	☐
4.	Warning signs/ flash lights installed	☐
5.	Cold work permit taken (if applicable)	☐
6.	PPEs like film badges, dosimeters used	☐

Additional precautions, if any _____

(Radiography Agency's BARC/AERB authorized Supervisor)

(Contractor's Safety Officer)

Permission is granted.

Permit is valid from _____ AM/PM _____ Date to _____ AM/PM _____
Date

(Signature of permit issuing authority)

Name : _____ Designation : _____ Date : _____

Permit renewal :

Permit extended upto		Additional precautions required, if any	Sign of issuing authority with date
Date	Time		

Work completed/ stopped/ area cleared at _____ Hrs of Date _____

(Sign. of permit issuing authority)

Name :

FORMAT NO. : HSE-9 REV 0
DEMOLISHING/DISMANTLING WORK PERMIT

Project : Sr.No. :
Name of the work : Date :
Name of contractor : Job No.:

Name of sub-contractor : No. of workers to be engaged :

Line No./ Equipment No./ Structure to be dismantled :

Location details of dismantling/ demolition with sketch : (clearly indicate the area)

The following items have been checked & compliance shall be ensured during currency of the permit:

S. No.	Item description	Done	Not Applicable
1.	Services like power, gas supply, water, etc. disconnected	☐	☐
2.	Dismantling/ Demolishing method reviewed & approved	☐	☐
3.	Usage of appropriate PPEs ensured	☐	☐
4.	Precautions taken for neighbouring structures	☐	☐
5.	First-Aid arrangements made	☐	☐
6.	Fire fighting arrangements ensured	☐	☐
7.	Precautions taken for blasting	☐	☐

(Contractor's Supervisor)

(Contractor's Safety Officer)

Permission is granted.

(Permit issuing authority)

Name :

Date :

Completion report :

Dismantling/ Demolishing is completed on _____ Date at _____ Hrs.

Materials/ debris transported to identified location ☐ Tagging completed (as applicable) ☐

Services like power, gas supply, water, etc. restored ☐

(Permit issuing authority)

ELECTRICAL	NO.	DATE	REVISION	BY	CHECKED	CONVENOR	CHAIRMAN (S.B.)
	0	04.12.01	ISSUED AS STANDARD	<i>Patil</i>	<i>anand</i>	<i>[Signature]</i>	<i>[Signature]</i>

ELECTRICAL POWER IS THE MAINSTAY OF ANY CONSTRUCTION ACTIVITY. AT THE SAME TIME IT REQUIRES UTMOST CARE IN IT'S UTILISATION TO AVOID ACCIDENTS DUE TO ELECTRICAL SHOCK, FIRE INCIDENTS OR ELECTRIC SHORT CIRCUITS. EXPOSURE OF ELECTRICAL INSTALLATION TO ADVERSE ENVIRONMENTAL CONDITIONS INCREASE THE RISK OF SUCH ACCIDENTS. HENCE IT IS NECESSARY TO TAKE EXTRA PRECAUTIONS FOR SUCH INSTALLATIONS TO ENSURE SAFETY OF PERSONNEL AND EQUIPMENT. THIS STANDARD ADDRESSES THE SAFETY MEASURES REQUIRED TO BE ADOPTED FOR THE ELECTRICAL INSTALLATIONS BY ALL CONTRACTORS DURING CONSTRUCTION PHASE.

1. ALL ELECTRICAL CONNECTIONS/WORK FOR ELECTRICAL INSTALLATIONS SHALL BE CARRIED OUT AS PER PROVISIONS OF THE LATEST REVISION OF THE FOLLOWING CODES AND STANDARDS IN ADDITION TO THE REQUIREMENTS OF STATUTORY AUTHORITIES AND IE RULES:
OISD-STD-173 : FIRE PREVENTION AND PROTECTION SYSTEM FOR ELECTRICAL INSTALLATIONS.
SP-30 (BIS) : NATIONAL ELECTRIC CODE.
THE INSTALLATION SHALL HAVE APPROVAL FROM CONCERNED STATUTORY AUTHORITIES.
2. ALL ELECTRICAL CONNECTIONS SHALL BE DONE BY AN ELECTRICIAN WITH VALID LICENCE AND TO THE SATISFACTION OF ENGINEER-IN-CHARGE.
3. ONE COMPETENT LICENCED ELECTRICIAN SHALL BE MADE AVAILABLE BY CONTRACTOR AT SITE ROUND THE CLOCK TO ATTEND TO THE NORMAL/EMERGENCY JOBS.
4. ALL SWITCH BOARDS/WELDING MACHINES SHALL BE KEPT IN WELL VENTILATED & COVERED SHED. THE SHED SHALL BE ELEVATED TO AVOID WATER LOGGING. NO FLAMMABLE MATERIALS SHALL BE USED FOR CONSTRUCTING THE SHED. ALSO FLAMMABLE MATERIALS SHALL NOT BE STORED IN AND AROUND ELECTRICAL EQUIPMENT/SWITCHBOARD. ADEQUATE CLEARANCES AND OPERATIONAL SPACE SHALL BE PROVIDED AROUND THE EQUIPMENT.
5. FIRE EXTINGUISHERS AND INSULATING MATS SHALL BE PROVIDED IN ALL POWER DISTRIBUTION CENTERS.
6. TEMPORARY ELECTRICAL EQUIPMENT SHALL NOT BE EMPLOYED IN HAZARDOUS AREAS WITHOUT OBTAINING SAFETY PERMIT.
7. PROPER HOUSE KEEPING SHALL BE DONE AROUND THE ELECTRICAL INSTALLATIONS.
8. ALL TEMPORARY INSTALLATIONS SHALL BE TESTED BEFORE ENERGISING, TO ENSURE PROPER EARTHING, BONDING, SUITABILITY OF PROTECTION SYSTEM, ADEQUACY OF FEEDERS/CABLES ETC.
9. ALL WELDERS SHALL USE HAND GLOVES IRRESPECTIVE OF HOLDER VOLTAGE.
10. MULTILINGUAL (ENGLISH, HINDI AND LOCAL LANGUAGE) CAUTION BOARDS, SHOCK TREATMENT CHARTS AND INSTRUCTION PLATE CONTAINING LOCATION OF ISOLATION POINT FOR INCOMING SUPPLY, NAME & TELEPHONE NO. OF CONTACT PERSON IN EMERGENCY SHALL BE PROVIDED IN SUBSTATIONS AND NEAR ALL DISTRIBUTION BOARDS/LOCAL PANELS.
11. OPERATION OF EARTH LEAKAGE DEVICE SHALL BE CHECKED REGULARLY BY TEMPORARILY CONNECTING SERIES TEST LAMP (2 BULBS OF EQUAL RATING CONNECTED IN SERIES) BETWEEN PHASE AND EARTH.
12. THE FOLLOWING DESIGN FEATURES SHALL BE ENSURED FOR ALL ELECTRICAL INSTALLATIONS DURING CONSTRUCTION PHASE.
 - 12.1 EACH INSTALLATION SHALL HAVE A MAIN SWITCH WITH A PROTECTIVE DEVICE, INSTALLED IN AN ENCLOSURE ADJACENT TO THE METERING POINT. THE OPERATING HEIGHT OF THE MAIN SWITCH SHALL NOT EXCEED 1.5 M. THE MAIN SWITCH SHALL BE CONNECTED TO THE POINT OF SUPPLY BY MEANS OF ARMOURED CABLE.
 - 12.2 THE OUTGOING FEEDERS SHALL BE DOUBLE OR TRIPLE POLE SWITCHES WITH FUSES/MCBs. LOADS IN A THREE PHASE CIRCUIT SHALL BE BALANCED AS FAR AS POSSIBLE AND LOAD ON NEUTRAL SHOULD NOT EXCEED 20% OF LOAD IN THE PHASE.



ENGINEERS INDIA LIMITED
NEW DELHI

**SAFETY MEASURES FOR
ELECTRICAL INSTALLATIONS
DURING CONSTRUCTION**

STANDARD

7-51-0332

SH. 1 OF 2

REV

0

ELECTRICAL	NO.	DATE	REVISION	BY	CHECKED	CONVENOR	CHAIRMAN (S.B.)
	0	04.12.01	ISSUED AS STANDARD	<i>Latika</i>	<i>ananta</i>	<i>SK</i>	<i>AKA</i>
12.3 THE INSTALLATION SHALL BE ADEQUATELY PROTECTED AGAINST OVERLOAD, SHORT CIRCUIT AND EARTH LEAKAGE BY THE USE OF SUITABLE PROTECTIVE DEVICES. FUSES WHEREVER USED SHALL BE HRC TYPE. USE OF REWIRABLE FUSES SHALL BE STRICTLY PROHIBITED. THE EARTH LEAKAGE DEVICE SHALL HAVE AN OPERATING CURRENT NOT EXCEEDING 30 mA. 12.4 ALL CONNECTIONS TO THE HANDTOOLS/WELDING RECEPTACLES SHALL BE TAKEN THROUGH PROPER SWITCHES, SOCKETS AND PLUGS. 12.5 ALL SINGLE PHASE SOCKETS SHALL BE 3 PIN TYPE ONLY. ALL UNUSED SOCKETS SHALL BE PROVIDED WITH SOCKET CAPS. 12.6 ONLY 3 CORE (P+N+E) OVERALL SHEATHED FLEXIBLE CABLES WITH MINIMUM CONDUCTOR SIZE OF 1.5 MM² COPPER SHALL BE USED FOR ALL HAND TOOLS. 12.7 ONLY METALLIC DISTRIBUTION BOXES WITH DOUBLE EARTHING SHALL BE USED AT SITE. NO WOODEN BOXES SHALL BE USED. 12.8 ALL POWER CABLES SHALL BE TERMINATED WITH COMPRESSION TYPE CABLE GLANDS. TINNED COPPER LUGS SHALL BE USED FOR MULTISTRAND WIRES/CABLES. 12.9 CABLES SHALL BE FREE FROM ANY INSULATION DAMAGE. 12.10 CABLES SHALL BE LAID UNDERGROUND AT A MINIMUM DEPTH OF 900 MM, COVERED WITH SAND, BRICK AND SOIL FOR ENSURING MECHANICAL PROTECTION. CABLES SHALL NOT BE LAID IN WATER LOGGED AREA AS FAR AS PRACTICABLE. CABLE ROUTE MARKERS SHALL BE PROVIDED AT EVERY 25 M OF BURIED TRENCH ROUTE. WHEN LAID ABOVE GROUND, CABLES SHALL BE PROPERLY CLEATED OR SUPPORTED ON RIGID POLES OF ATLEAST 2 M HIGH. MINIMUM HEAD CLEARANCE OF 6 METERS SHALL BE PROVIDED AT ROAD CROSSINGS. 12.11 UNDER GROUND ROAD CROSSINGS FOR CABLES SHALL BE AVOIDED TO THE EXTENT FEASIBLE. IN ANY CASE NO UNDER GROUND POWER CABLE SHALL BE ALLOWED TO CROSS THE ROADS WITHOUT PIPE SLEEVE. 12.12 ALL CABLE JOINTS SHALL BE DONE WITH PROPER JOINTING KIT. NO TAPED/TEMPORARY JOINTS SHALL BE USED. 12.13 AN INDEPENDENT EARTHING FACILITY SHOULD PREFERABLY BE ESTABLISHED WITHIN THE TEMPORARY INSTALLATION PREMISES. ALL APPLIANCES AND EQUIPMENT SHALL BE ADEQUATELY EARTHED. IN CASE ARMoured CABLES ARE USED, THE ARMOUR SHALL BE BONDED TO THE EARTHING SYSTEM. 12.14 ALL CABLES AND WIRE ROPE USED FOR EARTH CONNECTIONS SHALL BE TERMINATED THROUGH TINNED COPPER LUGS. 12.15 IN CASE OF LOCAL EARTHING, EARTH ELECTRODES SHALL BE BURIED NEAR THE SUPPLY POINT AND EARTH CONTINUITY WIRE SHALL BE CONNECTED TO LOCAL EARTH PLATE FOR FURTHER DISTRIBUTION TO VARIOUS APPLIANCES. ALL INSULATED WIRES FOR EARTH CONNECTION SHALL HAVE INSULATION OF GREEN COLOUR. 12.16 SEPARATE CORE SHALL BE PROVIDED FOR NEUTRAL. EARTH/STRUCTURES SHALL NOT BE USED AS A NEUTRAL IN ANY CASE. 12.17 ON/OFF POSITION OF ALL SWITCHES SHALL BE CLEARLY DESIGNATED/PAINTED FOR EASY ISOLATION IN EMERGENCY. 13. ALL INSULATIONS SHALL BE INSPECTED BY ENGINEER-IN-CHARGE ATLEAST ONCE IN A MONTH.							
 ENGINEERS INDIA LIMITED NEW DELHI			SAFETY MEASURES FOR ELECTRICAL INSTALLATIONS DURING CONSTRUCTION			STANDARD	REV
						7-51-0332 SH. 2 OF 2	0

OIL INDUSTRY SAFETY DIRECTORATE (OISD) GUIDELINES-192 & 207

[ANNEXURE- XI TO SPECIAL CONDITIONS OF CONTRACT]

SAFETY PRACTICES DURING CONSTRUCTION

OISD-GDN-192

**Oil Industry Safety Directorate
Government of India
Ministry of Petroleum and Natural Gas**

CONTENTS

SECTION	Page No.
1.0 Introduction	1
2.0 Scope	1
3.0 Definitions	1
4.0 General Duties	2
4.1 General Duties Of Execution Agencies	2
4.2 General Duties Of Owners	3
5.0 Safety Practices At Work Places	3
5.1 General Provisions	3
5.2 Means Of Access And Egress	4
5.3 Housekeeping	4
5.4 Precautions Against The Fall Of Materials And Persons, And Collapse Of Structures	4
5.5 Prevention Of Unauthorised Entry	4
5.6 Fire Prevention And Fire Fighting	4
5.7 Lighting	5
5.8 Plant, Machinery, Equipment and Hand Tools	5
6.0 Construction Activities	6
6.1 Excavation	6
6.2 Scaffolding, Platforms & Ladders	8
6.3 Structural Work, Laying Of Reinforcement & Concreting	10
6.4 Road Work	13
6.5 Cutting/Welding	13
6.6 Working In Confined Spaces	14
6.7 Proof/Pressure Testing	15
6.8 Working At Heights	16
6.9 Handling And Lifting Equipment	17
6.10 Vehicle Movement	21
6.11 Electrical	22
6.12 Offshore	24
6.13 Demolition	27
6.14 Radiography	28
6.15 Sand/Shot Blasting / Spray Painting	28
6.16 Work above Water	29
7.0 Additional Safety Precaution for Units with Hydrocarbons	29
8.0 First Aid	30
9.0 Documentation	31
10.0 Safety Awareness & Training	31
11.0 References	32
Annexure I	33

SAFETY PRACTICES DURING CONSTRUCTION

1.0 INTRODUCTION

Safety in Construction Management deserves utmost attention especially in the hydrocarbon industry, such as Exploration, Refineries, Pipelines and Marketing installations, Gas Processing units etc. Construction is widely recognised as one of the accident prone activities. Most of the accidents are caused by inadequate planning, failure during the construction process and/or because of design deficiencies. Besides property loss, accidents also result in injuries and fatalities to the personnel; same needs to be prevented.

The reasons for accidents during construction activities are related to unique nature of the industry, human behaviour, difficult work-site conditions, extended odd duty hours, lack of training & awareness and inadequate safety management. Unsafe working methods, equipment failure and improper housekeeping also tend to increase the accident rate in construction.

Ensuring good quality of materials, equipment and competent supervision along with compliance of standard engineering practices shall go a long way to in built safety into the system.

The objective of this standard is to provide practical guidance on technical and educational framework for safety and health in construction with a view to:

- (a) prevent accidents and harmful effects on the health of workers arising from employment in construction;
- (b) ensure appropriate safety during implementation of construction;
- (c) provide safety practice guidelines for appropriate measures of planning, control and enforcement.

2.0 SCOPE

This document specifies broad guidelines on safe practices to be adhered to during construction activities in oil industry. However, before commencing any job, specific hazards and its effects should be assessed and necessary corrective/preventive actions should be taken by all concerned. The document is intended only to supplement and not to

replace or supersede the prevailing statutory requirements, which shall also be followed as applicable. For Personal Protective Equipment, OISD-STD-155 (Part I&II) shall be referred to. The scope of this document does not include the design aspects and quality checks during construction.

3.0 DEFINITIONS

Definitions of various terminology are given below:

- *Adequate, appropriate or suitable* are used to describe qualitatively or quantitatively the means or method used to protect the worker.
- *Brace*: A structural member that holds one point in a fixed position with respect to another point; bracing is a system of structural members designed to prevent distortion of a structure.
- *By hand*: The work is done without the help of a mechanised tool.
- *Competent Authority*: A statutory agency having the power to issue regulations, orders or other instructions having the force of law.
- *Competent person*: A person possessing adequate qualifications, such as suitable training and sufficient knowledge, experience and skill for the safe performance of the specific work. The competent authorities may define appropriate criteria for the designation of such persons and may determine the duties to be assigned to them.
- *Execution agency*:
Any physical or legal person, having contractual obligation with the owner, and who employs one or more workers on a construction site
- *Owner*:
Any physical or legal person for whom construction job is carried out.
It shall also include owner's designated representative/consultant/nominee/agent, authorised from time to time to act for and on its behalf, for supervising/

coordinating the activities of the execution agency.

- *Hazard*: Danger or potential danger.
- *Guard-rail*: An adequately secured rail erected along an exposed edge to prevent persons from falling.
- *Hoist*: A machine, which lifts materials or persons by means of a platform, which runs on guides.
- *Lifting gear*: Any gear or tackle by means of which a load can be attached to a lifting appliance but which does not form an integral part of the appliance or load.
- *Lifting appliance*: Any stationary or mobile appliance used for raising or lowering persons or loads.
- *Means of access or egress*: Passageways, corridors, stairs, platforms, ladders and any other means for entering or leaving the workplace or for escaping in case of danger.
- *Scaffold*: Any fixed, suspended or mobile temporary structure supporting workers and material or to gain access to any such structure and which is not a lifting appliance as defined above.
- *Toe-board*: A barrier placed along the edge of a scaffold platform, runway, etc., and secured there to guard against the slipping of persons or the falling of material.
- *Worker*: Any person engaged in construction activity.
- *Workplace*: All places where workers need to be or to go by reason of their work.

4.0 GENERAL DUTIES

4.1 GENERAL DUTIES OF EXECUTION AGENCIES

4.1.1 Execution agency should:

- i) provide means and organisation to comply with the safety and health measures required at the workplace.
- ii) provide and maintain workplaces, plant, equipment, tools and machinery and organise

construction work so that, there is no risk of accident or injury to health of workers. In particular, construction work should be planned, prepared and undertaken so that:

- (a) dangers, liable to arise at the workplace, are prevented;
 - (b) excessively or unnecessarily strenuous work positions and movements are avoided;
 - (c) organisation of work takes into account the safety and health of workers;
 - (d) materials and products used are suitable from a safety and health point of view;
 - (e) working methods are adopted to safeguard workers against the harmful effects of chemical, physical and biological agents.
- iii) establish committees with representatives of workers and management or make other arrangement for the participation of workers in ensuring safe working conditions.
 - iv) arrange for periodic safety inspections by competent persons of all buildings, plant, equipment, tools, machinery, workplaces and review of systems of work, regulations, standards or codes of practice. The competent person should examine and ascertain the safety of construction machinery and equipment.
 - v) provide such supervision to ensure that workers perform their work with due regard to safety and health of theirs as well as that of others.
 - vi) Employ only those workers who are qualified, trained and suited by their age, physique, state of health and skill.
 - vii) satisfy themselves that all workers are informed and instructed in the hazards connected with their work and environment and trained in the precautions necessary to avoid accidents and injury to health.
 - viii) Ensure that buildings, plant, equipment, tools, machinery or workplaces in which a dangerous defect has been found should not be used until the defect has been rectified.

- ix) Organise for and remain always prepared to take immediate steps to stop the operation and evacuate workers as appropriate, where there is an imminent danger to the safety of workers.
- x) establish a checking system by which it can be ascertained that all the members of a shift, including operators of mobile equipment, have returned to the camp or base at the close of work on dispersed sites and where small groups of workers operate in isolation.
- xi) provide appropriate first aid, training and welfare facilities to workers as per various statutes like the Factories Act, 1948 etc. and, whenever collective measures are not feasible or are insufficient, provide and maintain personal protective equipment and clothing in line with the requirement as per OISD-STD-155 (Vol. I & II) on Personnel Protective Equipment. They should also provide access to workers to occupational health services.
- xii) Educate workers about their right and the duty at any workplace to participate in ensuring safe working conditions to the extent of their control over the equipment and methods of work and to express views on working procedures adopted as may affect safety and health.
- xiii) Ensure that except in an emergency, workers, unless duly authorised, should not interfere with, remove, alter or displace any safety device or other appliance furnished for their protection or the protection of others, or interfere with any method or process adopted with a view to avoiding accidents and injury to health.
- xiv) Ensure that workers do not operate or interfere with plant and equipment that they have not been duly authorised to operate, maintain or use.
- xv) Ensure that workers do not sleep, rest or cook etc in dangerous places such as scaffolds, railway tracks, garages, confined spaces or in the vicinity of fires, dangerous or toxic substances, running machines or vehicles and heavy equipment etc.
- xvii) Obtain the necessary clearance/permits as required and specified by owner
- xviii) As per the Govt. circular as amended from time to time all contractors who employ more than 50 workers or where the contract value exceeds Rs. 50 crores, the following facilities are to be provided by contractor at site :
- Arrangement for drinking water
 - Toilet facilities
 - A creche where 10 or more women workers are having children below the age of 6 years
 - Transport arrangement for attending to emergencies
- xix) should deploy a safety officer at site
- 4.2 GENERAL DUTIES OF OWNERS**
- 4.2.1 Owners should:
- i) co-ordinate or nominate a competent person to co-ordinate all activities relating to safety and health on their construction projects;
 - ii) inform all contractors on the project of special risks to health and safety;
 - iii) Ensure that executing agency is aware of the owner's requirements and the executing agency's responsibilities with respect to safety practices before starting the job.
- 5.0 SAFETY PRACTICES AT WORK PLACES**
- 5.1. GENERAL PROVISIONS**
- 5.1.1 All openings and other areas likely to pose danger to workers should be clearly indicated.
- 5.1.2 Workers & Supervisors should use the safety helmet and other requisite Personal Protective Equipment according to job & site requirement. They should be trained to use personal protective equipment.
- 5.1.3 Never use solvents, alkalis and other oils to clean the skin.
- 5.1.4 Lift the load with back straight and knees bent as far as possible. Seek the help in case of heavy load.

5.1.5 Ensure the usage of correct and tested tools and tackles. Don't allow the make shift tools and tackles.

5.1.6 No loose clothing should be allowed while working near rotating equipment or working at heights.

5.2 MEANS OF ACCESS AND EGRESS

Adequate and safe means of access (atleast two, differently located) to and egress from all workplaces should be provided. Same should be displayed and maintained.

5.3 HOUSEKEEPING

5.3.1 Ensure:

- i) proper storage of materials and equipment;
- ii) removal of scrap, inflammable material, waste and debris at appropriate intervals.

5.3.2 Removal of loose materials, which are not required for use, to be ensured. Accumulation of these at the site can obstruct means of access to and egress from workplaces and passageways.

5.3.3 Workplaces and passageways, that are slippery owing to oil, grease or other causes, should be cleaned up or strewn with sand, sawdust, ash etc.

5.4 PRECAUTIONS AGAINST THE FALL OF MATERIALS & PERSONS AND COLLAPSE OF STRUCTURES

5.4.1 Precautions should be taken such as the provision of fencing, look-out men or barriers to protect any person against injury by the fall of materials, or tools or equipment being raised or lowered.

5.4.2 Where necessary to prevent danger, guys, stays or supports should be used or other effective precautions should be taken to prevent the collapse of structures or parts of structures that are being erected, maintained, repaired, dismantled or demolished.

5.4.3 All openings through which workers are liable to fall should be kept

effectively covered or fenced and displayed prominently.

5.4.4 As far as practicable, guardrails and toe-boards should be provided to protect workers from falling from elevated workplaces.

5.5 PREVENTION OF UNAUTHORISED ENTRY

5.5.1 Construction sites located in built-up areas and alongside vehicular and pedestrian traffic routes should be fenced to prevent the entry of unauthorised persons.

5.5.2 Visitors should not be allowed access to construction sites unless accompanied by or authorised by a competent person and provided with the appropriate protective equipment.

5.6 FIRE PREVENTION AND FIRE FIGHTING

5.6.1 All necessary measures should be taken by the executing agency and owner to:

- i) avoid the risk of fire;
- ii) control quickly and efficiently any outbreak of fire;
- iii) bring out a quick and safe evacuation of persons.
- iv) Inform unit/fire station control room, where construction work is carried out within existing operating area.

5.6.2 Combustible materials such as packing materials, sawdust, greasy/oily waste and scrap wood or plastics should not be allowed to accumulate in workplaces but should be kept in closed metal containers in a safe place.

5.6.3 Places where workers are employed should, if necessary to prevent the danger of fire, be provided with:

- i) suitable and sufficient fire-extinguishing equipment, which should be easily visible and accessible;
- ii) an adequate water supply at sufficient pressure meeting the requirements of various OISD standards.

5.6.4 To guard against danger at places having combustible material,

- workers should be trained in the action to be taken in the event of fire, including the use of means of escape.
- 5.6.5 At sites having combustible material, suitable visual signs should be provided to indicate clearly the direction of escape in case of fire.
- 5.6.6 Means of escape should be kept clear at all times. Escape routes should be frequently inspected particularly in high structures and where access is restricted.
- 5.7 LIGHTING**
- 5.7.1 Where natural lighting is not adequate, working light fittings or portable hand-lamps should be provided at workplace on the construction site where a worker will do a job.
- 5.7.2 Emergency lighting should be provided for personnel safety during night time to facilitate standby lighting source, if normal system fails.
- 5.7.2 Artificial lighting should not produce glare or disturbing shadows.
- 5.7.3 Lamps should be protected by guards against accidental breakage.
- 5.7.4 The cables of portable electrical lighting equipment should be of adequate size & characteristics for the power requirements and of adequate mechanical strength to withstand severe conditions in construction operations.
- 5.8 PLANT, MACHINERY, EQUIPMENT AND HAND TOOLS**
- 5.8.1 General Provisions**
- i) Plant, machinery and equipment including hand tools, both manual and power driven, should:
- be of proper design and construction, taking into account health, Safety and ergonomic principles.
 - be maintained in good working order;
 - be used only for work for which they have been designed.
- d) be operated only by workers who have been authorised and given appropriate training.
- e) be provided with protective guards, shields or other devices as required.
- ii) Adequate instructions for safe use should be provided.
- iii) Safe operating procedures should be established and used for all plant, machinery and equipment.
- iv) Operators of plant, machinery and equipment should not be distracted while work is in progress.
- v) Plant, machinery and equipment should be switched off when not in use and isolated before any adjustment, clearing or maintenance is done.
- vi) Where trailing cables or hose pipes are used they should be kept as short as practicable and not allowed to create a hazard.
- vii) All moving parts of machinery and equipment should be enclosed or adequately guarded.
- viii) Every power-driven machine and equipment should be provided with adequate means, immediately accessible and readily identifiable to the operator, of stopping it quickly and preventing it from being started again inadvertently.
- ix) Operators of plant, machinery, equipment and tools should be provided with PPEs, including where necessary, suitable ear protection.
- 5.8.2 Hand tools**
- i) Hand tools should be repaired by competent persons.
- ii) Heads of hammers and other shock tools should be dressed or ground to a suitable radius on the edge as soon as they begin to mushroom or crack.
- iii) When not in use and while being carried or transported sharp tools should be kept in sheaths, shields, chests or other suitable containers.
- iv) Only insulated or nonconducting tools should be used on or near live electrical installations.

- v) Only non-sparking tools should be used near or in the presence of flammable or explosive dusts or vapours.

5.8.3 Pneumatic Tools

- i) Operating triggers on portable pneumatic tools should be:
 - a) so placed as to minimise the risk of accidental starting of the machine.
 - b) so arranged as to close the air inlet valve automatically when the pressure of the operator's hand is removed.
- ii) Hose and hose connections for compressed air supply to portable pneumatic tools should be:
 - a) designed and tested for the pressure and service for which they are intended;
 - b) fastened securely on the pipe outlet and equipped with the safety chain, as appropriate.
- iii) Pneumatic shock tools should be equipped with safety clips or retainers to prevent dies and tools from being accidentally expelled from the barrel.
- iv) Pneumatic tools should be disconnected from power and the pressure in hose lines released before any adjustment or repair is made.

5.8.4 Electrical Tools

- i) Low voltage portable electrical tools should generally be used.
- ii) All electrical tools should be earthed, unless they are "all insulated" or "double insulated" tools which do not require earthing.
- iii) All electrical tools should get inspected and maintained on a regular basis by a competent electrician and complete records kept.

5.8.5 Engines

- i) Engines should:
 - a) be installed so that they can be started safely and the maximum safe speed cannot be exceeded.
 - b) have controls for limiting speed.

- c) have devices to stop them from a safe place in an emergency.
- ii) IC engines should not be run in confined spaces unless adequate exhaust ventilation is provided.
- iii) When IC engines are being fuelled:
 - a) the engine should be shut off.
 - b) care should be taken to avoid spilling fuel;
 - c) no person should smoke or have an naked light in the vicinity.
 - d) a fire extinguisher should be kept readily available.
- iv) Secondary fuel reservoir should be placed outside the engine room.

6.0 CONSTRUCTION ACTIVITIES

The various common activities in construction are as under:

- Excavation
- Scaffolding, Platforms & Ladders
- Structural Work, Laying of Reinforcement & Concreting
- Road Work (Laying of roads)
- Cutting /Welding
- Working in Confined Space
- Proof/Pressure Testing
- Working at Heights
- Handling & Lifting Equipments
- Vehicle Movement
- Electrical
- Offshore
- Demolition
- Radiography
 - Sand/shot blasting/ spray painting
 - Work above water

The safe practices to be followed during the implementation of above construction activities are given below:

6.1 EXCAVATION

- 6.1.1 All excavation work should be planned and the method of excavation and the type of support

work required should be decided considering the following:

- i) the stability of the ground;
 - ii) the excavation will not affect adjoining buildings, structures or roadways;
 - iii) to prevent hazard, the gas, water, electrical and other public utilities should be shut off or disconnected, if necessary;
 - iv) presence of underground pipes, cable conductors, etc.,
 - v) the position of culvert/bridges, temporary roads and spoil heaps should be determined;
- 6.1.2 Before digging begins on site, all excavation work should be planned and the method of excavation and the type of support work required decided.
- 6.1.3 All excavation work should be supervised.
- 6.1.4 Sites of excavations should be thoroughly inspected:
- i) daily, prior to each shift and after interruption in work of more than one day;
 - ii) after every blasting operation;
 - iii) after an unexpected fall of ground;
 - iv) after substantial damage to supports;
 - v) after a heavy rain, frost or snow;
 - vi) when boulder formations are encountered.
- 6.1.5 Safe angle of repose while excavating trenches exceeding 1.5m depth upto 3.0m should be maintained. Based on site conditions, provide proper slope, usually 45°, and suitable bench of 0.5m width at every 1.5m depth of excavation in all soils except hard rock or provide proper shoring and strutting to prevent cave-in or slides.
- 6.1.6 As far as possible, excavated earth should not be placed within one meter of the edge of the trench or depth of trench whichever is greater.
- 6.1.7 Don't allow vehicles to operate too close to excavated area. Maintain atleast 2m distance from edge of excavation. No load, plant or equipment should be placed or moved near the edge of any excavation where it is likely to cause its collapse and thereby endanger any person unless precautions such as the provision of shoring or piling are taken to prevent the sides from collapsing.
- 6.1.8 Adequately anchored stop blocks and barriers should be provided to prevent vehicles being driven into the excavation. Heavy vehicles should not be allowed near the excavation unless the support work has been specially designed to permit it.
- 6.1.9 If an excavation is likely to affect the security of a structure on which persons are working, precautions should be taken to protect the structure from collapse.
- 6.1.10 Barricade at 1m height (with red & white band/self glowing caution board) should be provided for excavations beyond 1.5m depth. Provide two entries/exits for such excavation.
- 6.1.11 Necessary precautions should be taken for underground utility lines like cables, sewers etc. and necessary approvals/clearances from the concerned authorities shall be obtained before commencement of the excavation job.
- 6.1.12 Water shall be pumped/bailed out, if any accumulates in the trench. Necessary precautions should be taken to prevent entry of surface water in trenches.
- 6.1.13 During rains, the soil becomes loose. Take additional precaution against collapse of side wall.
- 6.1.14 In hazardous areas, air should be tested to ascertain its quality. No one should be allowed entry till it is suitable for breathing.
- 6.1.15 In case of mechanised excavation, precaution shall be taken to not to allow anybody to come within one meter of extreme reach of the mechanical shovel. The mechanised excavator shall be operated by a well-trained experienced operator. When not in operation, the machine shall be kept on firm leveled ground with mechanical shovel resting on ground. Wheel or belt shall be suitably jammed to prevent any accidental movement of the

machine. Suitable precautions as per manufacturer guidelines should be taken for dozers, graders and other heavy machines.

- 6.1.16 In case of blasting, follow strictly IS:4081-1986 & Indian Explosive Act and rules for storage, handling and carrying of explosive materials and execution of blasting operation.

6.2 SCAFFOLDING, PLATFORMS & LADDERS

6.2.1 Metal as material of construction

- i) A scaffold should be provided and maintained or other equally safe and suitable provision should be made where work cannot safely be done on or from the ground or from part of a building or other permanent structure.
- ii) Scaffolds should be provided with safe means of access, such as stairs, ladders or ramps. Ladders should be secured against inadvertent movement.
- iii) Every scaffold should be constructed, erected and maintained so as to prevent collapse or accidental displacement when in use.
- iv) Every scaffold and part thereof should be constructed :
 - (a) in such a way so as not to cause hazards for workers during erection and dismantling;
 - (b) in such a way so as guard rails and other protective devices, platforms, ladders, stairs or ramps can be easily put together;
 - (c) with sound material and of requisite size and strength for the purpose for which it is to be used and maintained in a proper condition.
- v) Boards and planks used for scaffolds should be protected against splitting.
- vi) Materials used in the construction of scaffolds should be stored under good conditions and apart from any material unsuitable for scaffolds.
- vii) Couplers should not cause deformation in tubes. Couplers should be made of drop forged steel or equivalent material.
- viii) Tubes should be free from cracks, splits and excessive corrosion and be straight to the eye, and tube ends cut cleanly square with the tube axis.
- ix) Scaffolds should be designed for their maximum load as per relevant code.
- x) Scaffolds should be adequately braced.
- xi) Scaffolds which are not designed to be independent should be rigidly connected to the building at designated vertical and horizontal places.
- xii) A scaffold should never extend above the highest anchorage to an extent which might endanger its stability and strength.
- xiii) Loose bricks, drainpipes, chimney-pots or other unsuitable material should not be used for the construction or support of any part of a scaffold.
- xiv) Scaffolds should be inspected and certified:
 - (a) before being taken into use;
 - (b) at periodic intervals thereafter as prescribed for different types of scaffolds;
 - (c) after any alteration, interruption in use, exposure to weather or seismic conditions or any other occurrence likely to have affected their strength or stability.
- xv) Inspection should more particularly ascertain that:
 - (a) the scaffold is of suitable type and adequate for the job;
 - (b) materials used in its construction are sound and of sufficient strength;
 - (c) it is of sound construction and stable;
 - (d) that the required safeguards are in position.
- xvi) A scaffold should not be erected, substantially altered or dismantled except by or under the supervision.
- xvii) Every scaffold should be maintained in good and proper condition, and every part should be kept fixed or secured so that no part can be

displaced in consequence of normal use.

- xviii) If out-rigger scaffolding is to be used, it should be specifically designed and inspected before putting in use.

6.2.2 Lifting appliances on scaffolds

- i) When a lifting appliance is to be used on a scaffold:
 - (a) the parts of the scaffold should be carefully inspected to determine the additional strengthening and other safety measures required;
 - (b) any movement of the scaffold members should be prevented;
 - (c) if practicable, the uprights should be rigidly connected to a solid part of the building at the place where the lifting appliance is erected.

6.2.3 Prefabricated scaffolds

- i) In the case of prefabricated scaffold systems, the instructions provided by the manufacturers or suppliers should be strictly adhered to. Prefabricated scaffolds should have adequate arrangements for fixing bracing.
- ii) Frames of different types should not be intermingled in a single scaffold.
- iii) Scaffolding shall be erected on firm and level ground.
- iv) All members of metal scaffolding shall be checked periodically to screen out defective / rusted members. All joints should be properly lubricated for easy tightening.
- v) Entry to scaffolding should be restricted.
- vi) Erection, alteration and removal shall be done under supervision of experienced personnel.
- vii) Use of barrels, boxes, loose bricks etc., for supporting platform shall not be permitted.
- viii) Each supporting member of platform shall be securely fastened and braced
- ix) Where planks are butt-joined, two parallel putlogs shall be used, not

more than 100mm apart, to give support to each plank.

- x) Platform plank shall not project beyond its end support to a distance exceeding 4 times the thickness of plank, unless it is effectively secured to prevent tipping. Cantilever planks should be avoided.
- xi) The platform edges shall be provided with 150mm high toe board to eliminate hazards of tools or other objects falling from platform.
- xii) Erect ladders in the "four up-one out position"
- xiii) Lash ladder securely with the structure.
- xiv) Using non-slip devices, such as, rubber shoes or pointed steel ferules at the ladder foot, rubber wheels at ladder top, fixing wooden battens, cleats etc.
- xv) When ladder is used for climbing over a platform, the ladder must be of sufficient length, to extend at least one meter above the platform, when erected against the platform in "four up-one out position."
- xvi) Portable ladders shall be used for heights not more than 4mt. Above 4mt flights, fixed ladders shall be provided with at least 600 mm landings at every 6mt or less.
- xvii) The width of ladder shall not be less than 300mm and rungs shall be spaced not more than 300mm.
- xviii) Every platform and means of access shall be kept free from obstruction.
- xix) If grease, mud, gravel, mortar etc., fall on platform or scaffolds, these shall be removed immediately to avoid slippage.
- xx) Workers shall not be allowed to work on scaffolds during storms or high wind. After heavy rain or storms, scaffolds shall be inspected before reuse.
- xxi) Don't overload the scaffolding. Remove excess material and scrap immediately.
- xxii) Dismantling of scaffolds shall be done in a pre-planned sequential manner.

6.2.4 Suspended scaffolds/boatwain's chair

- i) In addition to the requirements for scaffolds in general as regards soundness, stability and protection against the risk of falls, suspended scaffolds should meet the following specific requirements.
 - (a) platforms should be designed and built with dimensions that are compatible with the stability of the structure as a whole, especially the length;
 - (b) the number or anchorage should be compatible with the dimensions of the platform;
 - (c) the safety of workers should be safeguarded by an extra rope having a point of attachment independent of the anchorage arrangements of the scaffold;
 - (d) the anchorage and other elements of support of the scaffold should be designed and built in such a way as to ensure sufficient strength;
 - (e) the ropes, winches, pulleys or pulley blocks should be designed, assembled, used and maintained according to the requirements established for lifting gear adapted to the lifting of persons according to national laws and regulations;
 - (f) Before use, the whole structure should be checked by a competent person.

6.2.5 Bamboo Scaffolding

- i) In general, it should be avoided as far as possible. It should not be used in the unit/off-site areas and where hot work is to be done.
- ii) For construction and maintenance of residential and office buildings, situated outside explosive licensed area, bamboo scaffold, if used, should conform to provisions given in IS-3696 (Part 1)-1987.

6.3 STRUCTURAL WORK, LAYING OF REINFORCEMENT & CONCRETING

6.3.1 General provisions

- i) The erection or dismantling of buildings, structures, civil

engineering works, formwork, falsework and shoring should be carried out by trained workers only under the supervision of a competent person.

- ii) Precautions should be taken to guard against danger to workers arising from any temporary state of weakness or instability of a structure.
- iii) Formwork, falsework and shoring should be so designed, constructed and maintained that it will safely support all loads that may be imposed on it.
- iv) Formwork should be so designed and erected that working platforms, means of access, bracing and means of handling and stabilising are easily fixed to the formwork structure.

6.3.2. Erection and dismantling of steel and prefabricated structures

- i) The safety of workers employed on the erection and dismantling of steel and prefabricated structures should be ensured by appropriate means, such as provision and use of:
 - (a) ladders, gangways or fixed platforms;
 - (b) platforms, buckets, boatswain's chairs or other appropriate means suspended from lifting appliances;
 - (c) safety harnesses and lifelines, catch nets or catch platforms;
 - (d) Power-operated mobile working platforms.
- ii) Steel and prefabricated structures should be so designed and made that they can be safely transported and erected.
- iii) In addition to the need for the stability of the part when erected, the design should explicitly take following into account:
 - (a) the conditions and methods of attachment in the operations of transport, storing and temporary support during erection or dismantling as applicable;
 - (b) Methods for the provision of safeguards such as railings and working platforms, and, when necessary, for mounting them

- easily on the structural steel or prefabricated parts.
- iv) The hooks and other devices built in or provided on the structural steel or prefabricated parts that are required for lifting and transporting them should be so shaped, dimensioned and positioned as:
 - (a) to withstand with a sufficient margin the stresses to which they are subjected;
 - (b) Not to set up stresses in the part that could cause failures, or stresses in the structure itself not provided for in the plans, and be designed to permit easy release from the lifting appliance. Lifting points for floor and staircase units should be located (recessed if necessary) so that they do not protrude above the surface;
 - (c) To avoid imbalance or distortion of the lifted load.
 - v) Storeplaces should be so constructed that:
 - (a) there is no risk of structural steel or prefabricated parts falling or overturning;
 - (b) storage conditions generally ensure stability and avoid damage having regard to the method of storage and atmospheric conditions;
 - (c) racks are set on firm ground and designed so that units cannot move accidentally.
 - vi) While they are being stored, transported, raised or set down, structural steel or prefabricated parts should not be subjected to stresses prejudicial to their stability.
 - vii) Every lifting appliance should:
 - (a) be suitable for the operations and not be capable of accidental disconnection;
 - (b) be approved or tested as per statutory requirement.
 - viii) Lifting hooks should be of the self-closing type or of a safety type and should have the maximum permissible load marked on them.
 - ix) Tongs, clamps and other appliances for lifting structural steel and prefabricated parts should:
 - (a) be of such shape and dimensions as to ensure a secure grip without damaging the part;
 - (b) be marked with the maximum permissible load in the most unfavourable lifting conditions.
 - x) Structural steel or prefabricated parts should be lifted by methods or appliances that prevent them from spinning accidentally.
 - xi) When necessary to prevent danger, before they are raised from the ground, structural steel or prefabricated parts should be provided with safety devices such as railings and working platforms to prevent falls of persons.
 - xii) While structural steel or prefabricated parts are being erected, the workers should be provided with appliances for guiding them as they are being lifted and set down, so as to avoid crushing of hands and to facilitate the operations. Use of such appliances should be ensured.
 - xiii) A raised structural steel or prefabricated part should be so secured and wall units so propped that their stability cannot be imperiled, even by external agencies such as wind and passing loads before its release from the lifting appliance.
 - xiv) At work places, instruction should be given to the workers on the methods, arrangements and means required for the storage, transport, lifting and erection of structural steel or prefabricated parts, and, before erection starts, a meeting of all those responsible should be held to discuss and confirm the requirements for safe erection.
 - xv) During transportation within the construction area, attachments such as slings and stirrups mounted on structural steel or prefabricated parts should be securely fastened to the parts.
 - xvi) Structural steel or prefabricated parts should be so transported that the conditions do not affect the stability of the parts or the means of transport result in jolting, vibration or stresses due to blows, or loads of material or persons.

- xvii) When the method of erection does not permit the provision of other means of protection against fall of persons, the workplaces should be protected by guardrails, and if appropriate by toe-boards.
- xviii) When adverse weather conditions such as snow, ice and wind or reduced visibility entail risks of accidents, the work should be carried on with particular care, or, if necessary, interrupted.
- xix) Structures should not be worked on during violent storms or high winds, or when they are covered with ice or snow, or are slippery from other causes.
- xx) If necessary, to prevent danger, structural steel parts should be equipped with attachments for suspended scaffolds, lifelines or safety harnesses and other means of protection.
- xxi) The risks of falling, to which workers moving on high or sloping girders are exposed, should be limited by all means of adequate collective protection or, where this is impossible, by the use of a safety harness that is well secured to a strong support.
- xxii) Structural steel parts that are to be erected at a great height should as far as practicable be assembled on the ground.
- xxiii) When structural steel or prefabricated parts are being erected, a sufficiently extended area underneath the workplace should be barricaded or guarded
- xxiv) Steel trusses that are being erected should be adequately shored, braced or guyed until they are permanently secured in position.
- xxv) Load-bearing structural member should not be dangerously weakened by cutting, holing or other means.
- xxvi) Structural members should not be forced into place by the hoisting machine while any worker is in such a position that he could be injured by the operation.
- xxvii) Open-web steel joists that are hoisted singly should be directly

placed in position and secured against dislodgment.

6.3.3 Reinforcement

- i) Ensure that workers use Personnel Protective equipment like safety helmet, safety shoes, gloves etc.
- ii) Don't place the hand below the rods for checking clear distance. Use measuring devices.
- iii) Don't wear loose clothes while checking the rods.
- iv) Don't stand unnecessarily on cantilever rods.
- v) To carry out welding/cutting of rods, safety procedures/precautions as mentioned in Item No. 6.5 to be followed.
- vi) For supplying of rods at heights, proper staging and/or bundling to be provided.
- vii) Ensure barricading and staging for supplying and fixing of rods at height.
- viii) For short distance carrying of materials on shoulders, suitable pads to be provided.
- ix) While transporting material by trucks/trailers, the rods shall not protrude in front of or by the sides of driver's cabin. In case such protrusion cannot be avoided behind the deck, then it should not extend $1/3^{rd}$ of deck length or 1.5M which ever is less and tied with red flags/lights.

6.3.4 Concreting

- i) Ensure stability of shuttering work before allowing concreting.
- ii) Barricade the concreting area while pouring at height/depths.
- iii) Keep vibrator hoses, pumping concrete accessories in healthy conditions and mechanically locked.
- iv) Pipelines in concrete pumping system shall not be attached to temporary structures such as scaffolds and formwork support as the forces and movements may effect their integrity.

- v) Check safety cages & guards around moving motors/parts etc. provided in concreting mixers.
- vi) Use Personal Protective Equipment like gloves, safety shoes etc. while dealing with concrete and wear respirators for dealing with cement.
- vii) Earthing of electrical mixers, vibrators, etc. should be done and verified.
- viii) Cleaning of rotating drums of concrete mixers shall be done from outside. Lockout devices shall be provided where workers need to enter.
- ix) Where concrete mixers are driven by internal combustion engine, exhaust points shall be located away from the worker's workstation so as to eliminate their exposure to obnoxious fumes.
- x) Don't allow unauthorised person to stand under the concreting area.
- xi) Ensure adequate lighting arrangements for carrying out concrete work during night.
- xii) Don't allow the same workers to pour concrete round the clock. Insist on shift pattern.
- xiii) During pouring, shuttering and its supports should be continuously watched for defects.

6.4 ROAD WORK

- 6.4.1 Site shall be barricaded and provided with warning signs, including night warning lamps at appropriate locations for traffic diversion.
- 6.4.2 Filled and empty bitumen drums shall be stacked separately at designated places.
- 6.4.3 Mixing aggregate with bitumen shall preferably be done with the help of bitumen batch mixing plant, unless operationally non-feasible.
- 6.4.4 Road rollers, Bitumen sprayers, Pavement finishers shall be driven by experienced drivers with valid driving license.
- 6.4.5 Workers handling hot bitumen sprayers or spreading bitumen aggregate mix or mixing bitumen

with aggregate, shall be provided with PVC hand gloves and rubber shoes with legging up to knee joints.

- 6.4.6 At the end of day's work, surplus hot bitumen in tar boiler shall be properly covered by a metal sheet, to prevent anything falling in it,
- 6.4.7 If bitumen accidentally falls on ground, it shall be immediately covered by sprinkling sand, to prevent anybody stepping on it. Then it shall be removed with the help of spade.
- 6.4.8 For cement concrete roads, besides site barricading and installation of warning signs for traffic diversion, safe practices mentioned in the chapter on "Concreting", shall also be applicable.

6.5 CUTTING/WELDING

- 6.5.1 Common hazards involved in welding/cutting are sparks, molten metal, flying particles, harmful light rays, electric shocks etc. Following precautions should be taken: -
 - i) A dry chemical type fire extinguisher shall be made available in the work area.
 - ii) Adequate ventilation shall be ensured by opening manholes and fixing a shield or forced circulation of air etc, while doing a job in confined space.
 - iii) Ensure that only approved and well-maintained apparatus, such as torches, manifolds, regulators or pressure reducing valves, and acetylene generators, be used.
 - iv) All covers and panels shall be kept in place, when operating an electric Arc welding machine.
 - v) The work piece should be connected directly to Power supply, and not indirectly through pipelines/structures/equipments etc.
 - vi) The welding receptacles shall be rated for 63 A suitable for 415V, 3 Phase system with a scraping earth. Receptacles shall have necessary mechanical interlocks and earthing facilities.
 - vii) All cables, including welding and ground cables, shall be checked for

- any worn out or cracked insulation before starting the job. Ground cable should be separate without any loose joints.
- viii) Cable coiling shall be maintained at minimum level, if not avoidable.
 - ix) An energised electrode shall not be left unattended.
 - x) The power source shall be turned off at the end of job.
 - xi) All gas cylinders shall be properly secured in upright position.
 - xii) Acetylene cylinder shall be turned and kept in such a way that the valve outlet points away from oxygen cylinder.
 - xiii) Acetylene cylinder key for opening valve shall be kept on valve stem, while cylinder is in use, so that the acetylene cylinder could be quickly turned off in case of emergency. Use flash back arrestors to prevent back-fire in acetylene/oxygen cylinder.
 - xiv) When not in use, valves of all cylinders shall be kept closed.
 - xv) All types of cylinders, whether full or empty, shall be stored at cool, dry place under shed.
 - xvi) Forced opening of any cylinder valve should not be attempted.
 - xvii) Lighted gas torch shall never be left unattended.
 - xviii) Store acetylene and oxygen cylinders separately.
 - xix) Store full and empty cylinders separately.
 - xx) Avoid cylinders coming into contact with heat.
 - xxi) Cylinders that are heavy or difficult to carry by hand may be rolled on their bottom edge but never dragged.
 - xxii) If cylinders have to be moved, be sure that the cylinder valves are shut off.
 - xxiii) Before changing torches, shut off the gas at the pressure reducing regulators and not by crimping the hose.
 - xxiv) Do not use matches to light torches, use a friction lighter.
 - xxv) Move out any leaking cylinder immediately.
 - xxvi) Use trolleys for oxygen & acetylene cylinder and chain them.
 - xxvii) Always use Red hose for acetylene and other fuel gases and Black for oxygen, and ensure that both are in equal length.
 - xxviii) Ensure that hoses are free from burns, cuts and cracks and properly clamped.
 - xxix) Avoid dragging hoses over sharp edges and objects
 - xxx) Do not wrap hoses around cylinders when in use or stored.
 - xxxi) Protect hoses from flying sparks, hot slag, and other hot objects.
 - xxxii) Lubricants shall not be used on Ox-fuel gas equipment.
 - xxxiii) During cutting/welding, use proper type goggles/face shields.
- ## 6.6 WORKING IN CONFINED SPACES
- ### 6.6.1 Following safety practices for working in confined space like towers, columns, tanks and other vessels should be followed in addition to the safety guidelines for specific jobs like scaffolding, cutting/welding etc.
- i) Shut down, isolate, depressurise and purge the vessel as per laid down procedures.
 - ii) Entry inside the vessel and to carry out any job should be done after issuance of valid permit only in line with the requirement of OISD-STD-105.
 - iii) Ensure proper and accessible means of exit before entry inside a confined space.
 - iv) The number of persons allowed inside the vessel should be limited to avoid overcrowding.
 - v) When the work is going on in the confined space, there should always be one man standby at the nearby manway.

- vi) Before entering inside the vessels underground or located at lower elevation, probability of dense vapours accumulating nearby should also be considered in addition to inside the vessel.
- vii) Ensure requisite O₂ level before entry in the confined space and monitor level periodically or other wise use respiratory devices.
- viii) Check for no Hydrocarbon or toxic substances before entry and monitor level periodically or use requisite Personal Protective Equipment.
- ix) Ensure adequate ventilation or use respiratory devices.
- x) Depending upon need, necessary respirator system, gas masks and suit shall be worn by everyone entering confined space. In case of sewer, OWS or in the confined area where there is a possibility of toxic or inert gas, gas masks shall be used by everyone while entering.
- xi) Barricade the confined spaces during hoisting, radiography, blasting, pressure testing etc.
- xii) Use 24V flameproof lamp fittings only for illumination.
- xiii) Use tools with air motors or electric tools with maximum voltage of 24V.
- xiv) House keeping shall be well maintained.
- xv) Safety helmet, safety shoes and safety belt shall be worn by everyone entering the confined space.
- xvi) Don't wear loose clothing while working in a confined space.
- xvii) In case of the vessels which are likely to contain pyrophoric substances (like Iron Sulphide), special care need to be taken before opening the vessel. Attempt should be made to remove the pyrophoric substances. Otherwise, these should be always kept wet by suitable means.
- xviii) The cutting torches should also be kept outside the vessel immediately after the cutting.
- xix) The gas cylinders used for cutting/welding shall be kept outside.
- xx) All cables, hoses, welding equipment etc., shall be removed from confined space at end of each work day, even if the work is to be resumed in the same space the next day.
- xxi) To the extent possible sludge shall be cleared and removed from outside before entering.
- xxii) No naked light or flame or hot work such as welding, cutting and soldering should be permitted inside a confined space or area unless it has been made completely free of the flammable atmosphere, tested and found safe by a competent person. Only non-sparking tools and flameproof hand lamps protected with guard and safety torches should be used inside such confined space or area for initial inspection, cleaning or other work required to be done for making the area safe.
- xxiii) Communication should be always maintained between the worker and the attendant.

6.7 PROOF/PRESSURE TESTING

- 6.7.1 Review test procedure before allowing testing with water or air or any other fluid.
- 6.7.2 Provide relief valves of adequate size while testing with air or other gases.
- 6.7.3 Ensure compliance of necessary precautions, step wise loading, tightening of fasteners, grouting etc. before and during testing.
- 6.7.4 Inform all concerned in advance of the testing.
- 6.7.5 Keep the vents open before opening any valve for filling/drainage of liquid used for hydrotesting. The filling/drainage should not exceed the designed rate for pressure testing.
- 6.7.6 Provide separate gauges of suitable range for pressurising pump and the equipment to be tested.
- 6.7.7 Provide gauges at designated locations for monitoring of pressures.

6.7.8 Check the calibration of all pressurising equipment and accessories and maintain records.

6.7.9 Take readings at pre-defined intervals.

6.8 WORKING AT HEIGHTS

6.8.1 General Provision

- i) While working at a height of more than 3 meters, ISI approved safety belt shall be used.
- ii) While working at a height of more than 3 meters, permit should be issued by competent person before commencement of the job.
- iii) Worker should be well trained on usage of safety belt including its proper usage at the time of ascending/descending.
- iv) All tools should be carried in tool kits to avoid their falling.
- v) If the job is on fragile/sloping roof, roof walk ladders shall be used.
- vi) Provide lifeline wherever required.
- vii) Additional safety measures like providing Fall Arrestor type Safety belt, safety net should be provided depending upon site conditions, job requirements.
- viii) Keep working area neat and clean. Remove scrap material immediately.
- ix) Don't throw or drop material/equipment from height.
- x) Avoid jumping from one member to another. Use proper passageway.
- xi) Keep both hands free while climbing. Don't try to bypass the steps of the ladder.
- xii) Try to maintain calm at height. Avoid over exertion.
- xiii) Avoid movements on beam.
- xiv) Elevated workplaces including roofs should be provided with safe means of access and egress such as stairs, ramps or ladders.

6.8.2 Roof Work

- i) All roof-work operations should be pre-planned and properly supervised.

ii) Roof work should only be undertaken by workers who are physically and psychologically fit and have the necessary knowledge and experience for such work.

iii) Work on roofs shouldn't be carried on in weather conditions that threaten the safety of workers.

iv) Crawling boards, walkways and roof ladders should be securely fastened to a firm structure.

v) Roofing brackets should fit the slope of the roof and be securely supported.

vi) Where it is necessary for a person to kneel or crouch near the edge of the roof, necessary precautions should be taken.

vii) On a large roof where work have to be carried out at or near the edge, a simple barrier consisting of crossed scaffold tubes supporting a tubing guardrail may be provided.

viii) All covers for openings in roofs should be of substantial construction and be secured in position.

ix) Roofs with a pitch of more than 10 should be treated as sloping.

x) When work is being carried out on sloping roofs, sufficient and suitable crawling boards or roof ladders should be provided and firmly secured in position.

xi) During extensive work on the roof, strong barriers or guardrails and toe-boards should be provided to stop a person from falling off the roof.

xii) Where workers are required to work on or near roofs or other places covered with fragile material, through which they are liable to fall, they should be provided with suitable roof ladders or crawling boards strong enough and when spanning across the supports for the roof covering to support those workers.

xiii) A minimum of two boards should be provided so that it is not necessary for a person to stand on a fragile roof to move a board or a ladder, or for any other reason.

6.8.3 Work on tall chimneys

- i) For the erection and repair of tall chimneys, scaffolding should be provided. A safety net should be maintained at a suitable distance below the scaffold.
- ii) The scaffold floor should always be at least 65 cm below the top of the chimney.
- iii) Under the working floor of the scaffolding the next lower floor should be left in position as a catch platform.
- iv) The distance between the inside edge of the scaffold and the wall of the chimney should not exceed 20 cm at any point.
- v) Catch platforms should be erected over:
 - (a) the entrance to the chimney;
 - (b) Passageways and working places where workers could be endangered by falling objects.
- vi) For climbing tall chimneys, access should be provided by:
 - (a) stairs or ladders;
 - (b) a column of iron rungs securely embedded in the chimney wall;
 - (c) Other appropriate means.
- vii) When workers use the outside rungs to climb the chimney, a securely fastened steel core rope looped at the free end and hanging down at least 3 m should be provided at the top to help the workers to climb on to the chimney.
- viii) While work is being done on independent chimneys the area surrounding the chimney should be enclosed by fencing at a safe distance.
- ix) Workers employed on the construction, alteration, maintenance or repair of tall chimneys should not:
 - a) work on the outside without a safety harness attached by a lifeline to a rung, ring or other secure anchorage;
 - b) put tools between the safety harness and the body or in pockets not intended for the purpose;

- c) haul heavy materials or equipment up and down by hand to or from the workplace on the chimney;
- d) fasten pulleys or scaffolding to reinforcing rings without first verifying their stability;
- e) work alone;
- f) climb a chimney that is not provided with securely anchored ladders or rungs;
- g) Work on chimneys in use unless the necessary precautions to avoid danger from smoke and gases have been taken.
- x) Work on independent chimneys should not be carried on in high winds, icy conditions, fog or during electrical storms.

6.9 HANDLING AND LIFTING EQUIPMENT:

6.9.1 General Provisions

Following are the general guidelines to be followed with regard to all types of handling and lifting equipment in addition to the guidelines for specific type of equipments dealt later on.

- i) There should be a well-planned safety programme to ensure that all the lifting appliances and lifting gear are selected, installed, examined, tested, maintained, operated and dismantled with a view to preventing the occurrence of any accident;
- ii) All lifting appliances shall be examined by competent persons at frequencies as specified in "The Factories act".
- iii) Check thoroughly quality, size and condition of all lifting tools like chain pulley blocks, slings, U-clamps, D-shackles etc. before putting them in use.
- iv) Safe lifting capacity of all lifting & handling equipment, tools and shackles should be got verified and certificates obtained from competent authorities before its use. The safe working load shall be marked on them.
- v) Check periodically the oil, brakes, gears, horns and tyre pressure of all moving equipments like cranes,

- forklifts, trailers etc as per manufacturer's recommendations.
- vi) Check the weights to be lifted and accordingly decide about the crane capacity, boom length and angle of erection.
 - vii) Allow lifting slings as short as possible and check packing at the friction points.
 - viii) While lifting/placing of the load, no unauthorised person shall remain within the radius of the boom and underneath the load.
 - ix) While loading, unloading and stacking of pipes, proper wedges shall be placed to prevent rolling down of the pipes.
 - x) Control longer jobs being lifted up from both ends.
 - xi) Only trained operators and riggers should carry out the job. While the crane is moving or lifting the load, the trained rigger should be there for keeping a vigil against hitting any other object.
 - xii) During high wind conditions and nights, lifting of heavy equipments should be avoided. If unavoidable to do erection in night, operator and rigger should be fully trained for night signaling. Also proper illumination should be there.
 - xiii) Allow crane to move on hard, firm and leveled ground.
 - xiv) When crane is in idle condition for long periods or unattended, crane boom should either be lowered or locked as per manufacturer's guidelines.
 - xv) Hook and load being lifted shall remain in full visibility of crane operators, while lifting, to the extent possible.
 - xvi) Don't allow booms or other parts of crane to come within 3 meters reach of overhead electrical cables.
 - xvii) No structural alterations or repairs should be made to any part of a lifting appliance, which may affect the safety of the appliance without the permission and supervision of the competent person.

6.9.2 Hoists

- i) Hoist shafts should be enclosed with rigid panels or other adequate fencing at:
 - (a) ground level on all sides;
 - (b) all other levels at all points at which access is provided;
 - (c) all points at which persons are liable to be struck by any moving part.
- ii) The enclosure of hoist shafts, except at approaches should extend where practicable at least 2mt above the floor, platform or other place to which access is provided except where a lesser height is sufficient to prevent any person falling down the hoistway and there is no risk of any person coming into contact with any moving part of the hoist, but in no case should the enclosure be less than 1mt in height.
- iii) The guides of hoist platforms should offer sufficient resistance to bending and, in the case of jamming by a safety catch, to buckling.
- iv) Where necessary to prevent danger, adequate covering should be provided above the top of hoist shafts to prevent material falling down them.
- v) Outdoor hoist towers should be erected on firm foundations, and securely braced, guyed and anchored.
- vi) A ladderway should extend from the bottom to the top of outdoor hoist towers, if no other ladderway exists within easy reach.
- vii) Hoisting engines should be of ample capacity to control the heaviest load that they will have to move.
- viii) Hoists should be provided with devices that stop the hoisting engine as soon as the platform reaches its highest stopping place.
- ix) Winches should be so constructed that the brake is applied when the control handle is not held in the operating position.
- x) It should not be possible to set in motion from the platform a hoist, which is not designed for the conveyance of persons.

- xi) Winches should not be fitted with pawl and ratchet gears on which the pawl must be disengaged before the platform is lowered.
- xii) Hoist platforms should be capable of supporting the maximum load that they will have to carry with a safety factor.
- xiii) Hoist platforms should be equipped with safety gear that will hold the platform with the maximum load if the hoisting rope breaks.
- xiv) If workers have to enter the cage or go on the platform at landings there should be a locking arrangement preventing the cage or platform from moving while any worker is in or on it.
- xv) On sides not used for loading and unloading, hoist platforms should be provided with toe-boards and enclosures of wire mesh or other suitable material to prevent the fall of parts of loads.
- xvi) Where necessary to prevent danger from falling objects, hoist platforms should be provided with adequate covering.
- xvii) Counterweights consisting of an assemblage of several parts should be made of specially constructed parts rigidly connected together.
- xviii) Counterweights should run in guides.
- xix) Platforms should be provided at all landings used by workers.
- xx) Following notices should be posted up conspicuously and in very legible characters:
 - (a) on all hoists:
 - on the platform: the carrying capacity in kilograms or other appropriate standard unit of weight;
 - on the hoisting engine: the lifting capacity in kilograms or other appropriate standard unit of weight;
 - (b) on hoists authorised or certified for the conveyance of persons:

- on the platform or cage: the maximum number of persons to be carried at one time;

(c) on hoists for goods only:

- on every approach to the hoist and on the platform: prohibition of use by persons.

- xxi) Hoists intended for the carriage of persons should be provided with a cage so constructed as to prevent any person from falling out or being trapped between the cage and any fixed part of the structure when the cage gate is shut, or from being struck by the counterbalance weight or by articles or materials tailing down the hoistway.
- xxii) On each side in which access is provided, the cage should have a gate fitted with devices which ensure that the gate cannot be opened except when the cage is at a landing and that the gate must be closed before the cage can move away from the landing.
- xxiii) Every gate in the enclosure of the hoist shaft which gives access from a landing place to the cage should be fitted with devices to ensure that the gate cannot be opened except when the cage is at that landing place, and that the cage cannot be moved away from that landing place until the gate is closed.

6.9.3 Derricks

Stiff-leg derricks

- i) Derricks should be erected on a firm base capable of taking the combined weight of the crane structure and maximum rated load.
- ii) Devices should be used to prevent masts from lifting out of their seating.
- iii) Electrically operated derricks should be effectively earthed from the sole plate or framework.
- iv) Counterweights should be so arranged that they do not subject the backstays, sleepers or pivots to excessive strain.
- v) When derricks are mounted on wheels:

- a) a rigid member should be used to maintain the correct distance between the wheels;
 - b) they should be equipped with struts to prevent them from dropping if a wheel breaks or the derrick is derailed.
- vi) The length of a derrick jib should not be altered without consulting the manufacturer.
 - vii) The jib of a scotch derrick crane should not be erected within the backstays of the crane.

Guy derricks

- i) The restraint of the guy ropes should be ensured by fitting stirrups or anchor plates in concrete foundations.
- ii) The mast of guy derricks should be supported by six top guys spaced approximately equally.
- iii) The spread of the guys of a guy derrick crane from the mast should not be more than 45° from the horizontal.
- iv) Guy ropes of derricks should be equipped with a stretching screw or turnbuckle or other device to regulate the tension.
- v) Gudgeon pins, sheave pins and fool bearings should be lubricated frequently.
- vi) When a derrick is not in use, the boom should be anchored to prevent it from swinging.

6.9.4 Gin poles

- i) Gin poles should:
 - (a) be straight;
 - (b) consist of steel or other suitable metal;
 - (c) be adequately guyed and anchored;
 - (d) be vertical or raked slightly towards the load;
 - (e) be of adequate strength for the loads that they will be required to lift/move.
- ii) Gin poles should not be spliced and if a gin pole is composed of different elements, they should be assembled in conformity with their intrinsic material strength.

- iii) Gin poles should be fastened at their feet to prevent displacement in operation.
- iv) Gin poles, which are moved from place to place and re-erected, should not be taken into use again before the pole, lifting ropes, guys, blocks and other parts have been inspected, and the whole appliance has been tested under load.
- v) When platforms or skips are hoisted by gin poles, precautions should be taken to prevent them from spinning and to provide for proper landing.

6.9.5 Tower cranes

- i) Where tower cranes have cabs at high level, persons, capable and trained to work at heights, should only be employed as crane operators.
- ii) The characteristics of the various machines available should be considered against the operating requirements and the surroundings in which the crane will operate before a particular type of crane is selected.
- iii) Care should be taken in the assessment of wind loads both during operations and out of service. Account should also be taken of the effects of high structures on wind forces in the vicinity of the crane.
- iv) The ground on which the tower crane stands should have the requisite bearing capacity. Account should be taken of seasonal variations in ground conditions.
- v) Bases for tower cranes and tracks for rail-mounted tower cranes should be firm and level. Tower cranes should only operate on gradients within limits specified by the manufacturer. Tower cranes should only be erected at a safe distance from excavations and ditches.
- vi) Tower cranes should be sited where there is clear space available for erection, operation and dismantling. As far as possible, cranes should be sited so that loads do not have to be handled over occupied premises, over public thoroughfares, other construction works and railways or near power cables.

- vii) Where two or more tower cranes are sited in positions where their jibs could touch any part of the other crane, there should be direct means of communication between them and a distinct warning system operated from the cab so that one driver may alert the other of impending danger.
- viii) The manufacturers' instructions on the methods and sequence of erection and dismantling should be followed. The crane should be tested before being taken into use.
- ix) The climbing operation of climbing tower cranes should be carried out in accordance with manufacturers' instructions. The free-standing height of the tower crane should not extend beyond what is safe and permissible in the manufacturers' instructions.
- x) When the tower crane is left unattended, loads should be removed from the hook, the hook raised, the power switched off and the boom brought to the horizontal. For longer periods or at times when adverse weather conditions are expected, out of service procedures should be followed. The main jib should be slewed to the side of the tower away from the wind, put into free slew and the crane immobilised.
- xi) A windspeed measuring device should be provided at an elevated position on the tower crane with the indicator fitted in the drivers' cab.
- xii) Devices should be provided to prevent loads being moved to a point where the corresponding safe working load of the crane would be exceeded. Name boards or other items liable to catch the wind should not be mounted on a tower crane other than in accordance with the manufacturers' instructions.
- xiii) Tower cranes should not be used for magnet, or demolition ball service, piling operations or other duties, which could impose excessive loading on the crane structure.

6.9.6 Lifting ropes

- i) Only ropes with a known safe working capacity should be used as lifting ropes.
- ii) Lifting ropes should be installed, maintained and inspected in accordance with manufacturers' instructions.
- iii) Repaired steel ropes should not be used on hoists.
- iv) Where multiple independent ropes are used, for the purpose of stability, to lift a work platform, each rope should be capable of carrying the load independently.

6.10 VEHICLE MOVEMENT

- 6.10.1 Park vehicles only at designated places. Don't block roads to create hindrance for other vehicles.
- 6.10.2 Don't overload the vehicle.
- 6.10.3 Obey speed limits and traffic rules.
- 6.10.4 Always expect the unexpected and be a defensive driver.
- 6.10.5 Drive carefully during adverse weather and road conditions.
- 6.10.6 Read the road ahead and ride to the left.
- 6.10.7 Be extra cautious at nights. Keep wind screens clean and lights in working condition.
- 6.10.8 All vehicles used for carrying workers and construction materials must undergo predictive/preventive maintenance and daily checks
- 6.10.9 Driver with proper valid driving license shall only be allowed to drive the vehicle
- 6.10.10 Routes shall be leveled, marked and planned in such a way so as to avoid potential hazards such as overhead power lines and sloping ground etc.
- 6.10.11 While reversing the vehicles, help of another worker should be ensured at all times
- 6.10.12 An unattended vehicle should have the engine switched off
- 6.10.13 Wherever possible one-way system shall be followed
- 6.10.14 Barriers/fixed stops should be provided for excavation/openings to prevent fall of vehicle

- 6.10.15 Load should be properly secured
- 6.10.16 The body of the tipper lorry should always be lowered before driving the vehicle off.
- 6.10.17 Signs/signals/caution boards etc. should be provided on routes .

6.11 ELECTRICAL

6.11.1 General Provisions

- i) Only persons having valid licenses should be allowed to work on electrical facilities.
- ii) No person should be allowed to work on live circuit. The same, if unavoidable, special care and authorisation need to be taken.
- iii) Treat all circuits as "LIVE" unless ensured otherwise.
- iv) Electrical "Tag Out" procedure "MUST" be followed for carrying out maintenance jobs.
- v) Display voltage ratings prominently with "Danger" signs.
- vi) Put caution/notice signs before starting the repair works.
- vii) All electrical equipment operating above 250V shall have separate and distinct connections to earth grid.
- viii) Proper grounding to be ensured for all switch boards and equipment including Portable ones prior to taking into service.
- ix) Make sure that electrical switch boards, portable tools, equipments (like grinding machine etc.) don't get wet during their usage. If it happens, stop the main supply, make the tools dry and then only use them. Check proper earthing.

All temporary switch boards/ KIOSKS put up at work site should be suitably protected from rain and the level of same should be high enough to avoid contact with water due to water logging.
- x) Don't work wet on electrical system.
- xi) Don't overload the electrical system.
- xii) Use only proper rated HRC fuses.
- xiii) Industrial type extension boards and Plug sockets are only to be used.
- xiv) ELCB for all temporary connections must be provided. Use insulated 3 pin plug tops.
- xv) All power supply cables should be laid properly and neatly so that they don't cause hindrance to persons working and no physical damage also takes place to the cables during various construction activities.
- xvi) All Power cables to be properly terminated using glands and lugs of proper size and adequately crimped.
- xvii) Use spark-proof/flame proof type electrical fittings in Fire Hazard zones as per area classification under OISD-STD-113.
- xviii) Check installations of steel plates/pipes to protect underground cables at crossings.
- xix) Don't lay unarmored cable directly on ground, wall, roof or trees. All temporary cables should be laid at least 750 mm below ground and cable markers should be provided. Proper sleeves should be provided at road crossings. In case temporary cables are to be laid on wooden poles/steel poles, the minimum cable heights should be 4.5 M.
- xx) Maintain safe overhead distance of HT cables as per Indian Electricity Rules and relevant acts.
- xxi) Don't connect any earthing wire to the pipelines/structures.
- xxii) Don't make any unsafe temporary connections, naked joints/wiring etc.
- xxiii) Ensure that temporary cables are free from cuts, damaged insulation, kinks or improper insulated joints.
- xxiv) Check at periodic intervals that pins of sockets and joints are not loose.
- xxv) Protect electrical wires/equipments from water and naked flames.
- xxvi) Illuminate suitably all the work areas.
- xxvii) All switchboards should be of MS structure only and incoming source should be marked.
- xxviii) Hand lamps should not be of more than 24V rating.
- xxix) Fire extinguishers (DCP/CO₂/Sand buckets) should be kept near

temporary switch boards being used for construction purposes. Don't use water for fighting electrical fires.

xxx) Insulating mats shall be provided in the front and back end of switch boards.

xxxi) All parts of electrical installations should be so constructed, installed and maintained as to prevent danger of electric shock, fire and external explosion.

Periodic checking/certification of electrical safety appliances such as gloves, insulating mats, hoods etc. to be done/witnessed along with maintaining a register at site signed by competent authority.

xxxii) A notice displaying following, should be kept exhibited at suitable places:

- a) prohibiting unauthorised persons from entering electrical equipment rooms or from handling or interfering with electrical apparatus;
- b) containing directions as to procedures in case of fire, rescue of persons in contact with live conductors and the restoration of persons suffering from electric shock;
- c) specifying the person to be notified in case of electrical accident or dangerous occurrence, and indicating how to communicate with him.

xxxiii) No other cables/pipes to be laid in trench used for electrical cables.

xxxiv) Utmost care should be taken while excavating Earth from cable trench to avoid damage or any accident.

xxxv) Sub-station floor cut-outs meant for switch board installations to be covered wherever installation is incomplete.

NOTE: A Residual Current Operated Circuit Breaker (RCCB) or Earth Leakage Circuit Breaker (ELCB), when installed, protects a human being to the widest extent. RCCB or ELCB should be provided as per Indian Electricity Rules.

6.11.2 Inspection and maintenance

i) All electrical equipment should be inspected before taking into use to

ensure suitability for its proposed use.

ii) At the beginning of every shift, the person using the electrical equipment should make a careful external examination of the equipment and conductors, especially the flexible cables.

iii) Apart from some exceptional cases, work on or near live parts of electrical equipment should be forbidden.

iv) Before any work is begun on conductors or equipment that do not have to remain live:

- a) the current should be switched off by a responsible authorised person;
- b) precautions should be taken to prevent the current from being switched on again;
- c) the conductors or the equipment should be tested to ascertain that they are dead;
- d) the conductors and equipment should be earthed and short-circuited;
- e) neighbouring live parts should be adequately protected against accidental contact.

v) After work has been done on conductors and equipment, the current should only be switched on again on the orders of a competent person after the earthing and short-circuiting have been removed and the workplace reported safe.

vi) Electricians should be provided with approved and tested tools, and personal protective equipment such as rubber gloves, mats etc.

vii) All conductors and equipment should be considered to be live unless there is a proof of the contrary.

viii) When work has to be done in dangerous proximity to live parts the current should be cut off. If for operational reasons this is not possible, the live parts should be fenced off or enclosed by qualified staff from the sub-station concerned.

6.11.3. Testing

- i) Electrical installations should be inspected and tested and the results recorded.
- ii) Periodic testing of the efficiency of the earth leakage protective devices should be carried out.
- iii) Particular attention should be paid to the earthing of apparatus, the continuity of protective conductors, polarity and insulation resistance, protection against mechanical damage and condition of connections at points of entry.

6.12 OFFSHORE

6.12.1 General

The isolated nature of offshore installations are hazardous. They call for greater need for safety and survival at offshore. Safety at offshore is safety of installations and safety of personnel. Safety problems and accidents at offshore have high risks due to limited space, helicopter operation, sea transport etc. Following are the general safety guidelines to be followed in addition to the safety guidelines stipulated for specific jobs dealt later on:

- i) Workers should be well trained to do their job independently with high degree of self-control and self-discipline.
- ii) On arrival at offshore, everyone should be briefed about the safety rules to be followed at offshore, evacuation system etc. All personnel should wear overall (dangri), helmet and shoes for personnel protection.
- iii) In case of emergency, workers should follow instruction of Field Production Superintendent (F.P.S.) In certain cases instructions may be given to abandon the offshore installation and evacuate the persons to safe location.
- iv) To overcome above problems, offshore personnel must receive training for using life saving appliances and other personal survival techniques.
- v) Any person working at offshore should have one person as standby for any eventuality.

6.12.2 Drilling Rigs

- i) Location of jack up rigs should not be less than 5 Kms from shipping route. Orientation of the rig, wind direction etc are required for safe landing of helicopter. Information w.r.t. sea currents, wind speed, Hi-lo tide etc are required for mooring of supply vessels.
- ii) Sea bed condition at every location should be ensured for safety of rig.
- iii) Radio and other communication facilities should be such to maintain contact with base all times.
- iv) During toeing of rig, the rig deck should be clear of load, toeing lines should be in good condition and tensions in various toeing lines should be constantly monitored.
- v) Few steps during toeing are:
 - a) crane booms should be secured to their vestr,
 - b) all hatches and water tight doors should be closed,
 - c) number of personnel on board should be restricted,
 - d) evacuate in case of emergency and operation should be completed preferably in day light.

6.12.3 Drilling

- i) In view of CO₂ and H₂S gas cut from well, effective ventilation should be provided where drilling is in progress.
- ii) Safety alarm shall be checked in advance in view of failure of ventilation system.
- iii) Suitable sensors for H₂S and Methane should be function tested time to time and suitable colour code should be given.
- iv) Working areas of the crane should be illuminated during night to avoid accident.
- v) Clear space should be available for despatch and receipt of load and, in particular, basket transfer of passengers. Persons engaged in loading/unloading of materials should be protected from falling into the sea.

- vi) Signal light should be fitted at the top of the jib.
- vii) Crane hook should be fitted with safety latches.
- viii) Experienced person should be engaged in operation of specific equipment like winches, cranes etc.
- ix) At least three cable turns shall always be there on the winch drum.
- x) Adequate communication like walkie talkie, round robin phone should be available between the crane operator, supervisor and helper.
- xi) Crane operation should be completely stopped during helicopter landing/taking off.
- xii) Except for helicopter landing deck, all decks, platforms, bridges, ladders should have rigid and fixed guard rails atleast one meter high and should have one intermediate rail midway between the handrail and 100 mm toe board.
- xiii) Wooden ladders shall not be used at offshore.
- xiv) Flow sensor in the flow line should be ensured for safe working and to avoid blow out.
- xv) Hydrogen sulphide gas In offshore is of great risk and at 10 ppm (0.001%) concentration in air, a person should not be exposed for more than 8 hours, If concentration is more, then breathing apparatus should be used. Corrosion of equipment is also caused by H₂S.
- xvi) Portable H₂S gas detector should be continuously used.

6.12.4 Production Platforms

- i) In case hydrocarbon is released due to overpressure, leak, overflow, gas blow etc., shut down process to stop flow of hydrocarbon. Prevent ignition of released hydrocarbon and in case of fire shut in the process complex and follow emergency contingency plan.
- ii) Sub surface safety valve (SSSV) below the well head should be actuated during uncontrolled well - flow and they should be regularly checked.

- iii) Surface safety valve or SDV should be checked for no gas leakage from bleed port / flange etc., in the well head area. It should not be in "mechanical override" or bypassed from panel.
- iv) High pressure gas lift lines - blowdown system should be O.K.
- v) Auto actuation of SDVs in the inlet of pressure vessels should be O.K. and in "normal position" from shutdown panels. A record of status of switches normal/bypassed in auto-con* panels (PSH, PSL, LSL, ILSL) should be maintained.

* Shut Down Panels

- vi) Welders rectifier set and electrical connections to it should be checked and approved by electrical-in-charge for proper electrical safety.
- vii) "SCADA" telemetry system if available should be operational for remote opening and closing of wells at unmanned platforms (through RPMC).
- viii) Local ESD/FSD (near the work site) should be provided for jobs of very critical nature, so that the persons working can access it immediately in emergency for safety. Safety officer should judge the requirement & inform FPS for the same.
- ix) Railings and Gratings etc. in and around work area should be O.K. and inspected to avoid slippage of man into sea.
- x) Emergency shut down (ESD) system is initiated when an abnormal condition is detected. ESD should be checked once in six months.
- xi) Platform should be manned round the clock.
- xii) Welding and cutting work should be regulated by hot work permit.
- xiii) All detectors should be calibrated as per recommendation of the manufacturer.
- xiv) No system should be by-passed which affects the system of platform.

- xv) In H₂S field platforms, due care shall be taken as per recommendations.
- xvi) Follow the instructions of F.P.S. during stay at platform

6.12.5 Fire Prevention And Control

- i) Provision be made for safe handling and storage of dirty rags, trash, and waste oil. Flammable liquids and chemicals applied on platform should be immediately cleaned.
- ii) Paint containers and hydrocarbon samples, gas cylinders for welding and cutting should be stored properly. Cylinders should be transported in hand-cart.
- iii) Smoking should be restricted and no smoking area should be identified.
- iv) Special attention should be given to crude oil pump seals, diesel and gas engines which are potential source of ignition in the event of failure.
- v) Fire and smoke detectors i.e. ultraviolet heat, thermal and smoke detector should be function tested once in three months.
- vi) Fire is controlled in offshore by water spraying, Halon, CO₂ flooding, DCP and sprinkler system.
- vii) Foaming agent is applied for controlling fire in liquid hydrocarbon. The system is not effective in gas fire.
- viii) Light weight breathing system should be used.
- ix) The fire control plan at offshore should reveal control station, fire alarms and fire detectors, deluge valves and sprinkler, fire extinguishing appliances, fireman outfit and ventilation system.
- x) Fire fighting equipment should be maintained in ready to use condition.

6.12.6 Life Saving Appliances

- i) Life boats with a speed of 6 knots and carrying capacity upto 50 persons are used in offshore.
- ii) No. of life boats on one installation should have a capacity to

accommodate twice the number of persons onboard installation.

- iii) Launching appliances and life boat equipment should be checked every week.
- iv) Boat landing areas should be adequately illuminated.
- v) Life raft has no power and they rely on drift.
- vi) Life jacket lifts the wearer after entering water.
- vii) Life buoys are used to rescue persons if any person accidentally falls in the sea.
- viii) All life saving appliances should be inspected by the MMD surveyor /sr. officials once a year.
- ix) Every life boat shall be inspected once a week.
- x) Every life boat and life raft should be serviced once a year by a competent authority,

6.12.7 Safety Precautions during Helicopter Transportation

- i) Passenger briefing regarding safety rules while travelling in helicopter should be carried out before boarding the helicopter.
- ii) Emergency procedure should be briefed to all the passenger In case helicopter is to ditch into the sea.
- iii) Heli-pad should have a non-skid surface. Nylon rope net should be stretched on the deck.
- iv) Proper drainage should be available on helideck.
- v) There should be no obstruction on the helideck itself and within 3 meters of its parameter. Closest super structure above the helideck should have red obstruction light.
- vi) While landing fire crew of two persons should be standby adjacent to helideck.
- vii) Heli-deck should be properly illuminated for night landing.
- viii) During switching off helicopter, persons should not be allowed to go out/ towards helicopter

6.13 DEMOLITION

6.13.1. General provisions

- i) When the demolition of any building or structure might present danger to workers or to the public:
 - (a) necessary precautions, methods and procedures should be adopted, including those for the disposal of waste or residues;
 - (b) the work should be planned and undertaken only under the supervision of a competent person.
- ii) Before demolition operations begin:
 - (a) structural details and builders' drawings should be obtained wherever possible;
 - (b) details of the previous use should be obtained to identify any possible contamination and hazards from chemicals, flammables, etc.;
 - (c) an initial survey should be carried out to identify any structural problems and risks associated with flammable substances and substances hazardous to health. The survey should note the type of ground on which the structure is erected, the condition of the roof trusses, the type of framing used in framed structures and the load-bearing walls;
 - (d) a method of demolition should be formulated after the survey and recorded in a method statement having taken all the various considerations into account and identifying the problems and their solutions;
- iii) All electric, gas, water and steam service lines should be shut off and, as necessary, capped or otherwise controlled at or outside the construction site before work commences.
- iv) If it is necessary to maintain any electric power, water or other services during demolition operations, they should be adequately protected against damage.
- v) As far as practicable, the danger zone round the building should be adequately fenced off and sign posted. To protect the public a fence 2m high should be erected enclosing the demolition operations and the access gates should be secured outside working hours.
- vi) The fabric of buildings contaminated with substances hazardous to health should be decontaminated. Protective clothing and respiratory devices should be provided and worn.
- vii) Where plant has contained flammable materials, special precautions should be taken to avoid fire and explosion.
- viii) The plant to be demolished should be isolated from all other plant that may contain flammable materials. Any residual flammable material in the plant should be rendered safe by cleaning, purging or the application of an inert atmosphere as appropriate.
- ix) Care should be taken not to demolish any parts, which would destroy the stability of other parts.
- x) Demolition activities should not be continued under adverse climatic conditions such as high winds, which could cause the collapse of already weakened structures.
- xi) To prevent hazards parts of structures should be adequately shored, braced or otherwise supported.
- xii) Structures should not be left in a condition in which they could be brought down by wind pressure or vibration.
- xiii) Where a deliberate controlled collapse technique is to be used, expert engineering advice should be obtained, and:
 - (a) it should only be used where the whole structure is to come down because it relies on the removal of key structural members to effect a total collapse;
 - (b) it should only be used on sites that are fairly level and where there is enough surrounding space for all operatives and equipment to be withdrawn to a safe distance.
- xiv) When equipment such as power shovels and bulldozers are used for

demolition, due consideration should be given to the nature of the building or structure, its dimensions, as well as to the power of the equipment being used.

- xv) If a swinging weight is used for demolition, a safety zone having a width of at least one-and-a-half times the height of the building or structure should be maintained around the points of impact.

6.13.2. Demolition of structural steelwork

- i) All precautions should be taken to prevent danger from any sudden twist, spring or collapse of steelwork, ironwork or reinforced concrete when it is cut or released.
- ii) Steel construction should be demolished tier by tier.
- iii) Structural steel parts should be lowered and not dropped from a height.

6.14 RADIOGRAPHY

- 6.14.1 All radiography jobs shall be carried out as per BARC Safety Regulations
- 6.14.2 During field radiography, nearby area around the radiation source should be cordoned off.
- 6.14.3 If the field radiography is to be done at the same location repeatedly, it is advisable to provide either a wire fencing around or a temporary brick enclosure.
- 6.14.4 Special permission/permit should be taken for radiography from area-in-charge.
- 6.14.5 As far as possible, field radiography should be done only during night time when there is little or no occupancy there.
- 6.14.6 Radiation warning signals should be pasted all along the cordoned off area.
- 6.14.7 Entry into the restricted area by unauthorised persons should be strictly prohibited during exposure.
- 6.14.8 The radiation level alongwith the cordon should be monitored by a suitable and well-calibrated radiation survey meter.

- 6.14.9 All personnel working with radiography sources should wear appropriate protective equipment and film badges issued by BARC.

- 6.14.10 Protection facilities such as manipulator rod, remote handling tongs, lead pots, radiation hazard placards and means of cordon off shall be available at each site.

- 6.14.11 The radiography source shall never be touched or handled directly with hands.

- 6.14.12 The package containing radiography cameras and sources should never be carried by public transport like bus, train etc.

- 6.14.13 Radiography sources and cameras, when not in use, should be stored inside a source pit with lock and key arrangement as approved by BARC. The storage room should preferably be located in an isolated area of minimum occupancy and radiation level outside the storage room should not exceed 0.25 mR/hr as per BARC Regulations.

- 6.14.14 In case of an accident (due to loss or of damage to radiography source), action should be taken in line with BARC Safety Rules/Guidelines.

6.15 SAND/SHOT BLASTING/ SPRAY PAINTING

- 6.15.1 Sand blasting should be used only after approval from competent person.

- 6.15.2 Air Compressor used for sand/shot blasting/painting should have guard and positioned away from the work place.

- 6.15.3 Exhaust of the prime mover, if IC engine is used, should be directed away from the work place.

- 6.15.4 In case of motor driven compressor, the body of the motor as well as the compressor to be properly earthed.

- 6.15.5 The hoses used for compressed air should be of proper quality, and health of the same to be ensured through regular check/ test.

- 6.15.6 The operator of sand/shot blasting/painting should wear suitable PPE's including mask.
- 6.15.7 Adequate measures to be taken to suppress dust/spray particle.
- 6.15.8 Sand used for sand blasting should be suitably covered & protected from rain/moisture.
- 6.15.9 When these activities are done in confined places, adequate measure to be taken for proper ventilation.

6.16 WORK ABOVE WATER

6.16.1 General Provisions

- i) Where work is done over or in close proximity to water & where possibility of drowning exists, provision should be made for:
 - a) Preventing workers from falling into water;
 - b) The rescue of workers in danger of drowning;
 - c) Safe and sufficient transport.
- ii) Provisions for the safe performance of work over or in close proximity to water should include, where appropriate, the provision and use of suitable and adequate:
 - a) fencing, safety nets and safety harnesses;
 - b) lifebuoys, life jackets and manned boats;
 - c) protection against such hazards as reptiles and other animals.
- iii) Gangways, pontoons, bridges, footbridges and other walkways or work places over water should:
 - a) possess adequate strength and stability;
 - b) be sufficiently wide to allow safe movement of workers;
 - c) have level surfaces free from tripping hazards;
 - d) be adequately lit when natural light is insufficient;
 - e) where practicable and necessary, to prevent danger, be provided with toe-boards, guard rails, hand ropes etc.
 - f) be secured to prevent dislodgment by rising water or high winds;
 - g) if necessary, be equipped with ladders which should be sound, of sufficient strength and length and be securely lashed to prevent slipping.

- iv) All deck openings including those for buckets should be fenced.

6.16.2 Rescue & Emergency procedures

- i) Persons who work over water should be provided with some form of buoyancy aid. Life jackets should provide sufficient freedom of movement, have sufficient buoyancy to bring persons to the surface and keep them afloat face upwards, be easily secured to the body, be readily visible by way of self luminous paint/strip.
- ii) Nobody should work alone on or above water.
- iii) Each worker should be trained in the procedure to be followed in the event of an emergency.

7.0 ADDITIONAL SAFETY PRECAUTION FOR UNITS WITH HYDROCARBONS

In addition to general safety precautions as outlined above for the activities in Clause 6.0, following additional safety precautions need to be taken for the sites within the operating area or nearby, where presence of Hydrocarbons cannot be ruled out.

- i) No job shall be carried out without a valid permit. Permit should be in line with OISD-STD-105 "Work Permit System".
- ii) Smoking should be prohibited in all places containing readily combustible or flammable materials and "No Smoking" notices be prominently displayed.
- iii) In confined spaces and other places where flammable gases, vapours or dusts can cause danger, following measures should be taken:
 - (a) only approved type electrical installations and equipment, including portable lamps, should be used;
 - (b) there should be no naked flames or source of ignition;
 - (c) oily rags, waste and clothes or other substances liable to spontaneous ignition should be removed without delay to a safe place;
 - (d) ventilation should be provided.

- iv) Regular inspections should be made of places where there are fire risks. These include the vicinity of heating appliances, electrical installations and conductors, stores of flammable and combustible materials, welding and cutting operations.
- v) Welding, flame cutting and other hot work should only be done after issuance of work permit in line with the requirement of OISD-STD-105 after appropriate precautions, as required, are taken to reduce the risk of fire. For carrying out other jobs also, OISD-STD-105 should be followed strictly.
- vi) Fire-extinguishing equipment should be well maintained and inspected at suitable intervals by a competent person. Access to fire-extinguishing equipment such as hydrants, portable extinguishers and connections for hoses should be kept clear at all times.
- vii) All supervisors and a sufficient number of workers should be trained in the use of fire-extinguishing equipment, so that adequate trained personnel are readily available during all working periods.
- viii) Audio means to give warning in case of fire should be provided where this is necessary to prevent danger. Such warning should be clearly audible in all parts of the site where persons are liable to work. There should be an effective evacuation plan so that all persons are evacuated speedily without panic and accounted for and all plant and processes shut down.
- ix) Notices should be posted at conspicuous places indicating:
 - (a) the nearest fire alarm;
 - (b) the telephone number and address of the nearest emergency services.
- x) The work site shall be cleared of all combustible materials, as Sparks and molten metal coming from the welding job can easily ignite combustible materials near or below the welding site. If the combustible materials cannot be removed from the area, the same shall be properly shielded.
- xi) A dry chemical type fire extinguisher shall be made available in the work area. Also fire protection facilities like running hoses etc. as per permit should be complied with.
- xii) Wherever required, welding screens shall be put up to protect other equipment in adjoining areas against flying sparks. Material used should be metal/asbestos/water curtain.
- xiii) Welding or cutting of vessels/ equipments used in Hydrocarbon/ hazardous chemicals shall be done after proper gas freeing and verifying the same with the explosive-meter.
- xiv) The confined space/equipment shall be gas freed and cleaned.
- xv) Absence of any toxic gas and any flammable gas above explosion limit shall be ensured with the help of gas detection instrument and explosive meter respectively.
- xvi) Used and hot electrode stubs shall be discarded in a metal bucket.
- xvii) Use approved and certified flame arrestors for vehicles.
- xviii) Work permit to be obtained, if construction work is carried out within existing operating area.

8.0 FIRST AID

First aid facilities should be provided in line with various statutory regulations like factory act etc. However following care should be taken:

- i) First aid, including the provision of trained personnel should be ensured at work sites. Arrangement should be made for ensuring the medical attention of the injured workers. First aid box should be as per the Factory rules.
- ii) Suitable rescue equipment, like stretchers should be kept readily available at the construction site.
- iii) First-aid kits or boxes, as appropriate and as per statutory requirements, should be provided at workplaces and be protected against contamination by dust, moisture etc.

- iv) First-aid kit or boxes should not keep anything besides material for first aid in emergencies.
- v) First-aid kits and boxes should contain simple and clear instructions to be followed, be kept under the charge of a responsible person qualified to render the first aid and be regularly inspected and stocked.
- vi) Where the work involves risk of drowning, asphyxiation or electric shock, first-aid personnel should be proficient in the use of resuscitation and other life saving techniques and in rescue procedures.
- vii) Emergency telephone numbers of nearby Hospitals, Police, Fire Station and Administration should be prominently displayed.

9.0 DOCUMENTATION

The intention of keeping documentation of all types of accident(s) is to prevent recurrence of similar accident(s). All accidents should be reported as per OISD Guidelines (OISD-GDN-107) and Factories act, 1948.

All accidents (major, minor or near miss) should be investigated, analysed and recommendations should be documented along with implementation status.

All related data should be well-documented and further analysis highlighting the major cause(s) of accidents be done. This will help in identifying thrust areas and training needs for prevention of accidents.

10.0 SAFETY AWARENESS & TRAINING

Safety awareness to all section of personnel ranging from site-in-charge to workmen helps not only preventing the risk but also build up the confidence. Time and expenditures also get saved as a result.

Safety awareness basically seeks to persuade/inform people on safety besides supplementing skill also. Awareness programme may include followings:

- i) **Poster:** Posters with safety slogan in humorous, gruesome demonstrating manner may be used to discourage bad habits attributable to accidents by appealing to the workers' pride, self-love, affection curiosity or human aspects. These should be displayed in prominent location(s).
- ii) **Safety Sign Boards:** Different type of message of cautioning, attention, notice etc. should be displayed at the appropriate places for learning/awareness of the workmen while working at site.
- iii) **Films & Slides:** Film(s) narrating the accident including the causes and possible remedial ways of preventing the recurrence of a similar accident should be displayed at regular intervals. Slides consisting main points of the film show may also be shown to workers.
- iv) **Talks, lectures & conferences:** The success of these events would depend much on audience's understandings of the speaker (s). The speakers are to be knowledgeable and good presenter. Speakers should know to hold the attention and to influence the audiences.
- v) **Competitions:** Organise competition(s) between the different deptts/categories of workers. The sense of reward/recognition also will improve safety awareness and result in enhancing safety levels.
- vi) **Exhibitions:** Exhibitions also make the workers acquainted with hazards and means of preventive measures.
- vii) **Safety Publication:** Safety publications including pocket books dealing with ways of investigation and prevention in the field of safety and so on, may be distributed to workers to promote the safety awareness.
- viii) **Safety Drives:** From time to time, an intensive safety drive by organising a safety day or a safety week etc. should be launched.
- ix) **Training:** Training for covering the hazards for different trade should be imparted. Training should also include the specific hazards related

to a job in addition to the general safety training as has been dealt in various chapters and should include all workers. Reference may be drawn from OISD-STD-154.

11.0 REFERENCES

- i) *Factory Act, 1948*
- ii) *Indian Electricity Rules*
- iii) *Safety & Health in Construction by ILO*
- iv) *The Building & Other Construction Workers (Regulation, Employment and Conditions of Service) Act 1996*

**LIST OF SAFETY CODES FOR CIVIL WORKS PUBLISHED BY BUREAU OF
INDIAN STANDARDS**

Sr.no	Code No.	Title
01.	IS : 818	Code of Practice for Safety and Health Requirements in Electric and Gas Welding and Cutting Operations – First Revision.
02.	IS : 875	Code of practice for Structural safety of buildings: Masonry walls
03.	IS : 933	Specification for Portable Chemical Fire Extinguisher, Foam Type – Second Revision.
04.	IS : 1179	Specification for Equipment for Eye and Face Protection during Welding – First Revision.
05.	IS : 1904	Code of practice for Structural safety of buildings: Shallow foundations
06.	IS : 1905	Code of practice for Structural safety of buildings: Masonry walls
07.	IS : 2171	Specification for Portable Fire Extinguishers, Dry Powder Type – Second Revision.
08.	IS : 2361	Specification for Building Grips – First Revision.
09.	IS : 2750	Specification for Steel Scaffoldings.
10.	IS : 2925	Specification for Industrial Safety Helmets – First Revision.
11.	IS : 3016	Code of Practice for Fires Precautions in Welding and Cutting Operations – First Revision.
12.	IS : 3521	Industrial safety belts and harnesses
13.	IS : 3696 – Part I	Safety Code for Scaffolds and Ladders : Part I – Scaffolds.
14.	IS : 3696 – Part II	Safety Code for Scaffolds and Ladders : Part II – Ladders.
15.	IS : 3764	Safety Code for Excavation Work.
16.	IS : 4014 -Part I & II	Code of practice for Steel tubular scaffolding
17.	IS : 4081	Safety Code for Blasting and Related Drilling Operations.
18.	IS : 4082	Recommendations on staking and storage of construction materials at site
19.	IS : 4130	Safety Code for Demolition of Buildings – First Revision.
20.	IS : 4138	Safety Code Working in Compressed Air-First Revision
21.	IS : 4756	Safety code for Tunneling works
22.	IS : 4912	Safety requirements for Floor and Wall Openings, Railings and toe Boards –First Revision.
23.	IS : 5121	Safety Code for Piling and other Deep Foundations.
24.	IS : 5916	Safety Code for Construction involving use of Hot Bituminous Materials.
25.	IS : 5983	Specification for Eye Protectors – First Revision.
26.	IS : 6922	Structures subject to underground blasts, criteria for safety and design of
27.	IS : 7155	Code of recommended practices for conveyor safety
28.	IS : 7205	Safety Code for Erection on Structural Steel Works.

Sr.no	Code No.	Title
29.	IS : 7069	Safety Code for Handling and Storage of Building Materials.
30.	IS : 7293	Safety Code for Working with Construction Machinery.
31.	IS : 7323	Guidelines for operation of Reservoirs
32.	IS : 7969	Safety code for handling and storage of building material
33.	IS : 8758	Recommendation for Fire Precautionary Measures in construction of Temporary Structures and Pandals.
34.	IS : 8989	Safety Code for Erection of Concrete Framed Structures.
35.	IS : 9706	Code of Practices for construction of Arial ropeways for transportation of material
36.	IS : 9759	Guidelines for de-watering during construction
37.	IS : 9944	Recommendations on safe working load for natural and man-made fibre roap slings
38.	IS : 10291	Safety code for dress divers in civil engineering works
39.	IS :10386 – Part I	Safety Code for Construction, Operation and Maintenance for River Valley Projects.
40.	IS :10386 – Part II	Safety Code for Construction, Operation and Maintenance of River Valley Projects.
41.	IS : 11057	Code of practice for Industrial safety nets
42.	IS : 13415	Code of Practice on safety for Protective barriers in and around building
43.	IS : 13416	Recommendations for preventive measures against hazards at working places

OISD – GDN – 207

**FOR RESTRICTED
CIRCULATION ONLY**

OCTOBER 2002

CONTRACTOR SAFETY

OISD – GUIDELINES – 207

**Oil Industry Safety Directorate
Government of India
Ministry of Petroleum & Natural Gas**

CONTRACTOR SAFETY

CONTENTS

SECTION	DESCRIPTION
1.0	INTRODUCTION
2.0	SCOPE
3.0	DEFINITIONS
4.0	DUTIES / RESPONSIBILITIES
4.1	Owner
4.2	Contractor
4.3	Consultant
4.5	Designer
5.0	SAFETY MANAGEMENT
5.1	Job Safety Analysis (JSA)
5.2	Criteria of a Selection of a Contractor
5.3	Site Planning and Layout
5.4	Gate Entry Procedure
5.5	Training
5.6	Inspection / Audit
5.7	Penalties for non-compliance
5.8	Incident Reporting and Investigation System
5.9	Safety Committee Meetings
5.10	Safety Equipment / Personnel Protective Equipment
6.0	REFERENCES
	ANNEXURE I List of BIS codes / Statutory Regulations
	ANNEXURE II Checklist for Safety Inspection / Audit

CONTRACTOR SAFETY

1.0 INTRODUCTION

Oil and Gas operations like Drilling, Production, Refining, Transportation and Distribution are inherently hazardous. A large number of contractor workforce is deployed to carry out construction, maintenance and other jobs. The analysis of the incidents in the Petroleum Sector indicates that a large number of incidents involved contractor workforce and have resulted in either casualty or injury besides leading to property damage and operational interruptions and environmental degradation.

In order to improve the safety levels of oil installations, the contractor safety is of utmost importance and there is a need to institute a good contractor safety system.

2.0 SCOPE

This standard covers broadly the guidelines on the management system for enhancing the safety levels of the contractor workforce deployed in construction, maintenance and operation activities in the hydrocarbon industry.

The safety precautions to be taken while carrying out different activities during construction / maintenance have separately been covered in OISD-GDN-192 on "Safety Practices during Construction".

3.0 DEFINITIONS

Work station/Work site

A place/unit where the job is carried out by contractor/executing agency in specified manner with safety, during construction phase or in operation phase.

Owner

Any physical or legal person/entity for whom prescribed job is carried out.

It shall also include owner's designated representative / consultant /nominee / agent, authorised from time to time to act for and

on its behalf, for supervising / co-ordinating the activities of the contractor/execution agency.

Contractor / Executing Agency

A physical or legal person/entity having contractual obligation with the owner, and who deploys one or more worker on the site.

Contractor Worker

It covers all workmen who are either self-employed or employed through contractor, the casual workers and includes contractor's supervisor, working at a location / site employed directly by Owner or through their contractor.

Incident

An incident is an unplanned, uncontrolled, unintended or unforeseen event, caused by unsafe acts and / or unsafe conditions, resulting in or having the potential to result in personal injury and/or property damage.

Consultant

Consultant is a physical or legal person/entity engaged by owner to provide the consultancy services to owner for management of the contract on their behalf or as specified.

Designer

Designer is a physical or legal person / entity engaged by owner to provide design services of a work site.

Owner's Representative / Engineer In Charge

The Owner's representative/Engineer-in-charge is the one, who has been designated by the owner to manage the contract.

Owner's Safety Officer

A properly trained person designated by owner who ensures safety at work site.

4.0 DUTIES/ RESPONSIBILITIES

4.1 OWNER

4.1.1 Owner's Management

The commitment to safety has to be emphasised by the owner by practice by its own management and employees at all levels. The duties and responsibilities of owner should include:

- i) To institute a mechanism for identification and compliance of all applicable statutory rules & regulations (Refer Annexure I for a list of few important Bureau of Indian Standards & statutory regulations).
- ii) To provide specific information to contractors and make workers aware on the hazards associated with job assigned.
- iii) To provide information about Risk Mitigation measures available at the place of work.
- iv) To provide the contractor with information on Owners Safety Plan & Regulations, Emergency Management Plan, lockout/ tag out procedure, confined space entry, work permit system, excavation/trench permit system etc.
- v) To specify rules (e.g. for security including access arrangements) and safety rules such as fire protection, first aid arrangements, Work Permit systems etc.
- vi) To provide comprehensive list of statutory regulations / standards and specification, to be complied with during execution of contract, in the tender document itself.
- vii) To ensure training of the contractor workforce, medical examination, and proper usage of safety equipment.

viii) To specify the requirements of Health, Safety and Environment (HSE) (commensurate with the nature of job) in Pre- Qualification criteria.

ix) To designate Engineer-in-charge and safety officer.

x) To arrange for a multi-disciplinary safety audit team to conduct surprise / regular safety audits and monitor the implementation of the recommendations.

xi) To introduce suitable schemes for motivation of the contractor worker to adhere to safety guidelines.

xii) To review safety practices & their implementation through periodic surprise visit of the work sites and monthly review meeting.

xiii) To develop the HSE plans and incorporate the same in the tender document.

xiv) To liaise with external agencies like press, public etc and with law enforcement, regulatory, statutory agencies etc.

xv) To report to statutory agencies on safety compliance and accidents, if any.

4.1.2 Owner's Representative/Engineer-in-charge

The duties & responsibilities of engineer-in-charge should include:

- i) To ensure that all Contract requirements including Health, Safety, Environment & Security are complied with.
- ii) To ensure that contractor workforce deployed is adequately qualified, trained and in state of health to commensurate with the requirements of the job.
- iii) To ensure that the Tools / Tackles and Machinery being used are properly

tested and are in sound working conditions and necessary resources proposed for providing safe place of work and necessary PPE are being used.

- iv) To take the required necessary corrective action immediately upon noticing or receipt of a report on noncompliance or any such condition which poses a threat to health, safety or environment. If during the course of execution of the contract, any situation of non-compliance with the contractor's safety and health plan are noticed / reported, the same will be taken up with the contractor for correction. In the event of repeated non compliance, suitable action to be initiated as per the contract.
- v) To ensure that the incidents are reported to all concerned within stipulated timeframe.
- vi) To ensure submission of a plan for safe working (Method Statement) from contractor and approval of the same by competent person / department.
- vii) To ensure that Work Permit System in line with OISD-STD-105 is adhered to.
- viii) To ensure availability of all the documentation needed for the execution of contract.
- ix) To ensure that the quality controls have been maintained during fabrication/erection and all jobs required for safe commissioning have been carried out.
- x) To ensure safe dismantling of all temporary facilities/connections put up by the contractor, after completion of work.
- xi) To compile a report on the safety performance (at the conclusion of each contract or periodically such as annually for renewable and long-term

contracts), which is to be considered in future when selecting contractors.

- xii) To ensure that the Consultant, contractor and sub-contractor employ / designate qualified & trained Safety Engineer / Officer commensurate with requirement of the job.

4.1.3 Owner's Safety Officer

The duties & responsibilities of the Owner's Safety Officer should include:

- i) To assess the hazards associated with jobs in consultation with all concerned and establish safe working procedure including identification of the escape routes.
- ii) To establish a written record of factors which can cause injuries and illnesses.
- iii) To undertake routine/surprise inspections of all work sites and identify unsafe conditions & practices, if any. Check for compliance of the safety practices being followed with approved HSE Plan.
- iv) To investigate promptly the incidents (including near-miss) in order to advise corrective and/or preventive action.
- v) To maintain statistical information for use in analyzing all phases of incidents and events involving contract personnel.
- vi) To provide the means for complying with the reporting requirements for occupational injuries and illnesses.
- vii) To check whether the proposed working arrangements are safe and satisfactory, particularly at the interface between the contractor's planned work and owner's existing facilities.
- viii) To communicate to the Contractor the imposed restrictions which may affect the work/personnel such as the temporary closure of a corridor or electrical isolation of equipment.

- ix) To review and monitor the contractor's adherence to approved HSE plan and all applicable environmental, health, and safety requirements.
- x) To ensure that Consultant, Contractor's Managers, Supervisors and workmen at all levels (who will plan, monitor, oversee and carry out the work) undergo Health, Safety and Environmental training in their respective responsibilities with respect to conducting work safely and with due regard for the protection of the environment.
- xi) To identify areas of operations where specialized training is required to deal with potential dangers.
- xii) To document and to bring to the attention of the Owner's Supervisor and Contractor any non-compliance/violation of the safety norms against approved safety and health plan or safety and health requirements and also raise these issues in the Safety Committee Meetings.
- xiii) To take part in Tool Box Meetings at random and to ensure maintenance of records.

4.2 CONTRACTOR

4.2.1 Contractor's Management

Duties & responsibilities of the contractor should include the following:

- i) To implement safe methods and practices, deploy appropriate machinery, tools & tackles, experienced supervisory personnel and skilled work force etc. required for execution.
- ii) To prepare a comprehensive and documented plan for implementation, monitoring and reporting of Health, Safety and Environment (HSE) and implement the same after its approval.

- iii) To nominate qualified & trained Safety Engineers / Officers reporting to the Site in charge, for supervision, co-ordination and, liaison for the implementation of the safety plan.

Similar HSE Plan should be implemented at the sub- contractor's or supplier's site /office. However the compliance with the HSE Plan is to be the sole responsibility of the Contractor.

- iv) To arrange suitable facilities in liaison with the owner for drinking water, toilets, lighting, canteen, crèche etc as applicable as per Laws/ Legislation at site and also arrange for workmen compensation insurance, third party liability insurance, registration under ESI / PF act etc as applicable.
- v) To arrange for fire protection equipment as per the advice of owner.
- vi) To ensure that its employees have completed appropriate health and safety training as required by the statute / regulation and also as per requirements of the Owner / Consultant. The documentation of such training imparted to all its employees should be maintained and produced for verification as required.
- vii) To comply with all the security arrangements of owner.
- viii) To ensure that the plant and equipment used on-site by him / his employees is correctly registered, controlled and maintained in sound working condition.
- ix) To ensure availability of First Aid boxes and First Aid trained attendant.
- x) To ensure that all incidents including near misses are reported to all concerned immediately.

In construction projects where sub-contractors are engaged, the contractor should set out the responsibilities, duties and safety measures that are expected of

the sub-contractor's workforce. These measures should include the provision and use of specific safety equipment, methods of carrying out specific tasks on safety and the inspection and appropriate use of tools.

The responsibilities indicated separately under contractor's Supervisor, Safety Officer and contract worker are contractually that of the Contractor and legally binding on the Contractor only. However the specific detailing as above has been given separately for guidance and operational convenience.

The selection of sub contractors, if employed, should be approved by the owner. Sub-contractor should comply fully with all safety rules and conditions applicable to the main contractor.

4.2.2 Contractor's Supervisor / Safety Officer

Duties & responsibilities of the Contractor's supervisor/Safety Officer should include the following:

- i) To ensure strict compliance with work permit system by carrying out work only with appropriate work permits and after ensuring that all safety precautions / conditions in the permit are complied with and closing the same after job completion.
- ii) To ensure that required guards and protective equipment are provided, used, and properly maintained.
- iii) To ensure that tools and equipment are properly maintained and tested.
- iv) To plan the workload and assign workers to jobs in commensuration with their qualification, experience and state of health.
- v) To ensure that the workers understand the work to be done, the hazards that may be encountered, and the proper precautions/procedure for carrying out the work safely.
- vi) To take immediate action to correct any violation of safety rules observed or reported.
- vii) To ensure that the workers likely to be exposed to hazardous chemicals/materials have access to appropriate Material Safety Data Sheets (MSDS), wherever applicable, and provide necessary mitigation measures.
- viii) To ensure inspection and certification of all tools (hand operated as well as mechanically operated) being used. Defective tools shall be immediately removed.
- ix) To ensure that appropriate warning signboards or tags are displayed.
- x) To ensure that workers have proper training for their job assignments, including use of appropriate PPE and first aid fire fighting equipment.
- xi) To comply with all applicable safety and health standards, rules, regulations and orders issued by competent authority pertaining to the assigned activities.
- xii) To ensure that sick and/or injured workers receive appropriate first aid and/or medical attention.
- xiii) To report each incident and/or injury in accordance with established procedures and assist in investigation.
- xiv) To take necessary action for correction of any unsafe act / condition at the workplace. However, in case the same is outside the limits of authority, it should be reported to Owner's Engineer-in-charge immediately.
- xv) To conduct daily inspections to ensure compliance with safety standards, codes, regulations, rules and orders applicable to the work concerned.

- xvi) To ensure that workers under their supervision are aware of their responsibilities.
- xvii) To arrange daily tool box meeting and regular site safety meetings and maintain records in the required formats. (Refer Clause 5.9.1)
- xviii) To arrange stand-by supervisor/ worker where situations so demand.
- xix) To develop methods and display banners/posters to inculcate safety consciousness.
- xx) To attend training and ensure participation of his workers for training as per schedule arranged by the Owner / Consultant and keeps himself updated.
- xxi) To keep records of number of persons working at the site.
- xxii) To keep a constant liaison with Engg-in-charge / owners' representative on safety issues.
- xxiii) To maintain accident & nearmiss record in a register.
- xxiv) To ensure that only PPE of the approved type by owner is used at site.

A separate Safety Officer should be assigned, where more than 100 workers are employed at site. For smaller jobs, the supervisor should assume the role of the safety officer also.

4.2.3 Contract workers

The duties & responsibilities of the contractor worker should include the following:

- i) To perform work safely as per the job requirement and instructions.
- ii) To inform all concerned regarding unsafe conditions/acts.

- iii) To wear PPE as stipulated and necessary for the job.
- iv) To inform promptly to their supervisor regarding all work related incidents resulting in personal injury, illness and/or property damage.
- v) To take all necessary and appropriate safety precautions to protect themselves, other personnel and the environment.

4.3 CONSULTANT

The activities and responsibilities covered under the scope of the Owner may be delegated to the consultant in those cases as applicable, based on the respective contract conditions. The primary responsibility of Consultant is to ensure compliance with agreed HSE plan for the contract by the Contractor. However those responsibilities conferred on Owner as Principal employer cannot be delegated to consultant.

Where the consultant's scope involves Engineering and Design, those factors under **Designer** should also be applicable.

In all cases, the Consultant's scope should include submission of latest HSE plans for work under his and Contractor's purview and implementing the same till job completion. It should conform to owner's overall HSE plan. This should include Guidelines and Implementation and Reporting Methodology to be followed with required report formats.

Adequate number of Safety Officers shall be provided by the Consultant with necessary skills required for the work to be performed.

The Consultant shall review the documents submitted by the contractor and advise owner on acceptance as well as advise suitability and number of Contractor's safety officers / supervisors.

4.4 DESIGNER

The Process Designer should identify all hazards and risks likely to be encountered during fabrication, erection including

dismantling, Pre-commissioning, commissioning and Performance run to meet the Guarantees and advise the risk mitigation measures.

All the hazards and safety measures to be adopted while handling Dangerous chemicals and Catalysts should be detailed by the Process Licensor and the same should be again included in the scope of the suppliers. Specific write ups/MSDS should be obtained from Patented single source suppliers also.

Designs should recognize, include and apply safe practice during preparation, construction and subsequent operational use and maintenance after completion of the Project.

All documents including drawings and calculations are to be originated, checked and approved in accordance with latest international codes, standards, specifications and design basis philosophy.

Preferred use of low risk materials, policy on hazardous substances, preferred use of low noise and dust-suppressed equipment etc. should be encouraged.

5.0 SAFETY MANAGEMENT

5.1 JOB SAFETY ANALYSIS (JSA)

Job safety analysis (JSA) provides a mechanism by which the contractor, safety officer or supervisor take a detailed look at how an individual task is performed and its inherent hazards and preventive measures. This procedure helps in integrating accepted safety and health principles and practices into a particular operation. In a JSA, each step of the job is examined to identify potential hazards and to determine the safest way to do the job.

A job safety analysis includes five steps as below:

- Select a job
- Break the job down into a sequence of steps
- Identify the hazards against each of these steps (based on knowledge of

accident, causes of injuries and personal experience) and determine the preventive measures to overcome these hazards

- Apply the controls to the hazards
- Evaluate the controls

5.2 CRITERIA OF SELECTION OF A CONTRACTOR

“Contractor Safety” can be ensured to a large extent if competent agency for execution of assignment or job, based on HSE system agreed upon by owner, is selected. It is necessary to assess his capabilities and competencies to perform work safely.

A databank should be developed for all the contractors for their past performance on HSE aspects. An attempt should also be made to get similar data from other similar industries.

The data required will depend upon complexity involved in the job and type / size of resources required. Format needs to be suitably developed depending upon size, nature of the job & hazard associated therein. The format designed should also take care of the skill required to carry out the job.

Performance review is essential for all type of contractors. It helps in recording actual performance/experience with contractors while the contract is in progress. It is essential that resources agreed as per the contract are reviewed at mobilization stage for ensuring compliance from the day one and thorough effective supervision / monitoring system are at place.

This activity also helps in taking timely action in case of unsatisfactory performance to correct the situation and ensure safe work during execution period and deciding about suitability of the contractor for future jobs.

The periodicity of such performance review will depend upon size/type/complexity of contract. However, the performance should be reviewed at least at mobilisation stage and at the end of the contract.

5.3 SITE PLANNING AND LAYOUT

Before starting the construction/maintenance job at existing workplace in operation or green field locations, following should be ensured: -

- i) Details regarding location of workshop/ fabrication yard, site office, stores, laboratory, electrical installations, placement of construction machinery, medical and welfare facilities, lighting underground and above ground piping route, cable route etc. should be decided prior to commencement of the work in consultation with owner / Consultants and implementation should be ensured. Layout should be displayed at strategic locations.
- ii) The resources required to meet any emergency situations like fire fighting, first aid etc. should be planned and mobilized as per the job requirement.
- iii) The sequence or order in which work to be done and any hazardous operations or processes should be identified.
- iv) Free access to site shall be provided with clear roads, passage, gangways, staircases etc. Access to construction site should be leveled, open and free from any obstructions like construction material or scrap/waste, exposure to hazards such as falling materials, material handling equipment and vehicles. Any pit or ditch shall be covered or barricaded.
- v) Arrangements should be made to maintain good housekeeping at site. Scrap and debris generated out of construction work should be removed/disposed off at a regular interval as directed. Emergency exit should be provided in case of blockade of primary exit.
- vi) Suitable warning notices and also the routes to and from welfare facilities should be displayed prominently.

vii) Pedestrian pathways and routes for vehicular traffic (light/heavy vehicles including material handling equipment) should be earmarked.

viii) Artificial lighting to be provided at places where work continues or workers pass by after sunset or in case natural light is insufficient like confined spaces.

ix) Keep all equipment /machines under cover to prevent them from dust, rain/flood water, heat etc. and follow storage instructions as applicable for each of them.

5.4 GATE ENTRY PROCEDURE

Gate entry at any site / workplace / unit is to be restricted to ensure entry of only authorised persons / vehicles.

5.4.1 Entry procedure for all contractor worker should be as follows:

A. Issuance of Pass

- i) The passes are to be issued after the owner's representative/engineer-in-charge forwards the application of the contractor providing complete details of the workers being engaged. The contractor may be asked to submit Character & Antecedents (C&A) verification of individual worker from concerned authorities.
- ii) With regard to issuance of passes for all vehicles including material handling equipment, owner's representative / engineer-in-charge should forward the application only after ensuring that all documents pertaining to the fitness of the vehicle/equipment and valid driving license of the driver etc. are available.
- iii) The passes should be serially numbered with address, contractor name, identification mark, signature of the worker etc.
- iv) Special colour code for passes should be used for persons entering different

areas like Administrative Block, Unit area, Project Area (wherever applicable).

- v) Contractor workers engaged on routine basis for long periods should be provided with monthly photo pass.
- vi) Special permit is required separately for working beyond normal working hours and holidays.

B. Gate Entry

- i) Entry of the contractor's employees should be permitted with valid gate passes only.
- ii) Entry of contractor's workers should be allowed in presence of authorized representative of contractor.
- iii) Records of persons at the time of entry/exit should be maintained.
- iv) At the entry gate of the location, a physical checking for non-carrying of lighter, matchboxes, explosives etc. should be carried out.
- v) Gate passes/Identity Cards should be displayed on persons at all the times.
- vi) For Mega-projects at existing / operating installations, it is preferable to have a separate gate for entry of contractor workers and also the project areas should be segregated fencing from operational area by fencing / other physical means.
- vii) No vehicle should be allowed to enter in an operational area without proper flame arrestor.
- viii) Awareness on Safety through training / posters etc. highlighting Do's and Don'ts should be spread within entire contractor workforce. Video/Audio tapes on Safety Topics should be played preferably.
- ix) For occasionally engaged labourers such as for material handling etc., spot photograph may be preferably

taken with two copies (one for preparing the pass and other for attachment with gate register). Specific advice and recommendation of User Department may be given due cognizance. Relevant details are to be written. The pass should be collected back at the gate after day's work.

5.4.2 Tank Truck Loading (TTL) Operation :

At the loading / unloading location, a large no. of Tank Trucks of petroleum products enter the installation. Crew members are generally not regular entrants. The procedure should be as follows:

- i) The gate pass should be issued to the individual crew members on written request of the transporter mentioning TT registration nos., License and certificate of training as per MV rule 9.
- ii) Character & Antecedent (C & A) verification of the TTL crew through local police is to be done preferably and record maintained.
- iii) For loading/unloading purpose, register entry at security gate is made before allowing entry into the premises with recording of names of crew members, time of entry, pass Sr. No., TT no. etc.
- iv) For loading/unloading, crew is allowed entry alongwith TT only, after checking of TT from explosive/security point of view.
- v) Out time, invoice no., Destination etc., are recorded while TTs go out of the security gate.

5.5 TRAINING

Training is to educate contractor workforce on various hazards associated with the job/workplace and on the respective preventive / mitigation measures to avoid untoward incidents.

i) Workers should be adequately and suitably:

- (a) informed of potential safety and health hazards to which they may be exposed to at their workplace;
- (b) instructed and trained in the measures available for the prevention, control and protection against those hazards.

ii) No person should be employed in any work at a workplace unless that person has received the necessary information, instruction and training so as to be able to do the work competently and safely. The competent authority should, in collaboration with employers, promote training programs to enable all the workers to read and understand the information / instructions related to safety and health matters.

iii) The information, instruction and training should be given in a language understood by the worker and written, Oral, visual and participative approaches should be used to ensure that the worker has assimilated the information.

iv) Every worker should receive instruction and training regarding the general safety and health measures common to the workplace. This should include:

- (a) general rights and duties of workers at the workplace;
- (b) means of access and egress both during normal working and in an emergency;
- (c) measures for good housekeeping;
- (d) location and proper use of welfare amenities and first aid facilities provided;
- (e) proper use and care of the items of personnel protective

equipment and protective clothing provided to the worker;

- (f) general measures for personal hygiene and health protection;
- (g) fire precautions to be taken;
- (h) action to be taken in case of an emergency;
- (i) requirements of relevant safety and health rules and regulations.

Copies of the relevant safety and health rules, regulations and procedures should be available to workers upon the commencement of and upon any change of employment.

5.5.1 Training Techniques

a) Lectures

This technique should be applied when it is required to transfer information in local language to a large contractor workforce with controlled content and time.

b) Case Study

This is an effective technique based on the presentation of case of real events by Trainer to highlight probable causes like Human Error, ignorance about the job etc.

c) Videos

Videos, an effective technique of communication, should be used to display the right techniques of performing a task in a safe manner and hazards associated with a job.

d) Demonstration at site

Right way to do a job should invariably be demonstrated to workers at the site itself. The right way is also a safe way. Hazards due to wrong procedures, short cuts and their adverse effects etc. should also be highlighted.

5.5.2 Training/Awareness Module and Frequency

A. General Safety Training to all categories of contractor employees should be imparted before induction and annually thereafter. No person should be allowed to enter the installation without undergoing this training. This training program may cover:

- i) Mandatory uses of PPE like Cotton clothes, Helmet, Safety Shoes, Safety Belts etc.
- ii) Probable Hazards
- iii) Important Telephone No / Escape route
- iv) First Aid
- v) Use of Fire extinguisher

The contractor workers, if engaged in operation of the plants/facilities, should be trained in line with Clause No. 4.6 of OISD-GDN-206 on "Safety Management System". For other categories of contractor workers, training modules for different category employees are as follows:

B. Contractor Supervisor

Contractor Supervisor should be trained in accordance with the provision of clause no. 5.1.1.2, 5.2.7, 5.3.10, 5.6.12 and 5.7.8 of OISD-STD-154 on 'Safety Aspects in Functional Training'

C. Contractor Worker

Yearly training programme should be carried out for contractor worker and the records should be maintained. The training programme should cover at least the following:

- i) Worker responsibility for safety of himself and work area.
- ii) Associated hazards with the job and job area including electrical shock hazards.

- iii) Importance of First Aid fire fighting equipment, their use & operations
- iv) Communication system at the installation
- v) Fire / Accident Reporting procedure
- vi) General Safety rules
- vii) Safety Measures during execution of job such as:
 - Welding / Cutting / Grinding
 - Working at height
 - Confined space entry
 - X ray / radiation
 - Erection / Dismantling of scaffolding
 - Tank construction and repairs
 - Handling of chemicals etc.
- viii) Importance & use of PPE
- ix) Emergency Routes
- x) Assembly Points
- xi) Job Specific Training

D. Consultant / Contractor

Awareness program should be carried out for Consultant / Contractor at the time of induction. This program should cover at least the following:

- i) Responsibility of contractor for safety of their personnel and work area
- ii) Hazardous property of Petroleum products and chemical used
- iii) Communication system
- iv) Fire / Accident Reporting procedure
- v) Medical facility available
- vi) Statutory requirements

- vii) Importance of First Aid equipment and required at the site
- viii) Work Permit system
- ix) Direct/ Indirect losses due to accident
- x) Safety Measures while executing the jobs such as:
 - Welding / Cutting / Grinding
 - Working at height
 - Confined space entry
 - X ray / radiation
 - Erection / Dismantling of scaffolding
 - Tank construction and repairs
 - Handling of chemicals etc.
 - electrical jobs
- xi) Safety training needs of their supervisors and workers
- xii) Importance & Use of PPE at the site
- xiii) General Safety rules at the installation

E Security Personnel

Training program should be carried out for Security personnel at the time of induction and annually thereafter and the records should be maintained. The training program should cover at least the following:

- i) Layout of Plant and Facilities
- ii) Vulnerable locations
- iii) Safety regulations (Statutory and in company)
- iv) Fire Protection Facilities and Locations
- v) Role in case of Fire / Disaster
- vi) Emergency Procedure and Drills
- vii) Industrial First Aid
- viii) Use of Personnel Protective Equipment
- ix) Disaster Management Plan

5.6 INSPECTION / AUDIT

Inspection / Audit is a tool to evaluate compliance of all safety requirements. Most of the information could be gathered

through site inspection using ready-made check lists to ensure that contractors / agencies abide by the safety rules and norms while working at operating / construction sites.

A checklist, while carrying out different type of jobs, should be developed based on hazards associated with the job being performed and requirements as per OISD-GDN-192 on "Safety Practices during Construction". Typical format is enclosed at Annexure II, which should be modified to suit the requirement of the site / job to be done.

Before starting the work and at regular intervals thereafter, Contractor's Supervisor/safety Officer and Owner's representative / Engineer-in charge/safety Officer should inspect as per the checklist so prepared to ensure that contractor has prepared to start the work with all safety precaution required for safe execution of job.

5.7 PENALTIES FOR NON-COMPLIANCE

Financial or other type of penalties like seizure of gate passes, stoppage of work for a limited period etc. may be levied on the contractors or their workers for non-compliance of safety rules. A provision of suitable accident severity based penalty clause for contractor may be incorporated to ensure adherence of systems and procedures. A few of the usual non-compliance are as follows:

- Non-usage of PPEs like Safety helmet / Safety shoes / Safety goggles / Respiratory protection etc. by the contractor personnel
- Non-usage of the safety belt and life line by the workers while working at height
- Non-provision of basic safety requirement such as 24 V lamp for working in confined space, uncertified / non standard lifting tools, earth leakage protection & earthing connections for electrical appliances as per Indian Electricity Rules, emergency isolation switches etc.

- Violation of Safety Permit conditions like Fire fighting equipment
- Non-barricading of area while rigging, digging etc.
- Working without valid work permit
- Unauthorised road closure/blockage

5.8 INCIDENT REPORTING AND INVESTIGATION SYSTEM

All the incidents including near-miss should be reported immediately by contractor's Supervisor to Contractor and owner's Supervisor/Engineer-in-charge, who should inform to Owner's Safety Officer and owner's Management. Owner's Safety Department will be required for onward reporting as per OISD, Statutory requirements.

All accidents regardless of the extent of injury or damage should be investigated in order to find probable causes, lessons learnt thereof and remedial measures required to prevent its recurrence.

The incident investigation should be done as per provision of clause no. 4.12 of OISD-GDN-206 on 'Safety Management System'. All the recommendations of investigation / Enquiry Report need to be monitored closely for its implementation. A proper record needs to be maintained to ensure implementation of all the recommendations and same should be reviewed from time to time.

5.9 SAFETY COMMITTEE MEETINGS

Following three type of safety committee meetings should be held aiming at raising the level of safety consciousness at the site:

5.9.1 Toolbox meeting

To maintain awareness, update training and convey important safety and health information, contractor supervisors should conduct tool box meetings at least weekly and also prior to start of any work. All the contractor workers should attend this meeting. The owner's supervisor/Engineer-in-charge and safety officers should also

attend these meetings on random basis. Tool box meeting should be conducted more frequently depending upon circumstances. Record of the same can be maintained in the following typical format.

TOOLBOX MEETING FORM

SUBJECT :
 PRESENTER :
 DATE :
 TIME : From..... To.....
 CONTENT IN BRIEF :

Participant's Name	Signature
-----	-----
-----	-----
-----	-----

5.9.2 Site Safety Committee Meeting

Primary purpose of this safety committee is to enable owner, contractor and workers to work together to monitor the site safety and health plan so as to prevent accidents and improve working condition on site. Its size and membership will depend on the size and nature of job.

The safety committee should include representatives of owner, consultant, contractor identified as safety officer/supervisor. It should be headed by Engineer-in-charge.

The safety committee should have regular and frequent meetings, atleast fortnightly, to discuss the safety and health program on site and to make suggestions for improvement. The meetings should be documented with a time bound action plan. The functions carried out by safety committee should include:

- i) Review compliance of pending items of last Safety meetings.
- ii) Consideration of the reports of safety personnel.
- iii) Discussion of accident/near-miss and illness reports in order to make appropriate recommendation for prevention.

- | | |
|---|--|
| <ul style="list-style-type: none"> iv) Examination/evaluation of suggestions made by workers. v) Dissemination of acquired knowledge through training programs and information sharing sessions. vi) Discussion & review of Fire Prevention & Disaster Management Plan. vii) To send recommendation to Apex Body for consideration/approvals. | <ul style="list-style-type: none"> 2) OISD-GDN-192 on “Safety During Construction” 3) OISD-STD-155 Part(I&II) on “Personnel Protective Equipment” 4) Building & Other Construction workers (Regulation of Employment & Condition of Service) Act 1996 |
|---|--|

5.9.3 Safety Review Meeting by Location Head

This meeting should be headed by the Location head and attended by Owner’s Supervisor/Engineer-in-charge, owner’s safety Officer and all concerned department heads. Prime purpose of this review is to ensure that all the recommendations of various committees are being complied with and to take decisions on critical points raised. This meeting should take place at least once in every quarter. All the investigation reports/ audit findings with status of implementation of recommendations should be discussed.

5.10 SAFETY EQUIPMENT / PERSONNEL PROTECTIVE EQUIPMENT

The type of safety equipment to be used is decided based on the job requirement. Selection should be made based on OISD-GDN-192, OISD-STD-155 (Part I & II) and the job requirement. Safety equipment / Personnel Protective Equipment (PPE) shall be of approved make. Contractor shall provide necessary training to each employee regarding proper usage and upkeep of PPE including its limitation.

A register showing stock and issue of PPE should be maintained by the contractor at site and must be available for inspection.

6.0 REFERENCES

- 1) OISD-GDN-206 on “Safety Management System”

ANNEXURE I**LIST OF SAFETY CODES FOR CIVIL WORKS PUBLISHED BY BUREAU OF
INDIAN STANDARDS**

Sl.no.	Code No.	Title
1	IS: 818	Code of Practice for Safety and Health Requirements in Electric and Gas Welding and Cutting Operations – First Revision.
2	IS: 875	Code of practice for Structural safety of buildings: Masonry walls
3	IS: 933	Specification for Portable Chemical Fire Extinguisher, Foam Type – Second Revision.
4	IS: 1179	Specification for Equipment for Eye and Face Protection during Welding – First Revision
5	IS: 1904	Code of practice for Structural safety of buildings: Shallow foundations
6	IS: 1905	Code of practice for Structural safety of buildings: Masonry walls
7	IS: 1989 – Part II	Leather Safety Boots and shoes for heavy metal industry
8	IS: 2171	Specification for Portable Fire Extinguishers, Dry Powder Type – Second Revision
9	IS: 2361	Specification of Building Grips – First Revision
10	IS: 2750	Specification for Steel Scaffoldings
11	IS: 2925	Specification for Industrial Safety Helmets – First Revision
12	IS: 3016	Code of Practice for Fires Precautions in Welding and Cutting Operations – First Revision
13	IS: 3521	Industrial Safety Belts and harnesses
14	IS: 3696 – Part I	Safety Code for Scaffolds and Ladders: Part I – Scaffolds
15	IS: 3696 – Part II	Safety Code for Scaffolds and Ladders: Part II – Ladders
16	IS: 3764	Safety Code for Excavation Work
17	IS: 4014 – Part I & II	Code of Practice for Steel Tubular Scaffolding
18	IS: 4081	Safety Code for Blasting and Related Drilling Operations
19	IS: 4082	Recommendations on stacking and storage of construction materials at site
20	IS: 4130	Safety Code for Demolition of Buildings – First Revision
21	IS: 4138	Safety Code for working in compressed air – First Revision

22	IS: 4756	Safety Code for Tunneling works
23	IS: 4912	Safety requirements for Floor and Wall openings, Railings and toe boards – First Revision
24	IS: 5216 – Part I & II	Recommendations on safety procedures and practices in electrical work
25	IS: 5121	Safety code for piling and other deep foundations
26	IS: 5916	Safety Code for Construction involving use of Hot Bituminous materials
27	IS: 6994 – Part I	Specifications for safety gloves: Part I – Leather and Cotton gloves
28	IS: 5983	Specification for Eye Protectors – First Revision
29	IS: 6922	Criteria for safety and design of structures subject to underground blasts
30	IS: 7155	Code of recommended practices for conveyor safety
31	IS: 7205	Safety Code for Erection on Structural Steel Works
32	IS: 7069	Safety Code for Handling and Storage of Building Materials
33	IS: 7293	Safety Code for Working with Construction Machinery
34	IS: 7323	Guidelines for operation of Reservoirs
35	IS: 7969	Safety Code for handling and storage of building materials
36	IS: 8758	Recommendation for Fire Precautionary Measures in construction of Temporary Structures and Pandals
37	IS: 8989	Safety Code for Erection of Concrete Framed Structures
38	IS: 9706	Code of Practices for construction of Aerial ropeways for transportation of material
39	IS: 9759	Guidelines for de-watering during construction
40	IS: 9944	Recommendations on safe working load for natural and manmade fibre rope slings
41	IS: 10667	Guide for selection of industrial safety equipment for protection foot and leg
42	IS: 10291	Safety Code for dress divers in civil engineering works
43	IS: 10386 – Part I	Safety Code for Construction, Operation and Maintenance for River Valley Projects
44	IS: 10386 – Part II	Safety Code for Construction, Operation and Maintenance for

River Valley Projects

45	IS: 11057	Code of Practice for Industrial Safety Nets
46	IS: 13415	Code of Practice on safety for Protective barriers in and around building
47	IS: 13416	Recommendations for preventive measures against hazards at working places

Statutory Regulations

Latest Statutory Acts and Rules, as given below, may be referred:-

1. The Petroleum Acts 1934 and Petroleum Rules 2002
2. The Factory Act, 1948 (As amended by Factory Amendment Act 1987) and concerned Factory Rules
3. The Water (Prevention and Control of Pollution) Act 1974 & Rules 1975
4. The Environment (Protection) Act 1986
5. The Manufacturing, Storage and Import of Hazardous Rules 1989
6. The Hazardous Wastes Management (Management & Handling) Rules 1989
7. The Indian Electricity Act 1901 and Rules 1956
8. The Indian Explosive Acts, 1884 & The Indian Explosive Rules 1983
9. The Gas Cylinder Rules 1981 and the static & Mobile Pressure Vessels (Unfired) Rules 1981
10. The Indian Boiler Act 1923 and Regulations 1950
11. The Public Liability Act 1991 as amended in 1992
12. The Motor Vehicle act 1988 and Central Motor Vehicle rules 1989
13. Building & Other Construction workers (Regulation of Employment & Condition of Service) Act 1996

In addition to above, various other statutory acts like EPF, ESIS, Minimum wage act and other local statutory requirements shall also be complied with.

CHECK LIST FOR SAFETY INSPECTION / AUDIT

Job _____ Location _____ Date of Audit _____ Frequency _____

Inspected by _____ Contractor (s) _____

Sl.no.	ITEM	YES	NO	NA	REMARKS / ACTION
1.0	PERSONNEL PROTECTIVE EQUIPMENT (PPE): Are following PPEs being used as per the job requirements?				
1.1	Safety Helmets				
1.2	Safety Shoes				
1.3	Gum Boots				
1.4	Safety Belts with life line				
1.5	Gloves				
1.6	Ear Plug				
1.7	Goggles				
1.8	Shield Glass				
1.9	Face Protection				
1.10	Breathing Apparatus				
1.11	Canister Mask				
1.12	Hand wash / Eye wash/ Respirating filter / cloth				
1.13	Boiler Suit				
1.14	Others				
2.0	HOUSE KEEPING				
2.1	Whether Waste Bins are provided / used				
2.2	Are Passageways / Walkways clear?				
2.3	Is General neatness O.K.?				
2.4	Is the Ground free from oil, grease etc. and is not found to be slippery?				
2.5	Others				

3.0	EXCAVATION				
3.1	Whether soil stability is checked?				
3.2	Whether proper shoring for the excavation is provided to prevent cave-in for side of slope >45 Degree?				
3.3	Whether proper precautions have been taken if the excavation is adjoining to heavy structure like building, street and roadways?				
3.4	While excavating whether proper slope usually 45° & suitable benches of 0.5 m width at each 1.5 m depth are provided?				
3.5	Whether barricading of 1m height with glowing caution board is provided for excavation beyond 1.5m depth?				
3.6	Whether excavating earth is placed beyond 1m of the edge of the trench?				
3.7	Whether heavy vehicle movement is restricted to come too close to the excavating area?				
3.8	Whether necessary precaution is taken for underground pipes, sewers, cables by contractors?				
3.9	Whether excavation hot work permit is taken?				
3.10	Whether extra precaution is taken for bailing out water properly while excavating?				
3.11	During rains whether the excavation is done with extra precaution to prevent caving in?				
3.12	Whether two separate entry/ exit points with necessary ladders / steps, as per requirement, have been provided?				
3.13	Whether one person is available at all the time to communicate any hazards noticed with workers working in deep trenches or excavation?				
3.14	Whether necessary precautions like				

	regular gas testing are being taken in areas having hydrocarbons and LPG so that no gas accumulation takes place in the trenches.				
3.15	Whether IS: 4081-1986 & Indian Explosive act & rules for storage, handling & carrying of explosive material and execution of blasting operation is followed?				
3.16	Whether in case of mechanised excavation, caution board is provided for do's and don'ts like 'Nobody to enter' within one meter of the extreme reach?				
3.17	Whether the following are inspected during excavation work :- a) Boulder formation encountered b) Collapsing / development of cracks of sides c) Marked damage to support d) Unexpected fall of ground e) Inspection of site after each blast.				
3.18	Others				
4.0	PERMITS				
4.1	Whether valid work permit is issued to start any work?				
4.2	Whether all conditions of the permit are fulfilled before starting the job?				
4.3	As noted in the permit, whether compliance of all the recommendations are ensured?				
4.4	Whether permits are available at work site all the times?				
4.5	Whether hot work permit registered in fire station?				
4.6	Whether permits are being closed after the completion of job?				
4.7	Others				
5.0	SAFETY IN CUTTING / WELDING/GRINDING				
5.1	Whether LPG / Oxygen / Acetylene/ Gas				

	cylinders are kept outside only while working in confined space?				
5.2	Are Acetylene /LPG cylinders kept in upright position and secured at designated places under shed – wet gunny bags wrapped around it if the same is under sun at designated place?				
5.3	Check cylinder and cylinder valves for any kind of damage?				
5.4	Whether protective valves are kept on cylinder while not in use?				
5.5	Whether proper means and method for transportation of cylinders to avoid dropping and rolling are being adopted / followed?				
5.6	Whether gas cylinders, regulators are kept away/free from oil and grease?				
5.7	Whether all hoses were found to be free of any damage or crack?				
5.8	Whether oxygen and acetylene cylinders are stored separately?				
5.9	Whether color coding is being used for easy identification of different type of cylinders and hoses?				
5.10	Whether cylinder keys are available near the cylinder?				
5.11	Whether gas torches with NRV with flash back arrestor of approved make are only being used?				
5.12	Whether pressure gauges are in working condition and checked from time to time?				
5.13	Whether welding shields are used while welding?				
5.14	Whether proper earthing for welding machines are provided?				
5.15	Whether power is taken from approved sources (welding receptacles)?				
5.16	Whether welding receptacles are properly grounded?				

5.17	Whether welding cables are maintained in good condition and without any joints/cuts?				
5.18	Whether to avoid short circuit, welding machines are protected against rain?				
5.19	Whether earth connectors are securely connected to the job and not to the adjoining pipeline or structure?				
5.20	Whether flame arrestor of DG set is of approved make and quality?				
5.21	Others				
6.0	SAND / SHOT BLASTING				
6.1	Whether sand blasting is used only after getting approval from competent authority?				
6.2	Whether air compressor used for sand / shot blasting are positioned away from work place?				
6.3	Whether exhaust of the prime mover is directed away from the work place?				
6.4	Whether in case of motor driven compressor, the body of the motor as well as the compressor is properly earthed?				
6.5	Whether line operator of sand/shot blasting wear suitable PPEs including mask?				
6.6	Whether adequate measures are adopted to confine dust/spray particles?				
6.7	Whether adequate measures are taken for proper ventilation while the work is done in confined space?				
6.8	Others				
7.0	SAFETY WHILE WORKING AT HEIGHTS / SCAFFOLDING / LADDERS				
7.1	Whether work permit is obtained to take up work at height above 3 mts?				
7.2	Whether steel pipes scaffoldings are used in unit/off site areas?				

7.3	Whether provision for suitable platform with all scaffoldings are made? Whether its construction is as per specification with toe board and railing?				
7.4	Whether the area below working at height is cordoned?				
7.5	Whether suitable platform is provided?				
7.6	Whether ISI approved quality and good condition safety belts are used while working at heights?				
7.7	Whether life line of safety belt is Anchored to an independent secured support capable of withstanding load of a falling person?				
7.8	Whether the area around the scaffold is cordoned off to prohibit the entry of unauthorized person?				
7.9	Whether ropes used are of good condition and adequate strength free of defects?				
7.10	Whether ladder is placed at secured and leveled surface?				
7.11	Whether it is extended 1.5 Mts. Above the landing point?				
7.12	Whether ladder used are of adequate length and tying short ladder is avoided?				
7.13	Whether metallic ladders are placed away from electrical system?				
7.14	Whether tools or materials are removed after completion of the day's job at heights?				
7.15	Whether a valid permit is obtained before taking up work on asbestos or fragile roof?				
7.16	Whether sufficient precaution is taken while working on fragile roof?				
7.17	Whether provision is made to arrange duck ladder, crawling board for working at fragile roof?				
7.18	Whether scaffolding has been erected on rigid / firm / levelled surfaces only?				

7.19	Whether scaffold has been inspected by competent person prior to being put in use?				
7.20	Whether the scaffolding has been designed for the load to be borne?				
7.21	Whether the erection and dismantling of the scaffolding is being done only by trained persons and under supervision?				
7.22	Whether safety net with proper working arrangement and life line has been provided?				
7.23	Others				
8.0	SAFETY IN CONFINED SPACE				
8.1	Whether a permit is obtained to enter a confined space?				
8.2	Whether gas test for hydrocarbon, toxic gas, oxygen level is obtained before entering any confined space?				
8.3	Whether adequate oxygen level is ensured in confined space before entering? If not, whether all precaution like using of Breathing Apparatus set is ensured?				
8.4	Whether, in case of chance of ingress of hydrocarbon gases / toxic gases, Personnel Monitoring System (PMS) is used or not?				
8.5	Whether only in presence of a supervisor, worker enters in confined space?				
8.6	Whether provision of sufficient means of entry and exit is available?				
8.7	Whether provision of ventilation to remove welding fumes, dust, exhaust gases are made?				
8.8	Whether provision of 24V (Hand lamps with cage as per OISD-STD-155) light for working inside space is made?				

8.9	Is it strictly ensured that a stand-by trained person is standing outside before a person enters a confined space and communication is being maintained all the time with workers working inside?				
8.10	Whether life belt with one end under control of stand-by person outside is kept while working in confined space?				
8.11	Whether Personnel protective Equipment are in good condition as specified in the permit?				
8.12	Whether absence of Hydrogen Sulfide, CO or other toxic gas is ensured before entering into a confined space? If yes, whether proper required PPE like BA, Gas Mask are used.				
8.13	Whether boxing up is being done only as per the approved procedures and by competent persons?				
8.14	Whether all the safety precautions listed in OISD-GDN-192 are taken while working in sewers, OWS etc.?				
8.15	Whether proper house keeping is being maintained inside the confined space?				
8.16	Whether training has been provided to workers working in the confined space and the workers only of sound health are being asked to work in the confined space?				
8.17	Others				
9.0	SAFETY IN MATERIAL HANDLING				
9.1	Whether all lifting tools, tackles, machines, chains, ropes etc. are of sound construction, made of sound material and maintained in good condition?				
9.2	Whether safe working load, date of testing visibly marked/painted on the equipment?				
9.3	Whether lifting tools, tackles are of adequate strength for the load to be handled?				
9.4	Whether all parts including the working gears fixed or movable of every lifting machine, chain, rope, tackles specify the				

	following condition: a) Thoroughly examined by competent person at least once a year or such interval as required by statutory authority. b) Document of such examination are maintained and produced to owner supervisor before use of particular equipment?				
9.5	Whether chain blocks and cables are inspected before each use to assure their sound condition?				
9.6	Whether hoist and lift if used are: a) Properly maintained and thoroughly examined by competent authority at least once in every year. b) A register to be maintained to record particulars of such examination in prescribed forms and shall be produced to the owner supervisor before use.				
9.7	Whether area below the movement of boom of crane is cleared to avoid injury from falling objects?				
9.8	Whether it is ensured that crew of truck leave the truck in crane handling area before starting loading / unloading, if not involved in rigging operation?				
9.9	Whether transporting material from one place to another is done by suitable means?				
9.10	Whether carrier with sufficient capacity without projecting parts is used for transporting materials?				
9.11	Whether riggers engaged are well trained and conversant with signaling procedures including night signalling if required?				
9.12	Whether permission of authorized person is obtained before working on or near an overhead crane?				
9.13	Whether trained riggers are available all the time along with crane?				

9.14	Whether barricading has been done to ensure no unauthorised person enters in the working area of the crane?				
9.15	Whether lifting plan has been prepared and approved before start of the work?				
9.16	Whether route of crane movement has been planned before the crane moves out of the garage?				
9.17	Whether it has been ensured that no electrical cable come within 3 metres or safe distance from the boom of the crane?				
9.18	Whether boom is being kept in the horizontal position or locked while idling?				
9.19	Whether material is being stacked / destacked in trucks with the help of wedges to ensure no slippage while loading / unloading takes place?				
9.20	Whether the forklift / crane is being operated only by trained person?				
9.21	Others				
10.0	ELECTRICAL SAFETY				
10.1	Has the Electrical Line Clearance procedure been followed involving electrical and other concerned Dept. and filling of formats?				
10.2	Have Danger Signs with Voltage rating/ Men at work signboards been displayed at both Sub Station as well as the work site?				
10.3	Has the contractor worker understood the electrical circuit on which he is going to work with probable electrical hazards and mitigation measures to be adopted?				
10.4	Whether contractor has engaged electrician (s) having valid electrical licence in line with provisions in Indian Electricity Rules?				

10.5	Have all checks prior to switching operation been carried out and authorisation of owner/ user section obtained subsequently?				
10.6	Have all earthing links on electrical conductors removed before charging the line/ apparatus?				
10.7	Have PPE as prescribed under Indian Electricity Rules been in place, kept healthy and used?				
10.8	Are earthing and bonding arrangement of non-current carrying metallic parts in line with provisions of Indian Electricity Rules – 1956 amended time to time as IS: 3043?				
10.9	Have electrical part of OISD-GDN-192 and Clause No. 9.0 for Temporary installations in OISD-173 been understood and followed wherever applicable?				
10.10	Are flexible wires having voltage of 240 volts above earth potential taken through PVC conduits?				
10.11	Whether portable hand lamps with a voltage rating of not more than 24 volts used with flameproof enclosures in confined spaces within columns, vessels etc?				
10.12	Have the Switches, MCBs, fuses etc. been inspected for proper ratings?				
10.13	Has Earth Leakage Circuit Breaker (ELCB) been used on the incoming side to protect against leakage of current? Is the device tested every time the work is started?				
10.14	Whether all portable appliances are provided with insulated Three pin Plugs and socket arrangement?				
10.15	Whether industrial type extension boards and plug sockets are used?				
10.16	Has the electrical equipment brought to site by contractor been inspected by owner's supervisor/ safety officer for damage/cuts/abrasion etc? Is record of				

	Insulation Resistance, wherever required , being kept?				
10.17	Have standard practices for termination of conductors/ cables been followed (e.g. use of proper lugs, crimping tool, cable glands etc)? Is cable armour in continuity from feeding point to load?				
10.18	Are the Contractor supervisor and workmen well acquainted with first aid for electrical shock?				
10.19	Are the wires/ cables identifiable along their route towards the load by using colour coding and/or markers?				
10.20	Others				
11.0	ROAD WORK				
11.1	Whether site is barricaded and provided with warning signs including night warning lamps/ self glowing markers at appropriate location for diversion of traffic?				
11.2	Whether mixing aggregates with bitumen is done with the help of batch mixing plants? If no, whether adequate precautions have been taken?				
11.3	Whether road rollers, bitumen sprayers, pavement finishers are driven by experienced drivers with valid driving licenses?				
11.4	Whether the worker handling hot bitumen sprayers or spreading bitumen aggregate mix or mixing bitumen with aggregate are provided with PVC hand gloves rubber shoes with pegging upto knee joints?				
11.5	Others				
12.0	FORM WORK, REINFORCEMENT				
12.1	Whether form work, shuttering, shoring etc. are adequately designed and provided to erect the structure and to support the expected load?				

12.2	Whether staging (support) for shuttering is designed for loads like worker movement, impact load and other incidental loads during construction?				
12.3	Whether workers use PPEs at work site?				
12.4	Whether all safety procedures are adopted while cutting rod?				
12.5	Whether proper staging and bundling is provided for supplying rods at height?				
12.6	Whether sufficient cross bracings are provided for high staging works at vulnerable points?				
12.7	Others				
13.0	CONCRETING				
13.1	Whether the concreting area is barricaded?				
13.2	Whether vibrator hoses, pumping concrete accessories are in healthy condition and mechanically strong?				
13.3	Whether it is ensured that no pipe line in concrete pumping system is attached to any temporary strut such as scaffolds etc.?				
13.4	Whether it is checked that safety guards around moving parts are provided in concrete mixer/ machines?				
13.5	Whether earthing of electrical mixers, vibrator etc. are checked?				
13.6	Whether entry of unauthorised person in the concreting area is restricted?				
13.7	Whether adequate lighting arrangement is made in the concreting area if working during night?				
13.8	Whether PPEs like gum boots, gloves and dust masks etc. are being used?				
13.9	For overhead or underground work, whether form work and shuttering have been checked so that the same do not collapse during concreting?				

13.10	Others				
14.0	DEMOLISHING (DEMOLISHING BY BLAST NOT CONSIDERED)				
14.1	Has the stability of structure been examined by competent person and found OK?				
14.2	Are non-sparking tools being used, if required?				
14.3	Is intermittent clearing operation being done to keep the area reasonably tidy and clean?				
14.4	Whether effective barricading has been provided?				
14.5	Whether Electrical and other facilities like water, oil, gas pipelines have been isolated/protected?				
14.6	Whether the plan of demolition (including sequence of activities) has been prepared and approved prior to start of the work?				
14.7	Others				
15.0	RADIOGRAPHY				
15.1	Are safety precautions for handling of source as per guidelines of BARC being followed?				
15.2	Is the potency of the source being used within acceptable limits as per the BARC regulations?				
15.3	Is the area being cordoned with proper signs during radiography?				
15.4	Does proper place exist as per BARC regulations for storage of source / Personnel safety equipment?				
15.5	Does the radiographer has valid certificate of radiography from competent authority (BARC)?				
15.6	Is radiographer using Exposure Meter / Dosi Meter?				
15.7	Whether minimum occupancy of the				

	premises / workplace is being ensured while radiography is in progress?				
15.8	Is permit system being followed?				
15.9	Others				
16.0	ADDITIONAL SAFETY PRECAUTION FOR UNITS WITH HYDROCARBONS				
16.1	Are jobs being carried out with a valid work permit only as per OISD-STD-105 "Work Permit System".				
16.2	Is smoking prohibited in all places containing combustible or flammable materials and "No Smoking" notices prominently displayed.				
16.3	Are only approved type electrical installations and equipment, including portable lamps, being used?				
16.4	Are oily rags, waste, wooden materials and clothes or other substances liable to spontaneous ignition being removed?				
16.5	Are the combustible materials properly shielded in case same cannot be removed from the area?				
16.6	Has welding screens (like metal/asbestos/ water curtain) been put up to protect other equipment / facilities/ OWS/ drains in adjoining areas against flying sparks, as may be required?				
16.7	Is Gas-testing being done with the means of a calibrated Gas detection Meter prior to start of Hot work and being done subsequently at regular intervals as per the requirement?				
16.8	Are regular inspections being done of places where there are fire risks like in the vicinity of heating appliances, electrical installations and conductors, stores of flammable and combustible materials, welding and cutting operations?				
16.9	Are fire-extinguishing equipment being placed at strategic locations and are kept well maintained and inspected at suitable intervals by a competent person.				
16.10	Are access to fire-extinguishing equipment such as hydrants, portable				

	extinguishers and connections for hoses kept clear at all times?				
16.11	Are all supervisors and a sufficient number of workers trained in the use of fire-extinguishing equipment?				
16.12	Are audio means, to give warning in case of fire provided, audible in all parts of the site where persons are liable to work?				
16.13	Is there an effective evacuation plan in place so that all persons are evacuated speedily without panic?				
16.14	Others				
17.0	EMERGENCY PROCEDURES				
17.1	Is signaling / siren system effective?				
17.2	Is arrangement for rescuing affected person adequate?				
17.3	Are signs showing emergency exit route installed?				
17.4	Is emergency exit route clear of obstacles?				
17.5	Is communication system adequate?				
17.6	Whether emergency vehicle with driver has been provided to meet any emergency situation?				
17.7	Does any tie-up with hospitals or local doctors exist?				
17.8	Has the assembly point for workers in case of emergency been identified and earmarked?				
17.9	Has training been provided to a few workers for First Aid?				
17.10	Others				
18.0	WELFARE FACILITIES				
18.1	Is hygienic conditions prevailing at labour camps?				
18.2	Are First Aid facilities available?				

18.3	Does proper sanitation exist at site office and labour camps?				
18.4	Does any arrangement of medical facilities like tie ups with nearby hospital exist?				
18.5	Is proper drinking water facility available for workmen & staff?				
18.6	Are crèches provided for children (if applicable)?				
18.7	Is any proper place/canteen/restroom provided for eating food and taking rest?				
18.8	Is any place earmarked for storing / keeping clothing?				
18.9	Is Adequate washing facility available?				
18.10	Does proper ventilation at working place exist?				
18.11	Others				
19.0	GENERAL				
19.1	Are illumination levels at workplace and passages adequate?				
19.2	Is communication system adequate?				
19.3	Are display and caution boards provided at strategic locations?				
19.4	Are road barriers being used for blocking any roads/passage?				
19.5	Has the structure been adequately secured against storm/high winds during construction/ erection?				
19.6	Are the equipment properly earthed?				
19.7	Are vehicles being checked like brakes, oil, lights etc. on regular basis?				
19.8	Is compressed air being used only for its intended purpose and not for any other purpose?				
19.9	Are only proper clothes and not loose clothes being used while working around				

	machinery?				
19.10	Are nails or other sharp objects being removed or bent?				
19.11	Are machine guards over moving parts of machinery such as coupling, pulley, wheel etc. installed?				
19.12	Whether after maintenance of machinery the guards are securely fitted before putting into operation?				
19.13	Are working platforms / gangways provided with hand rails & toe guards?				
19.14	Are swing platforms provided with chains & secured adequately when not in use?				
19.15	Are the approaches to work sites being maintained & kept clear of obstacles?				
19.16	Whether engines of equipment entering into the operating area have exhaust and muffler system with approved spark arrestor?				
19.17	Whether vehicles/engine driven equipment, electrical equipment and tools used are certified?				
19.18	Whether contractors inform his workers about hazards and safe procedures?				
19.19	Whether sufficient care is taken so that spark do not go outside working enclosure & falls below?				
19.20	Whether contractor's qualified / trained supervisor is present?				
19.21	Whether all exhausts of engines are provided with approved type of flame arrestors and exhaust is not facing toward the place where the workers are working?				
19.22	Others				

Signature of the Auditor


CONDITIONS FOR ISSUE AND RECONCILIATION OF MATERIALS

[ANNEXURE– XII TO SPECIAL CONDITIONS OF CONTRACT]

सामग्री इश्यू और रिकन्सिलेशन

हेतु शर्तें

CONDITIONS FOR ISSUE AND RECONCILIATION OF MATERIALS

0	21/05/2008	Doc. No. 6-10-0001 Rev 0 has been revised and issued as Standard	 AS	 GH	 SCB	 VC
Rev. No	Date	Purpose	Prepared by	Checked by	Standards Committee Convenor	Standards Bureau Chairman
Approved by						

Abbreviations:

MS	:	Mild Steel
OFC	:	Optical Fibre Cable
OTDR	:	Optical Time Domain Report

Construction Standards Committee

Convenor :	Sh. S.C. Barman, HOD (Construction)
Members :	Sh. A.K. Mittal, DGM (Projects) Sh. M.P. Jain, AGM (Projects) Sh. Rakesh Nanda, AGM (Piping) Sh. Amarjeet Singh, Sr. Engineer (Constn)
Invitees :	Sh. V.K. Budhiraja, DGM (C&P) Sh. G.K. Iyer, Sr. Manager (Constn)

CONTENTS

1.0	CONDITIONS FOR ISSUE OF MATERIALS	4
2.0	RETURN OF UNUSED MATERIAL/ SCRAP	4
3.0	CEMENT	5
4.0	REINFORCEMENT BARS /STRUCTURAL STEEL/PLATES.....	6
5.0	PIPING MATERIALS.....	6
6.0	EQUIPMENTS	7
7.0	CABLES	7
8.0	LINE PIPES.....	8
9.0	OPTICAL FIBRE CABLE	8
10.0	OFC JOINTING KITS.....	9

1.0 CONDITIONS FOR ISSUE OF MATERIALS

Whenever any material is issued by Owner, following conditions for issue of material in addition to other conditions specified in the contract shall be applicable:

- 1.1 Necessary indents shall be raised by the Contractor as per procedure laid down by the Engineer-in-Charge from time to time, when the materials are required for incorporation in permanent works.
- 1.2 Materials shall be issued only for permanent works and not for temporary works, enabling works etc. unless specifically approved by the Engineer-in-Charge.
- 1.3 The Contractor shall bear all other cost including lifting, carting from issue points to work site/Contractor's store, custody and handling etc. and return of surplus/serviceable scrap materials to Owner's storage points to be designated by the Engineer-in-Charge. No separate payment for such expenditure shall be made.
- 1.4 No material shall be allowed to be taken outside the plant without a gate pass.
- 1.5 The Contractor shall be responsible for proper storage, preservation and watch & ward of the materials.

2.0 RETURN OF UNUSED MATERIAL/ SCRAP

- 2.1 All unused/scrap materials shall be the property of the Owner and shall be returned in good and acceptable condition category wise by the Contractor at his own cost to Owner's Store(s).
- 2.2 No credit shall be given to the Contractor for return of scrap. The Contractor should quote the rates accordingly. Contractor shall make his own arrangements for weighing the cut offs to be returned to Owner's stores.
- 2.3 In case the Contractor fails to return unused materials/ accountable scrap, then recovery for such quantity of materials, not returned by the Contractor shall be affected at following penal rates from the Contractor's bills or from any other dues of the Contractor to the Owner:

S. No.	Material		Penal Rates
1.	(a)	Penal rate for non return of accountable scrap	Issue Rate + 25% or Landed Rate + 25% (in case issue rate are not indicated in the contract)
	(b)	Penal rate for return of serviceable materials in excess of permitted % allowances	
	(c)	Penal rate for issuance of unplanned OFC jointing kits	

2.	(a)	Penal rates for non return of Unused material and or penal rate for generating scrap in excess of permitted % allowances	Twice the Issue Rates or Twice the Landed Rates (in case Issue Rates are not indicated in the Contract)
	(b)	Penal rate for using excess amount of materials like cement than permitted % allowances	

- NOTE :** 1) Landed Rate shall be arrived from the latest Purchase Order of respective material received at site by Owner/EIL.
- 2) In case more stringent penal rates have been indicated elsewhere in the Contract (based on Project requirement), the same shall supersede the above rates.

3.0 CEMENT

- 3.1 Cement as received from cement Manufacturer/Stockists shall be issued to the Contractor. The theoretical weight of cement in each bag for issue purpose shall be considered as 50 Kg or 20 bags per MT. However, cement bags weighing upto 4% less shall be accepted by the Contractors and charged for as full bag.
- 3.2 The Contractor is required to submit the design mix for different grades of concrete, keeping in view the requirements stipulated in IS:456 and IS 10262, specifically regarding durability, slump and water cement ratio and specific gravity of materials brought to site as analyzed in the laboratories. The design shall be based upon absolute volume method and theoretical consumption of cement shall be worked out on this basis. For other than concrete items, the coefficients for consumption of cement shall be adopted as per CPWD practice.
- 3.3 The permissible variation between Cement actually used on the job and theoretical consumption worked out on the basis stipulated in above para 3.2 and as determined by Engineer-in-Charge shall be 3% (Three percent only).

If the actual consumption is more than 103% of the theoretical consumption, then recovery at the penal rates for the quantity of cement beyond the limit of 103% of theoretical consumption shall be affected as per clause 2.3 above.

- 3.4 Unused quantity of cement shall be returned by the Contractor to the Owner's stores in good condition only.
- 3.5 The Contractor shall maintain a good store for storing cement issued to him. The flooring of the storage house, the clearances of cement bags from the side walls/ floor & stack height etc. shall be as instructed by the Engineer-in-Charge.
- 3.6 The contractor shall maintain a Cement Register in prescribed format and update the entries on daily basis.
- 3.7 The cement store shall be offered for inspection and verification by the Engineer-in-Charge or his authorized representative at any time when the Engineer-in-Charge feels the need to do so.
- 3.8 Empty cement bags shall be the property of the Contractor and shall have to be disposed off by him.

4.0 REINFORCEMENT BARS /STRUCTURAL STEEL/PLATES

- 4.1 The scrap allowance for the reinforcement bars/structural steel including steel plate issued by the Owner, shall be total 3% (2.5% accountable and 0.5% unaccountable) of the actual consumption as incorporated in the works.
- 4.2 All serviceable reinforcement bars/structural steel/steel plates shall be issued in available length/shapes/sizes and no claims for extra payment on account of issue of non-standard lengths/shapes/sizes and bending etc. shall be entertained. Reinforcement bars and structural steel shall be issued on weight basis as per normal warehousing practice. In exceptional circumstances, the reinforcement bars/ structural steel, if issued on linear measurement, the IS coefficients for unit weight shall be considered. For the purpose of billing and accounting, only linear measurements shall be taken and weight shall be calculated as per IS coefficients in three decimals. The difference in unit weight as per IS and actual as issued, if any, shall be to Contractor's account and Contractor is deemed to have considered the same at the time of bidding.
- 4.3 Reinforcement bars/structural steel/steel plates shall be issued only for those items where Owner's supply has been specifically mentioned in Schedule of Rates/ Scope of Supply. The storage of these items shall be done in such a way so as to avoid rusting/ damage to any kind to the materials.
- 4.4 All reinforcement bars/structural steel (except M.S. Plates) in length of 2 meters and above shall be considered as serviceable materials provided the material is in good and acceptable condition. Reinforcement bars/structural steel section (except M.S. Plates) in lengths less than 2M shall be treated as scrap.
- The contractor shall strive to avoid generation of cut pieces of length 2m and above, as far as practicable, by effectively planning & executing the construction works.
- 4.5 For the purpose of accounting of the plates, all plates measuring not less than 1 Sq.m in area and having any dimensions not less than 200mm when returned to Owner's store, shall be considered as serviceable material. All other pieces shall be treated as wastage/scrap. The Contractor shall prepare a plate cutting diagram in such a way that the minimum scrap is generated. Also the cut plates should be used at proper places to reduce the scrap.
- 4.6 The serviceable cut pieces as mentioned in 4.4 & 4.5 above shall be considered as unused material for reconciliation purpose.
- 4.7 Material appropriation shall be done and wherever applicable, the recovery at penal rates as per clause 2.3 above shall be affected from the contractor.

5.0 PIPING MATERIALS

- 5.1 All serviceable pipes shall be issued in available lengths/shapes and no claims for extra payments on account of issue of non-standard length & shape shall be entertained. Pipes shall be issued on linear measurement basis. All valves, flanges, fittings etc. shall be issued on number(s) basis. Contractor shall store the materials in such a way so as to avoid mixing of different types of material and shall maintain complete identification and traceability at all times.
- 5.2 The scrap allowance for pipes issued by the Owner shall be 3% (2.5% accountable + 0.5% unaccountable) of the actual consumption as incorporated in the works.
- 5.3 All pipes in length of 2 meters and above shall be considered as serviceable material provided the material is in good and acceptable condition and has clear identification and traceability

(Manufacturer's name, heat number/batch number and test certificates). Pipes in lengths less than 2M shall be treated as scrap.

The contractor shall strive to avoid generation of cut pieces of length 2m and above, as far as practicable, by effectively planning & executing the construction works.

- 5.4 All unused/scrap pipes, valves, flanges, forged fittings like elbows, reducers tees shall be returned by the Contractor category wise duly cleaned, greased and spec. marked at his own cost to Owner's stores.
- 5.5 Material appropriation shall be done and wherever applicable, the recovery at penal rates as per clause 2.3 above shall be affected from the contractor.

6.0 EQUIPMENTS

Various equipment/materials intended for the installation shall be received by Owner in unpacked, skid mounted, crated, packed or loose condition and shall be stored in the warehouses and open yards. In general, materials shall be issued to the Contractor in 'as received' condition. It shall be the Contractor's responsibility to draw, load and transport all materials from Owner's designated places of issue to the point of installation and return all packing materials like steel frames, wooden boxes/scrap etc. to Owner's stores.

All materials supplied by the Owner shall be duly protected by the Contractor at his own cost with appropriate preservative like primer, lacquer coating, grease etc. as required.

7.0 CABLES

Appropriation of cables shall be done as follows:

- 7.1 All the surplus and serviceable cables out of the cables quantity(ies) issued by the Owner to the Contractor shall be returned by the Contractor to the Owner's store in good condition and as directed by the Engineer-in-Charge.
- 7.2 The Contractor shall be allowed a cutting/wastage allowance (accountable scrap) of 1.5% for power cables and 3% for the control cables. This cutting/wastage allowance shall be computed on the length of cables actually laid, measured and accepted.
- 7.3 All cables being returned to store should carry Aluminium sheet tags indicating the size & type of cable. Cables of less than 15 meters length shall be termed as scrap. Cables of lengths 15M and above shall be termed as serviceable material & shall be returned size wise and category wise to the Owner's store in wooden drums. Cables of serviceable length being returned to stores in drum(s) shall be accepted only after Megger value continuity test and physical measurement is carried out by the Contractor to the satisfaction of Engineer-in-Charge. Empty cable drums and major packing material (as decided by Engineer-in-charge) shall be Owner's property and shall be returned to Owner's Store/designated place without any additional cost.

The contractor shall strive to avoid generation of cut pieces of length 15m and above, as far as practicable, by effectively planning & executing the construction works.

- 7.4 While carrying out material appropriation with the Contractor, the above points shall be taken into account. All serviceable materials returned by the Contractor (size wise & category wise) shall be deducted from the quantity(ies) issued to the Contractor for the respective sizes. Scrap generated for power cable and control cable shall also be returned to Owner's store on Lot basis. Wherever applicable, the recovery at penal rates as per clause 2.3 above shall be affected from the contractor.

8.0 LINE PIPES

8.1 All bare/ coated line pipes as per Line Pipe specifications shall be issued on linear measurement basis. The serviceable line pipes shall be issued in available lengths and shapes and no claim for extra payment on account of issue of non-standard length and shape shall be entertained. Contractor shall store and maintain the line pipes in proper manner to avoid mixing of different classes of pipes. Contractor shall maintain complete identification and traceability at all times. All cut pieces when returned to Owner's storage points after beveling, shall be considered as serviceable material provided:

- a) Corrosion Protection Coating is intact.
- b) Pipe pieces have pipe specifications, manufacturer's logo/name and heat number duly authenticated with hard stamp of the authorized inspector as per approved procedure.

All cut pieces of pipes measuring less than 2 M shall be treated as wastage/scrap.

The contractor shall strive to avoid generation of cut pieces of length 2m and above, as far as practicable, by effectively planning & executing the construction works.

8.2 For the purpose of accounting of bare/ coated line pipes, following allowances shall be permitted:

- a) Unaccountable wastage

- upto 100 Km	0.1%
- 101 to 500 Km	0.07%
- beyond 500 Km	0.05%
- b) Scrap (All cut pieces of pipes measuring less than 2 Meter) 0.25%
- c) Serviceable materials (All cut pieces of pipe measuring 2 Meter and above) 0.5%

The percentage allowance shall be accounted on the basis of pipe book chainage for main pipeline.

8.3 Material appropriation shall be done and wherever applicable, the recovery at penal rates as per clause 2.3 above shall be affected from the contractor.

9.0 OPTICAL FIBRE CABLE

9.1 For the purpose of accounting of optical fibre cable, all cut pieces measuring in length of 40 m and above when returned to Owner's storage points shall be treated as serviceable materials. All cut pieces of cable measuring less than 40 M shall be treated as scrap.

For the purpose of accounting of OFC (Optical Fibre Cable) following allowances shall be permitted:

- a) Unaccountable wastage 0.5%
- b) Scrap (All cut pieces of cables measuring less than 40 M) 0.25%
- c) Serviceable material (measuring 40m to 750m) 0.25%

The percentage allowance shall be accounted on the basis of pipe book chainage for main pipeline.

Cables returned in original drum (measuring 750m and above) with Optical Time Domain Report (OTDR) shall be considered as unused material.

- 9.2 The contractor shall strive to avoid generation of cut pieces of length 40m and above, as far as practicable, by effectively planning & executing the construction works.
- 9.3 Material appropriation shall be done and wherever applicable, the recovery at penal rates as per clause 2.3 above shall be affected from the contractor.

10.0 OFC JOINTING KITS

The Contractor shall make a schedule for use of Cable jointing kits and get the same approved from Engineer-in-charge. The quantity mentioned in this schedule shall be termed as 'planned' usage quantity which shall be issued to the Contractor. However, any jointing based on site requirements as decided by Engineer-in-charge shall be included in planned quantity.

Any unplanned jointing required to be carried out by the Contractor due to reasons not attributable to Owner/EIL shall be issued from spare quantity, if available with Owner. Such unplanned OFC Jointing Kits shall be charged from the contractor at penal rates as per clause 2.3 above.

SUPPLY OF STEEL & CEMENT

[ANNEXURE - XIII TO SPECIAL CONDITIONS OF CONTRACT]

SUPPLY OF STEEL & CEMENT

The Contractor shall purchase Steel & Cement from the following manufacturers or their stockists.

a) **TMT Bars**

1. Steel Authority of India Limited (SAIL)
2. Rashtriya Ispat Nigam Limited (RINL)
3. Tata Iron & Steel Company (TISCO)
4. Essar Steel (Essar)
5. Jindal Steel & Power Limited (Jindal)
6. Shyam Steel Industries, Kolkata,
7. SRMB Udyog Ltd, Kolkata.
8. Usha Martin, Ranchi/Jamshedpur.,
9. Rathil Udyog Ltd, Ghaziabad.

b) **Structural Steel (including Plates)**

1. Steel Authority of India Limited (SAIL)
2. Rashtriya Ispat Nigam Limited (RINL)
3. Tata Iron & Steel Company (TISCO)
4. Essar Steel (Essar)
5. Jindal Steel & Power Limited (Jindal)

c) **Cement**

1. Associated Cement Companies Limited (ACC Cement)
2. Ultratech Cement (L&T Cement / Aditya Birla Cement / Ultratech)
3. Gujarat Ambuja Cements Limited (Gujarat Ambuja Cement)
4. Shree Cement Limited (Shree Ultra Cement/ Bangur Cement)
5. Lafarge Cement India Limited (Lafarge Cement)
6. Cement Corporation of India Limited (CCI Cement)
7. Jaypee Cement Limited (Jaypee Cement)
8. JK Lakshmi Cement Limited (JK Lakshmi Cement)
9. Madras Cement Ltd (Ramco Group)

Note:

1. Any Contractor willing to supply material from manufacturer other than listed above, shall submit the credentials of the manufacturer to RCM at project site as per company's prescribed format furnishing documentary evidence for supply, performance, test certificates etc. along with list of executed works. However, the order for supply of such item(s) shall be placed by Contractor only after approval of the same by EIL/Owner based on Project specific requirements.